

HUMAN RNASE H AND OLIGONUCLEOTIDE COMPOSITIONS THEREOF**FIELD OF THE INVENTION**

The present invention relates to a human Type 2 RNase H which has now been cloned, expressed and purified to
5 electrophoretic homogeneity. The present invention further relates to oligonucleotide compositions that may serve as substrates for human RNase H1 or human Type 2 RNase H.

BACKGROUND OF THE INVENTION

RNase H hydrolyzes RNA in RNA-DNA hybrids. This enzyme
10 was first identified in calf thymus but has subsequently been described in a variety of organisms (Stein, H. and Hausen, P., *Science*, 1969, 166, 393-395; Hausen, P. and Stein, H., *Eur. J. Biochem.*, 1970, 14, 278-283). RNase H activity appears to be ubiquitous in eukaryotes and bacteria (Itaya, M. and Kondo K.
15 *Nucleic Acids Res.*, 1991, 19, 4443-4449; Itaya et al., *Mol. Gen. Genet.*, 1991 227, 438-445; Kanaya, S., and Itaya, M., *J. Biol. Chem.*, 1992, 267, 10184-10192; Busen, W., *J. Biol. Chem.*, 1980, 255, 9434-9443; Rong, Y. W. and Carl, P. L., ,
1990, *Biochemistry* 29, 383-389; Eder et al., *Biochimie*, 1993
20 75, 123-126). Although RNase Hs constitute a family of proteins of varying molecular weight, nucleolytic activity and

substrate requirements appear to be similar for the various isotypes. For example, all RNase Hs studied to date function as endonucleases, exhibiting limited sequence specificity and requiring divalent cations (e.g., Mg^{2+} , Mn^{2+}) to produce
5 cleavage products with 5' phosphate and 3' hydroxyl termini (Crouch, R. J., and Dirksen, M. L., *Nuclease*, Linn, S. M., & Roberts, R. J., Eds., Cold Spring Harbor Laboratory Press, Plainview, NY 1982, 211-241).

In addition to playing a natural role in DNA
10 replication, RNase H has also been shown to be capable of cleaving the RNA component of certain oligonucleotide-RNA duplexes. While many mechanisms have been proposed for oligonucleotide mediated destabilization of target RNAs, the primary mechanism by which antisense oligonucleotides are
15 believed to cause a reduction in target RNA levels is through this RNase H action. Monia et al., *J. Biol. Chem.*, 1993, 266:13, 14514-14522. *In vitro* assays have demonstrated that oligonucleotides that are not substrates for RNase H can inhibit protein translation (Blake et al., *Biochemistry*, 1985,
20 24, 6139-4145) and that oligonucleotides inhibit protein translation in rabbit reticulocyte extracts that exhibit low RNase H activity. However, more efficient inhibition was found in systems that supported RNase H activity (Walder, R.Y. and Walder, J.A., *Proc. Nat'l Acad. Sci. USA*, 1988, 85, 5011-
25 5015; Gagnor et al., *Nucleic Acid Res.*, 1987, 15, 10419-10436; Cazenave et al., *Nucleic Acid Res.*, 1989, 17, 4255-4273; and Dash et al., *Proc. Nat'l Acad. Sci. USA*, 1987, 84, 7896-7900.

Oligonucleotides commonly described as "antisense oligonucleotides" comprise nucleotide sequences sufficient in
30 identity and number to effect specific hybridization with a particular nucleic acid. This nucleic acid or the protein(s) it encodes is generally referred to as the "target." Oligonucleotides are generally designed to bind either directly to mRNA transcribed from, or to a selected DNA

portion of, a preselected gene target, thereby modulating the amount of protein translated from the mRNA or the amount of mRNA transcribed from the gene, respectively. Antisense oligonucleotides may be used as research tools, diagnostic
5 aids, and therapeutic agents.

"Targeting" an oligonucleotide to the associated nucleic acid, in the context of this invention, also refers to a multistep process which usually begins with the identification of the nucleic acid sequence whose function is to be
10 modulated. This may be, for example, a cellular gene (or mRNA transcribed from the gene) whose expression is associated with a particular disorder or disease state, or a foreign nucleic acid from an infectious agent. The targeting process also includes determination of a site or sites within this gene for
15 the oligonucleotide interaction to occur such that the desired effect, either detection or modulation of expression of the protein, will result.

RNase H1 from E.coli is the best-characterized member of the RNase H family. The 3-dimensional structure of E.coli
20 RNase HI has been determined by x-ray crystallography, and the key amino acids involved in binding and catalysis have been identified by site-directed mutagenesis (Nakamura et al., *Proc. Natl. Acad. Sci. USA*, 1991, 88, 11535-11539; Katayanagi et al., *Nature*, 1990, 347, 306-309; Yang et al., *Science*,
25 1990, 249, 1398-1405; Kanaya et al., *J. Biol. Chem.*, 1991, 266, 11621-11627). The enzyme has two distinct structural domains. The major domain consists of four α helices and one large β sheet composed of three antiparallel β strands. The Mg^{2+} binding site is located on the β sheet and consists of
30 three amino acids, Asp-10, Glu-48, and Gly-11 (Katayanagi et al., *Proteins: Struct., Funct., Genet.*, 1993, 17, 337-346). This structural motif of the Mg^{2+} binding site surrounded by β strands is similar to that in DNase I (Suck, D., and Oefner, C., *Nature*, 1986, 321, 620-625). The minor domain is believed
35 to constitute the predominant binding region of the enzyme and

is composed of an α helix terminating with a loop. The loop region is composed of a cluster of positively charged amino acids that are believed to bind electrostatically to the minor groove of the DNA/RNA heteroduplex substrate. Although
5 the conformation of the RNA/DNA substrate can vary, from A-form to B-form depending on the sequence composition, in general RNA/DNA heteroduplexes adopt an A-like geometry (Pardi et al., *Biochemistry*, 1981, 20, 3986-3996; Hall, K. B., and McLaughlin, L. W., *Biochemistry*, 1991, 30, 10606-10613; Lane
10 et al., *Eur. J. Biochem.*, 1993, 215, 297-306). The entire binding interaction appears to comprise a single helical turn of the substrate duplex. Recently the binding characteristics, substrate requirements, cleavage products and effects of various chemical modifications of the substrates
15 on the kinetic characteristics of E.coli RNase HI have been studied in more detail (Crooke, S.T. et al., *Biochem. J.*, 1995, 312, 599-608; Lima, W.F. and Crooke, S.T., *Biochemistry*, 1997, 36, 390-398; Lima, W.F. et al., *J. Biol. Chem.*, 1997, 272, 18191-18199; Tidd, D.M. and Worenus, H.M., *Br. J. Cancer*, 1989, 60, 343; Tidd, D.M. et al., *Anti-Cancer Drug Des.*, 1988, 3, 117.

In addition to RNase HI, a second E.coli RNase H, RNase HII has been cloned and characterized (Itaya, M., *Proc. Natl. Acad. Sci. USA*, 1990, 87, 8587-8591). It is comprised of 213
25 amino acids while RNase HI is 155 amino acids long. E. coli RNase HIM displays only 17% homology with E.coli RNase HI. An RNase H cloned from *S. typhimurium* differed from E.coli RNase HI in only 11 positions and was 155 amino acids in length (Itaya, M. and Kondo K., *Nucleic Acids Res.*, 1991, 19,
30 4443-4449; Itaya et al., *Mol. Gen. Genet.*, 1991, 227, 438-445). An enzyme cloned from *S. cerevisiae* was 30% homologous to E.coli RNase HI (Itaya, M. and Kondo K., *Nucleic Acids Res.*, 1991, 19, 4443-4449; Itaya et al., *Mol. Gen. Genet.*, 1991, 227, 438-445). Thus, to date, no enzyme cloned from a

species other than *E. coli* has displayed substantial homology to *E. coli* RNase H II.

Proteins that display RNase H activity have also been cloned and purified from a number of viruses, other bacteria
5 and yeast (Wintersberger, *U. Pharmac. Ther.*, 1990, 48, 259-280). In many cases, proteins with RNase H activity appear to be fusion proteins in which RNase H is fused to the amino or carboxy end of another enzyme, often a DNA or RNA polymerase. The RNase H domain has been consistently found
10 to be highly homologous to *E. coli* RNase HI, but because the other domains vary substantially, the molecular weights and other characteristics of the fusion proteins vary widely.

In higher eukaryotes two classes of RNase H have been defined based on differences in molecular weight, effects of
15 divalent cations, sensitivity to sulfhydryl agents and immunological cross-reactivity (Busen et al., *Eur. J. Biochem.*, 1977, 74, 203-208). RNase H Type 1 enzymes are reported to have molecular weights in the 68-90 kDa range, be activated by either Mn^{2+} or Mg^{2+} and be insensitive to
20 sulfhydryl agents. In contrast, RNase H Type 2 enzymes have been reported to have molecular weights ranging from 31-45 kDa, to require Mg^{2+} , to be highly sensitive to sulfhydryl agents and to be inhibited by Mn^{2+} (Busen, W., and Hausen, P., *Eur. J. Biochem.*, 1975, 52, 179-190; Kane, C. M.,
25 *Biochemistry*, 1988, 27, 3187-3196; Busen, W., *J. Biol. Chem.*, 1982, 257, 7106-7108.).

An enzyme with Type 2 RNase H characteristics has been purified to near homogeneity from human placenta (Frank et al., *Nucleic Acids Res.*, 1994, 22, 5247-5254). This protein
30 has a molecular weight of approximately 33 kDa and is active in a pH range of 6.5-10, with a pH optimum of 8.5-9. The enzyme requires Mg^{2+} and is inhibited by Mn^{2+} and *n*-ethyl maleimide. The products of cleavage reactions have 3' hydroxyl and 5' phosphate termini.

Despite the substantial information about members of the RNase family and the cloning of a number of viral, prokaryotic and yeast genes with RNase H activity, until now, no mammalian RNase H had been cloned. This has hampered efforts to understand the structure of the enzyme(s), their distribution and the functions they may serve.

In the present invention, a cDNA of human RNase H with Type 2 characteristics and the protein expressed thereby are provided.

10 SUMMARY OF THE INVENTION

The present invention provides oligonucleotides that can serve as substrates for human RNase H1. These oligonucleotides are mixed sequence oligonucleotides comprising at least two portions wherein a first portion is capable of supporting human RNase H1 cleavage of a complementary target RNA and a further portion which is not capable of supporting such human RNase H1 cleavage.

The present invention provides a mixed sequence oligonucleotide comprising at least 12 nucleotides and having a 3' end and a 5' end, said oligonucleotide being divided into a first portion and a further portion,

said first portion being capable of supporting cleavage of a complementary target RNA by human RNase H1 polypeptide, said further portion being incapable of supporting said RNase H cleavage;

wherein said first portion comprises at least 6 nucleotides and is positioned in said oligonucleotide such that at least one of said 6 nucleotides is 8 to 12 nucleotides from the 3' end of said oligonucleotide.

In a preferred embodiment the oligonucleotide comprises at least one CA nucleotide sequence. In another embodiment the first portion of the mixed sequence oligonucleotide of the present invention comprises nucleotides having a B-form conformational geometry. In a further embodiment each of the

nucleotides of the first portion of the oligonucleotide are 2'-deoxyribonucleotides. In a still further embodiment each of the nucleotides of the first portion of the oligonucleotide is a 2'-F arabinonucleotide or a 2'-OH arabinonucleotide. In yet another embodiment the nucleotides of the first portion are joined together in a continuous sequence by phosphate, phosphorothioate, phosphorodithioate or boranophosphate linkages. In yet a further embodiment all of the nucleotides of the further portion of the oligonucleotide are joined together in a continuous sequence by 3'-5' phosphodiester, 2'-5' phosphodiester, phosphorothioate, Sp phosphorothioate, Rp phosphorothioate, phosphorodithioate, 3'-deoxy-3'-amino phosphoroamidate, 3'-methylenephosphonate, methylene(methylimino), dimethylhydrazino, amide 3, amide 4 or boranophosphate linkages.

Yet another object of the present invention is to provide methods for identifying agents which modulate activity and/or levels of human RNase H1. In accordance with this aspect, the polynucleotides and polypeptides of the present invention are useful for research, biological and clinical purposes. For example, the polynucleotides and polypeptides are useful in defining the interaction of human RNase H1 and antisense oligonucleotides and identifying means for enhancing this interaction so that antisense oligonucleotides are more effective at inhibiting their target mRNA.

Yet another object of the present invention is to provide a method of prognosticating efficacy of antisense therapy of a selected disease which comprises measuring the level or activity of human RNase H in a target cell of the antisense therapy. Similarly, oligonucleotides can be screened to identify those oligonucleotides which are effective antisense agents by measuring binding of the oligonucleotide to the human RNase H1.

BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 shows the effects of conditions on human RNase H1 activity.

Figure 2 shows a denaturing polyacrylamide gel analysis
5 of human RNase H1 cleavage of a 17-mer RNA-DNA gapmer duplex.

Figure 3 shows analysis of human RNase H1 cleavage of a 25-mer Ras RNA hybridized with phosphodiester oligodeoxynucleotides of different lengths.

Figure 4 shows analysis of human RNase H1 cleavage of
10 RNA-DNA duplexes with different sequences, length and 3' or 5' overhangs.

Figure 5 shows product and processivity analysis of human RNase H1 cleavage on 17-mer Ras RNA-DNA duplexes.

Figure 6 provides the human Type 2 RNase H primary
15 sequence (286 amino acids; SEQ ID NO: 1) and sequence comparisons with chicken (293 amino acids; SEQ ID NO: 2), yeast (348 amino acids; SEQ ID NO: 3) and E. coli RNase H1 (155 amino acids; SEQ ID NO: 4) as well as an EST deduced mouse RNase H homolog (GenBank accession no. AA389926 and
20 AA518920; SEQ ID NO: 5). Boldface type indicates amino acid residues identical to human. "@" indicates the conserved amino acid residues implicated in E. coli RNase H1 Mg^{2+} binding site and catalytic center (Asp-10, Gly-11, Glu-48 and Asp-70). "*" indicates the conserved residues implicated in E. coli RNases
25 H1 for substrate binding.

DETAILED DESCRIPTION OF PREFERRED EMBODIMENTS

A Type 2 human RNase H has now been cloned and expressed. The enzyme encoded by this cDNA is inactive against single-stranded RNA, single-stranded DNA and double-
30 stranded DNA. However, this enzyme cleaves the RNA in an RNA/DNA duplex and cleaves the RNA in a duplex comprised of RNA and a chimeric oligonucleotide with 2' methoxy flanks and a 5-deoxynucleotide center gap. The rate of cleavage of the RNA duplexed with this so-called "deoxy gapmer" was

significantly slower than observed with the full RNA/DNA duplex. These properties are consistent with those reported for E.coli RNase H1 (Crooke et al., *Biochem. J.*, 1995, 312, 599-608; Lima, W. F. and Crooke, S. T., *Biochemistry*, 1997, 36, 390-398). They are also consistent with the properties of a human Type 2 RNase H protein purified from placenta, as the molecular weight (32 kDa) is similar to that reported by Frank et al., *Nucleic Acids Res.*, 1994, 22, 5247-5254) and the enzyme is inhibited by Mn^{2+} .

10 Thus, in accordance with one aspect of the present invention, there are provided isolated polynucleotides which encode human Type 2 RNase H polypeptides having the deduced amino acid sequence of Figure 1. By "polynucleotides" it is meant to include any form of RNA or DNA such as mRNA or cDNA
15 or genomic DNA, respectively, obtained by cloning or produced synthetically by well known chemical techniques. DNA may be double- or single-stranded. Single-stranded DNA may comprise the coding or sense strand or the non-coding or antisense strand.

20 Methods of isolating a polynucleotide of the present invention via cloning techniques are well known. For example, to obtain the cDNA contained in ATCC Deposit No. 98536, primers based on a search of the XREF database were used. An approximately 1 Kb cDNA corresponding to the carboxy terminal
25 portion of the protein was cloned by 3' RACE. Seven positive clones were isolated by screening a liver cDNA library with this 1 Kb cDNA. The two longest clones were 1698 and 1168 base pairs. They share the same 5' untranslated region and protein coding sequence but differ in the length of the 3'
30 UTR. A single reading frame encoding a 286 amino acid protein (calculated mass: 32029.04 Da) was identified (Figure 1). The proposed initiation codon is in agreement with the mammalian translation initiation consensus sequence described by Kozak, M., *J. Cell Biol.*, 1989, 108, 229-241, and is preceded by an
35 in-frame stop codon. Efforts to clone cDNA's with longer 5'

UTR's from both human liver and lymphocyte cDNA's by 5' RACE failed, indicating that the 1698-base-pair clone was full length.

In a preferred embodiment, the polynucleotide of the present invention comprises the nucleic acid sequence of the cDNA contained within ATCC Deposit No. 98536. The deposit of E. coli DH5 α containing a BLUESCRIPT[®] plasmid containing a human Type 2 RNase H cDNA was made with the American Type Culture Collection, 12301 Park Lawn Drive, Rockville, Maryland 20852, USA, on September 4, 1997 and assigned ATCC Deposit No. 98536. The deposited material is a culture of E. coli DH5 α containing a BLUESCRIPT[®] plasmid (Stratagene, La Jolla CA) that contains the full-length human Type 2 RNase H cDNA. The deposit has been made under the terms of the Budapest Treaty on the international recognition of the deposit of micro-organisms for the purposes of patent procedure. The culture will be released to the public, irrevocably and without restriction to the public upon issuance of this patent. The sequence of the polynucleotide contained in the deposited material and the amino acid sequence of the polypeptide encoded thereby are controlling in the event of any conflict with the sequences provided herein. However, as will be obvious to those of skill in the art upon this disclosure, due to the degeneracy of the genetic code, polynucleotides of the present invention may comprise other nucleic acid sequences encoding the polypeptide of Figure 1 and derivatives, variants or active fragments thereof.

Another aspect of the present invention relates to the polypeptides encoded by the polynucleotides of the present invention. In a preferred embodiment, a polypeptide of the present invention comprises the deduced amino acid sequence of human Type 2 RNase H provided in Figure 1 as SEQ ID NO: 1. However, by "polypeptide" it is also meant to include fragments, derivatives and analogs of SEQ ID NO: 1 which retain essentially the same biological activity and/or

function as human Type 2 RNase H. Alternatively, polypeptides of the present invention may retain their ability to bind to an antisense-RNA duplex even though they do not function as active RNase H enzymes in other capacities. In another
5 embodiment, polypeptides of the present invention may retain nuclease activity but without specificity for the RNA portion of an RNA/DNA duplex. Polypeptides of the present invention include recombinant polypeptides, isolated natural polypeptides and synthetic polypeptides, and fragments thereof
10 which retain one or more of the activities described above.

In a preferred embodiment, the polypeptide is prepared recombinantly, most preferably from the culture of *E. coli* of ATCC Deposit No. 98536. Recombinant human RNase H fused to histidine codons (his-tag; in the present embodiment six
15 histidine codons were used) expressed in *E. coli* can be conveniently purified to electrophoretic homogeneity by chromatography with Ni-NTA followed by C4 reverse phase HPLC. The purified recombinant polypeptide of SEQ ID NO: 1 is highly homologous to *E. coli* RNase H, displaying nearly 34% amino acid
20 identity with *E. coli* RNase H1. Figure 1 compares the protein sequences deduced from human RNase H cDNA (SEQ ID NO: 1) with those of chicken (SEQ ID NO: 2), yeast (SEQ ID NO: 3) and *E. coli* RNase HI (Gene Bank accession no. 1786408; SEQ ID NO: 4), as well as an EST deduced mouse RNase H homolog (Gene Bank
25 accession no. AA389926 and AA518920; SEQ ID NO: 5). The deduced amino acid sequence of human RNase H (SEQ ID NO: 1) displays strong homology with yeast (21.8% amino acid identity), chicken (59%), *E. coli* RNase HI (33.6%) and the mouse EST homolog (84.3%). They are all small proteins (<40
30 KDa) and their estimated pIs are all 8.7 and greater. Further, the amino acid residues in *E. coli* RNase HI thought to be involved in the Mg^{2+} binding site, catalytic center and substrate binding region are completely conserved in the cloned human RNase H sequence (Figure 1).

The human Type 2 RNase H of SEQ ID NO: 1 is expressed ubiquitously. Northern blot analysis demonstrated that the transcript was abundant in all tissues and cell lines except the MCR-5 line. Northern blot analysis of total RNA from 5 human cell lines and Poly A containing RNA from human tissues using the 1.7 kb full length probe or a 332-nucleotide probe that contained the 5' UTR and coding region of human RNase H cDNA revealed two strongly positive bands with approximately 1.2 and 5.5 kb in length and two less intense bands 10 approximately 1.7 and 4.0 kb in length in most cell lines and tissues. Analysis with the 332-nucleotide probe showed that the 5.5 kb band contained the 5' UTR and a portion of the coding region, which suggests that this band represents a pre-processed or partially processed transcript, or possibly an 15 alternatively spliced transcript. Intermediate sized bands may represent processing intermediates. The 1.2 kb band represents the full length transcripts. The longer transcripts may be processing intermediates or alternatively spliced transcripts.

20 RNase H is expressed in most cell lines tested; only MRC5, a breast cancer cell line, displayed very low levels of RNase H. However, a variety of other malignant cell lines including those of bladder (T24), breast (T-47D, HS578T), lung (A549), prostate (LNCap, DU145), and myeloid lineage (HL-60), 25 as well as normal endothelial cells (HUVEC), expressed RNase H. Further, all normal human tissues tested expressed RNase H. Again, larger transcripts were present as well as the 1.2 kb transcript that appears to be the mature mRNA for RNase H. Normalization based on G3PDH levels showed that expression was 30 relatively consistent in all of the tissues tested.

The Southern blot analysis of EcoRI digested human and various mammalian vertebrate and yeast genomic DNAs probed with the 1.7 kb probe shows that four EcoRI digestion products of human genomic DNA (2.4, 4.6, 6.0, 8.0 Kb) hybridized with 35 the 1.7 kb probe. The blot re-probed with a 430 nucleotide

probe corresponding to the C-terminal portion of the protein showed only one 4.6 kbp EcoRI digestion product hybridized. These data indicate that there is only one gene copy for RNase H and that the size of the gene is more than 10 kb. Both the
5 full length and the shorter probe strongly hybridized to one EcoRI digestion product of yeast genomic DNA (about 5 kb in size), indicating a high degree of conservation. These probes also hybridized to the digestion product from monkey, but none of the other tested mammalian genomic DNAs including the mouse
10 which is highly homologous to the human RNase H sequence.

A recombinant human RNase H (his-tag fusion protein) polypeptide of the present invention was expressed in E.coli and purified by Ni-NTA agarose beads followed by C4 reverse phase column chromatography. A 36 kDa protein copurified with
15 activity measured after renaturation. The presence of the his-tag was confirmed by Western blot analyses with an anti-penta-histidine antibody (Qiagen, Germany).

Renatured recombinant human RNase H displayed RNase H activity. Incubation of 10 ng purified renatured RNase H with
20 RNA/DNA substrate for 2 hours resulted in cleavage of 40% of the substrate. The enzyme also cleaved RNA in an oligonucleotide/RNA duplex in which the oligonucleotide was a gapmer with a 5-deoxynucleotide gap, but at a much slower rate than the full RNA/DNA substrate. This is consistent with
25 observations with E.coli RNase HI (Lima, W. F. and Crooke, S. T., Biochemistry, 1997, 36, 390-398). It was inactive against single-stranded RNA or double-stranded RNA substrates and was inhibited by Mn^{2+} . The molecular weight (~36kDa) and inhibition by Mn^{2+} indicate that the cloned enzyme is highly
30 homologous to E.coli RNase HI and has properties consistent with those assigned to Type 2 human RNase H.

The sites of cleavage in the RNA in the full RNA/DNA substrate and the gapmer/RNA duplexes (in which the oligonucleotide gapmer had a 5-deoxynucleotide gap) resulting
35 from the recombinant enzyme were determined. In the full

RNA/DNA duplex, the principal site of cleavage was near the middle of the substrate, with evidence of less prominent cleavage sites 3' to the primary cleavage site. The primary cleavage site for the gapmer/RNA duplex was located across the
5 nucleotide adjacent to the junction of the 2' methoxy wing and oligodeoxy nucleotide gap nearest the 3' end of the RNA. Thus, the enzyme resulted in a major cleavage site in the center of the RNA/DNA substrate and less prominent cleavages to the 3' side of the major cleavage site. The shift of its
10 major cleavage site to the nucleotide in apposition to the DNA 2' methoxy junction of the 2' methoxy wing at the 5' end of the chimeric oligonucleotide is consistent with the observations for E.coli RNase HI (Crooke et al. (1995) Biochem. J. 312, 599-608; Lima, W. F. and Crooke, S. T. (1997)
15 Biochemistry 36, 390-398). The fact that the enzyme cleaves at a single site in a 5-deoxy gap duplex indicates that the enzyme has a catalytic region of similar dimensions to that of E.coli RNase HI.

Accordingly, expression of large quantities of a
20 purified human RNase H polypeptide of the present invention is useful in characterizing the activities of a mammalian form of this enzyme. In addition, the polynucleotides and polypeptides of the present invention provide a means for identifying agents which enhance the function of antisense
25 oligonucleotides in human cells and tissues.

For example, a host cell can be genetically engineered to incorporate polynucleotides and express polypeptides of the present invention. Polynucleotides can be introduced into a host cell using any number of well known techniques such as
30 infection, transduction, transfection or transformation. The polynucleotide can be introduced alone or in conjunction with a second polynucleotide encoding a selectable marker. In a preferred embodiment, the host comprises a mammalian cell. Such host cells can then be used not only for production of
35 human Type 2 RNase H, but also to identify agents which

increase or decrease levels of expression or activity of human Type 2 RNase H in the cell. In these assays, the host cell would be exposed to an agent suspected of altering levels of expression or activity of human Type 2 RNase in the cells.

5 The level or activity of human Type 2 RNase in the cell would then be determined in the presence and absence of the agent. Assays to determine levels of protein in a cell are well known to those of skill in the art and include, but are not limited to, radioimmunoassays, competitive binding assays, Western

10 blot analysis and enzyme linked immunosorbent assays (ELISAs). Methods of determining increase activity of the enzyme, and in particular increased cleavage of an antisense-mRNA duplex can be performed in accordance with the teachings of Example 5. Agents identified as inducers of the level or activity of

15 this enzyme may be useful in enhancing the efficacy of antisense oligonucleotide therapies.

The present invention also relates to prognostic assays wherein levels of RNase in a cell type can be used in predicting the efficacy of antisense oligonucleotide therapy

20 in specific target cells. High levels of RNase in a selected cell type are expected to correlate with higher efficacy as compared to lower amounts of RNase in a selected cell type which may result in poor cleavage of the mRNA upon binding with the antisense oligonucleotide. For example, the MRC5

25 breast cancer cell line displayed very low levels of RNase H as compared to other malignant cell types. Accordingly, in this cell type it may be desired to use antisense compounds which do not depend on RNase H activity for their efficacy.

Similarly, oligonucleotides can be screened to identify

30 those which are effective antisense agents by contacting human Type 2 RNase H with an oligonucleotide and measuring binding of the oligonucleotide to the human Type 2 RNase H. Methods of determining binding of two molecules are well known in the art. For example, in one embodiment, the oligonucleotide can

35 be radiolabeled and binding of the oligonucleotide to human

Type 2 RNase H can be determined by autoradiography. Alternatively, fusion proteins of human Type 2 RNase H with glutathione-S-transferase or small peptide tags can be prepared and immobilized to a solid phase such as beads.

5 Labeled or unlabeled oligonucleotides to be screened for binding to this enzyme can then be incubated with the solid phase. Oligonucleotides which bind to the enzyme immobilized to the solid phase can then be identified either by detection of bound label or by eluting specifically the bound

10 oligonucleotide from the solid phase. Another method involves screening of oligonucleotide libraries for binding partners. Recombinant tagged or labeled human Type 2 RNase H is used to select oligonucleotides from the library which interact with the enzyme. Sequencing of the oligonucleotides leads to

15 identification of those oligonucleotides which will be more effective as antisense agents.

The oligonucleotides of the present invention are formed from a plurality of nucleotides that are joined together via internucleotide linkages. While joined together as a unit in

20 the oligonucleotide, the individual nucleotides of oligonucleotides are of several types. Each of these types contribute unique properties to the oligonucleotide. A first type of nucleotides are joined together in a continuous sequence that forms a first portion of the oligonucleotide.

25 The remaining nucleotides are of at least one further type and are located in one or more remaining portions or locations within the oligonucleotide. Thus, the oligonucleotides of the invention include a nucleotide portion that contributes one set of attributes and a further portion (or portions) that

30 contributes another set of attributes.

One attribute that is desirable is eliciting RNase H activity. To elicit RNase H activity, a portion of the oligonucleotides of the invention is selected to have B-form like conformational geometry. The nucleotides for this B-form

35 portion are selected to specifically include ribo-

pentofuranosyl and arabino-pentofuranosyl nucleotides. 2'-Deoxy-erythro-pentfuranosyl nucleotides also have B-form geometry and elicit RNase H activity. While not specifically excluded, if 2'-deoxy-erythro-pentfuranosyl nucleotides are included in the B-form portion of an oligonucleotide of the invention, such 2'-deoxy-erythro-pentfuranosyl nucleotides preferably does not constitute the totality of the nucleotides of that B-form portion of the oligonucleotide, but should be used in conjunction with ribonucleotides or an arabino nucleotides. As used herein, B-form geometry is inclusive of both C2'-endo and O4'-endo pucker, and the ribo and arabino nucleotides selected for inclusion in the oligonucleotide B-form portion are selected to be those nucleotides having C2'-endo conformation or those nucleotides having O4'-endo conformation. This is consistent with Berger, et. al., *Nucleic Acids Research*, **1998**, 26, 2473-2480, who pointed out that in considering the furanose conformations in which nucleosides and nucleotides reside, B-form consideration should also be given to a O4'-endo pucker contribution.

A-form nucleotides are nucleotides that exhibit C3'-endo pucker, also known as north, or northern, pucker. In addition to the B-form nucleotides noted above, the A-form nucleotides can be C3'-endo pucker nucleotides or can be nucleotides that are located at the 3' terminus, at the 5' terminus, or at both the 3' and the 5' terminus of the oligonucleotide. Alternatively, A-form nucleotides can exist both in a C3'-endo pucker and be located at the ends, or termini, of the oligonucleotide. In selecting nucleotides that have C3'-endo pucker or in selecting nucleotides to reside at the 3' or 5' ends of the oligonucleotide, consideration is given to binding affinity and nuclease resistance properties that such nucleotides need to impart to the resulting the oligonucleotide.

Nucleotides selected to reside at the 3' or 5' termini of oligonucleotides of the invention are selected to impart

nuclease resistance to the oligonucleotide. This nuclease resistance can also be achieved via several mechanisms, including modifications of the sugar portions of the nucleotide units of the oligonucleotides, modification of the internucleotide linkages or both modification of the sugar and the internucleotide linkage.

A particularly useful group of nucleotides for use in increasing nuclease resistance at the termini of oligonucleotides are those having 2'-O-alkylamino groups thereon. The amino groups of such nucleotides can be groups that are protonated at physiological pH. These include amines, monoalkyl substituted amines, dialkyl substituted amines and heterocyclic amines such as imidazole. Particularly useful are the lower alkyl amines including 2'-O-ethylamine and 2'-O-propylamine. Such O-alkylamines can also be included on the 3' position of the 3' terminus nucleotide. Thus the 3' terminus nucleotide could include both a 2' and a 3'-O-alkylamino substituent.

In selecting for nuclease resistance, it is important not to detract from binding affinity. Certain phosphorus based linkage have been shown to increase nuclease resistance. The above described phosphorothioate linkage increase nuclease resistance, however, it also causes loss of binding affinity. Thus, generally for use in this invention, if phosphorothioate internucleotide linkage are used, other modification will be made to nucleotide units that increase binding affinity to compensate for the decreased affinity contributed by the phosphorothioate linkages.

Other phosphorus based linkages having increase nuclease resistance that do not detract from binding affinity include 3'-methylene phosphonates and 3'-deoxy-3'-amino-phosphoroamidate linkages. A further class of linkages that contribute nuclease resistance but do not detract from binding affinity are non-phosphate in nature. Preferred among these are methylene(methylimino) linkages, dimethylhydraxino

linkages, and amine 3 and amide 4 linkages as described (Freier and Altmann, *Nucleic Acid Research*, 1997, 25, 4429-4443).

There are a number of potential items to consider when
5 designing oligonucleotides having improved binding affinities. It appears that one effective approach to constructing modified oligonucleotides with very high RNA binding affinity is the combination of two or more different types of modifications, each of which contributes favorably to various
10 factors that might be important for binding affinity.

Freier and Altmann, *Nucleic Acids Research*, (1997) 25:4429-4443, recently published a study on the influence of structural modifications of oligonucleotides on the stability of their duplexes with target RNA. In this study, the authors
15 reviewed a series of oligonucleotides containing more than 200 different modifications that had been synthesized and assessed for their hybridization affinity and T_m . Sugar modifications studied included substitutions on the 2'-position of the sugar, 3'-substitution, replacement of the 4'-oxygen, the use
20 of bicyclic sugars, and four member ring replacements. Several nucleobase modifications were also studied including substitutions at the 5, or 6 position of thymine, modifications of pyrimidine heterocycle and modifications of the purine heterocycle. Numerous backbone modifications were
25 also investigated including backbones bearing phosphorus, backbones that did not bear a phosphorus atom, and backbones that were neutral.

Four general approaches might be used to improve hybridization of oligonucleotides to RNA targets. These
30 include: preorganization of the sugars and phosphates of the oligodeoxynucleotide strand into conformations favorable for hybrid formation, improving stacking of nucleobases by the addition of polarizable groups to the heterocycle bases of the nucleotides of the oligonucleotide, increasing the number of
35 H-bonds available for A-U pairing, and neutralization of

backbone charge to facilitate removing undesirable repulsive interactions. We have found that by utilizing the first of these, preorganization of the sugars and phosphates of the oligodeoxynucleotide strand into conformations favorable for
5 hybrid formation, to be a preferred method to achieve improve binding affinity. It can further be used in combination with the other three approaches.

Sugars in DNA:RNA hybrid duplexes frequently adopt a C3' endo conformation. Thus modifications that shift the
10 conformational equilibrium of the sugar moieties in the single strand toward this conformation should preorganize the antisense strand for binding to RNA. Of the several sugar modifications that have been reported and studied in the literature, the incorporation of electronegative substituents
15 such as 2'-fluoro or 2'-alkoxy shift the sugar conformation towards the 3' endo (northern) pucker conformation. This preorganizes an oligonucleotide that incorporates such modifications to have an A-form conformational geometry. This A-form conformation results in increased binding affinity of
20 the oligonucleotide to a target RNA strand.

As used herein, the terms "substituent" and "substituent group" refers to groups that are attached to nucleosides of the invention. Substituent groups are preferably attached to selected sugar moieties but can alternatively be attached to
25 selected heterocyclic base moieties. Selected nucleosides may have substituent groups at both the heterocyclic base and the sugar moiety, however a single substituent group is preferred at a sugar 2', 3' or 5'-positions with the 2'-position being particularly preferred.


30 Substituent groups include fluoro, O-alkyl, O-alkylamino, O-alkylalkoxy, O-alkylaminoalkyl, O-alkyl imidazole, and polyethers of the formula (O-alkyl)_m, where m is 1 to about 10. Preferred among these polyethers are linear and cyclic polyethylene glycols (PEGs), and (PEG)-containing
35 groups, such as crown ethers and those which are disclosed by

Ouchi et al. (*Drug Design and Discovery* **1992**, 9, 93), Ravasio et al. (*J. Org. Chem.* **1991**, 56, 4329) and Delgado et al. (*Critical Reviews in Therapeutic Drug Carrier Systems* **1992**, 9, 249), each of which is herein incorporated by reference in its entirety. Further sugar modifications are disclosed in Cook, P.D., *Anti-Cancer Drug Design*, **1991**, 6, 585-607. Fluoro, O-alkyl, O-alkylamino, O-alkyl imidazole, O-alkylaminoalkyl, and alkyl amino substitution is described in United States Patent Application serial number 08/398,901, filed March 6, 1995, entitled Oligomeric Compounds having Pyrimidine Nucleotide(s) with 2' and 5' Substitutions, hereby incorporated by reference in its entirety.

Additional substituent groups amenable to the present invention include -SR and -NR₂ groups, wherein each R is, independently, hydrogen, a protecting group or substituted or unsubstituted alkyl, alkenyl, or alkynyl. 2'-SR nucleosides are disclosed in United States Patent No. 5,670,633, issued September 23, 1997, hereby incorporated by reference in its entirety. The incorporation of 2'-SR monomer synthons are disclosed by Hamm et al., *J. Org. Chem.*, **1997**, 62, 3415-3420. 2'-NR₂ nucleosides are disclosed by Goettingen, M., *J. Org. Chem.*, **1996**, 61, 6273-6281; and Polushin et al., *Tetrahedron Lett.*, **1996**, 37, 3227-3230.

Further representative substituent groups include hydrogen, hydroxyl, C₁-C₂₀ alkyl, C₂-C₂₀ alkenyl, C₂-C₂₀ alkynyl, halogen, amino, thiol, keto, carboxyl, nitro, nitroso, nitrile, trifluoromethyl, trifluoromethoxy, O-alkyl, O-alkenyl, O-alkynyl, S-alkyl, S-alkenyl, S-alkynyl, NH-alkyl, NH-alkenyl, NH-alkynyl, N-dialkyl, O-aryl, S-aryl, NH-aryl, O-aralkyl, S-aralkyl, NH-aralkyl, N-phthalimido, imidazole, azido, hydrazino, hydroxylamino, isocyanato, sulfoxide, sulfone, sulfide, disulfide, silyl, aryl, heterocycle, carbocycle, intercalator, reporter molecule, conjugate, polyamine, polyamide, polyalkylene glycol, or polyether;

or each substituent group has one of formula I or II:




wherein:

Z_0 is O, S or NH;

J is a single bond, O or C(=O);

5 E is C₁-C₁₀ alkyl, N(R₁)(R₂), N(R₁)(R₅), N=C(R₁)(R₂),
N=C(R₁)(R₅) or has one of formula III or IV;



each R₆, R₇, R₈, R₉ and R₁₀ is, independently, hydrogen, C(O)R₁₁, substituted or unsubstituted C₁-C₁₀ alkyl, substituted or unsubstituted C₂-C₁₀ alkenyl, substituted or unsubstituted C₂-C₁₀ alkynyl, alkylsulfonyl, arylsulfonyl, a chemical functional group or a conjugate group, wherein the substituent groups are selected from hydroxyl, amino, alkoxy, carboxy, benzyl, phenyl, nitro, thiol, thioalkoxy, halogen, alkyl, aryl, alkenyl and alkynyl;

or optionally, R₇ and R₈, together form a phthalimido moiety with the nitrogen atom to which they are attached;

or optionally, R₉ and R₁₀, together form a phthalimido moiety with the nitrogen atom to which they are attached;

20 each R₁₁ is, independently, substituted or unsubstituted
C₁-C₁₀ alkyl, trifluoromethyl, cyanoethoxy, methoxy, ethoxy,
t-butoxy, allyloxy, 9-fluorenylmethoxy, 2-(trimethylsilyl)-

ethoxy, 2,2,2-trichloroethoxy, benzyloxy, butyryl, isobutyryl, phenyl or aryl;

R_5 is T-L,

T is a bond or a linking moiety;

5 L is a chemical functional group, a conjugate group or a solid support material;

each R_1 and R_2 is, independently, H, a nitrogen protecting group, substituted or unsubstituted C_1 - C_{10} alkyl, substituted or unsubstituted C_2 - C_{10} alkenyl, substituted or
10 unsubstituted C_2 - C_{10} alkynyl, wherein said substitution is OR_3 , SR_3 , NH_3^+ , $N(R_3)(R_4)$, guanidino or acyl where said acyl is an acid amide or an ester;

or R_1 and R_2 , together, are a nitrogen protecting group or are joined in a ring structure that optionally includes an
15 additional heteroatom selected from N and O;

or R_1 , T and L, together, are a chemical functional group;

each R_3 and R_4 is, independently, H, C_1 - C_{10} alkyl, a nitrogen protecting group, or R_3 and R_4 , together, are a
20 nitrogen protecting group;

or R_3 and R_4 are joined in a ring structure that optionally includes an additional heteroatom selected from N and O;

Z_4 is OX, SX, or $N(X)_2$;

25 each X is, independently, H, C_1 - C_8 alkyl, C_1 - C_8 haloalkyl, $C(=NH)N(H)R_5$, $C(=O)N(H)R_5$ or $OC(=O)N(H)R_5$;

R_5 is H or C_1 - C_8 alkyl;

Z_1 , Z_2 and Z_3 comprise a ring system having from about 4 to about 7 carbon atoms or having from about 3 to about 6
30 carbon atoms and 1 or 2 hetero atoms wherein said hetero atoms are selected from oxygen, nitrogen and sulfur and wherein said ring system is aliphatic, unsaturated aliphatic, aromatic, or saturated or unsaturated heterocyclic;

Z_5 is alkyl or haloalkyl having 1 to about 10 carbon
35 atoms, alkenyl having 2 to about 10 carbon atoms, alkynyl

having 2 to about 10 carbon atoms, aryl having 6 to about 14 carbon atoms, $N(R_1)(R_2)OR_1$, halo, SR_1 or CN;

each q_1 is, independently, an integer from 1 to 10;

each q_2 is, independently, 0 or 1;

5 q_3 is 0 or an integer from 1 to 10;

q_4 is an integer from 1 to 10;

q_5 is from 0, 1 or 2; and

provided that when q_3 is 0, q_4 is greater than 1.

Representative substituents groups of Formula I are
10 disclosed in United States Patent Application Serial No. 09/130,973, filed August 7, 1998, entitled "Capped 2'-Oxyethoxy Oligonucleotides," hereby incorporated by reference in its entirety.

Representative cyclic substituent groups of Formula II
15 are disclosed in United States Patent Application Serial No. 09/123,108, filed July 27, 1998, entitled "RNA Targeted 2'-Modified Oligonucleotides that are Conformationally Preorganized," hereby incorporated by reference in its entirety.

20 Particularly preferred substituent groups include $O[(CH_2)_nO]_mCH_3$, $O(CH_2)_nOCH_3$, $O(CH_2)_nNH_2$, $O(CH_2)_nCH_3$, $O(CH_2)_nONH_2$, and $O(CH_2)_nON[(CH_2)_nCH_3]_2$, where n and m are from 1 to about 10.

Some preferred oligomeric compounds of the invention contain, at least one nucleoside having one of the following
25 substituent groups: C_1 to C_{10} lower alkyl, substituted lower alkyl, alkaryl, aralkyl, O-alkaryl or O-aralkyl, SH, SCH_3 , OCN, Cl, Br, CN, CF_3 , OCF_3 , $SOCH_3$, SO_2CH_3 , ONO_2 , NO_2 , N_3 , NH_2 , heterocycloalkyl, heterocycloalkaryl, aminoalkylamino, polyalkylamino, substituted silyl, an RNA cleaving group, a
30 reporter group, an intercalator, a group for improving the pharmacokinetic properties of an oligomeric compound, or a group for improving the pharmacodynamic properties of an oligomeric compound, and other substituents having similar properties. A preferred modification includes 2'-methoxy-
35 ethoxy [$2'-O-CH_2CH_2OCH_3$, also known as 2'-O-(2-methoxyethyl) or

2'-MOE] (Martin et al., *Helv. Chim. Acta*, 1995, 78, 486),
i.e., an alkoxyalkoxy group. A further preferred modification
is 2'-dimethylaminooxyethoxy, i.e., a $O(CH_2)_2ON(CH_3)_2$ group,
also known as 2'-DMAOE. Representative aminooxy substituent
5 groups are described in co-owned United States Patent
Application serial number 09/344,260, filed June 25, 1999,
entitled "Aminooxy-Functionalized Oligomers"; and a United
States Patent Application entitled "Aminooxy-Functionalized
Oligomers and Methods for Making Same," filed August 9, 1999,
10 presently identified by attorney docket number ISIS-3993,
hereby incorporated by reference in their entirety.

Other preferred modifications include 2'-methoxy (2'-O-
 CH_3), 2'-aminopropoxy (2'- $OCH_2CH_2CH_2NH_2$) and 2'-fluoro (2'-F).
Similar modifications may also be made at other positions on
15 nucleosides and oligomers, particularly the 3' position of the
sugar on the 3' terminal nucleoside or in 2'-5' linked
oligomers and the 5' position of 5' terminal nucleoside.
Oligomers may also have sugar mimetics such as cyclobutyl
moieties in place of the pentofuranosyl sugar. Representative
20 United States patents that teach the preparation of such
modified sugars structures include, but are not limited to,
U.S. Patents 4,981,957; 5,118,800; 5,319,080; 5,359,044;
5,393,878; 5,446,137; 5,466,786; 5,514,785; 5,519,134;
5,567,811; 5,576,427; 5,591,722; 5,597,909; 5,610,300;
25 5,627,053; 5,639,873; 5,646,265; 5,658,873; 5,670,633; and
5,700,920, certain of which are commonly owned, and each of
which is herein incorporated by reference, and commonly owned
United States patent application 08/468,037, filed on June 5,
1995, also herein incorporated by reference.

30 Representative guanidino substituent groups that are
shown in formula III and IV are disclosed in co-owned United
States Patent Application 09/349,040 entitled "Functionalized
Oligomers," filed July 7, 1999, hereby incorporated by
reference in its entirety.

Representative acetamido substituent groups are disclosed in a United States Patent Application entitled "2'-O-Acetamido Modified Monomers and Oligomers," filed August 19, 1999, presently identified by attorney docket number ISIS-
5 4071, hereby incorporated by reference in its entirety.

Representative dimethylaminoethyloxyethyl substituent groups are disclosed in an International Patent Application entitled "2'-O-Dimethylaminoethyloxyethyl-Modified Oligonucleotides," filed August 6, 1999, presently identified
10 by attorney docket number ISIS-4045, hereby incorporated by reference in its entirety.

Several 2'-substituents confer a 3'-endo pucker to the sugar where they are incorporated. This pucker conformation further assists in increasing the T_m of the oligonucleotide
15 with its target.

The high binding affinity resulting from 2' substitution has been partially attributed to the 2' substitution causing a C3' endo sugar pucker which in turn may give the oligomer a favorable A-form like geometry. This is a reasonable
20 hypothesis since substitution at the 2' position by a variety of electronegative groups (such as fluoro and O-alkyl chains) has been demonstrated to cause C3' endo sugar puckering (De Mesmaeker et al., *Acc. Chem. Res.*, **1995**, 28, 366-374; Lesnik et al., *Biochemistry*, **1993**, 32, 7832-7838).


25 In addition, for 2'-substituents containing an ethylene glycol motif, a gauche interaction between the oxygen atoms around the O-C-C-O torsion of the side chain may have a stabilizing effect on the duplex (Freier et al., *Nucleic Acids Research*, (1997) 25:4429-4442). Such gauche interactions have
30 been observed experimentally for a number of years (Wolfe et al., *Acc. Chem. Res.*, **1972**, 5, 102; Abe et al., *J. Am. Chem. Soc.*, **1976**, 98, 468). This gauche effect may result in a configuration of the side chain that is favorable for duplex formation. The exact nature of this stabilizing configuration

has not yet been explained. While we do not want to be bound by theory, it may be that holding the O-C-C-O torsion in a single *gauche* configuration, rather than a more random distribution seen in an alkyl side chain, provides an entropic advantage for duplex formation.

To better understand the higher RNA affinity of 2'-O-methoxyethyl substituted RNA and to examine the conformational properties of the 2'-O-methoxyethyl substituent, a self-complementary dodecamer oligonucleotide

10 2'-O-MOE r(CGCGAAUUCGCG) SEQ ID NO: 1
was synthesized, crystallized and its structure at a resolution of 1.7 Ångstrom was determined. The crystallization conditions used were 2 mM oligonucleotide, 50 mM Na Hepes pH 6.2-7.5, 10.50 mM MgCl₂, 15% PEG 400. The crystal data
15 showed: space group C2, cell constants $a=41.2$ Å, $b=34.4$ Å, $c=46.6$ Å, $\beta=92.4^\circ$. The resolution was 1.7 Å at -170°C . The current R -factor was 20% (R_{free} 26%).

This crystal structure is believed to be the first crystal structure of a fully modified RNA oligonucleotide
20 analogue. The duplex adopts an overall A-form conformation and all modified sugars display C3'-endo pucker. In most of the 2'-O-substituents, the torsion angle around the A'-B' bond, as depicted in Structure II below, of the ethylene glycol linker has a *gauche* conformation. For 2'-O-MOE, A' and
25 B' of Structure II below are methylene moieties of the ethyl portion of the MOE and R' is the methoxy portion.



In the crystal, the 2'-O-MOE RNA duplex adopts a general orientation such that the crystallographic 2-fold rotation axis does not coincide with the molecular 2-fold rotation axis. The duplex adopts the expected A-type geometry and all of the 24 2'-O-MOE substituents were visible in the electron density maps at full resolution. The electron density maps as well as the temperature factors of substituent atoms indicate flexibility of the 2'-O-MOE substituent in some cases.

Most of the 2'-O-MOE substituents display a *gauche* conformation around the C-C bond of the ethyl linker. However, in two cases, a *trans* conformation around the C-C bond is observed. The lattice interactions in the crystal include packing of duplexes against each other via their minor grooves. Therefore, for some residues, the conformation of the 2'-O-substituent is affected by contacts to an adjacent duplex. In general, variations in the conformation of the substituents (e.g. g^+ or g^- around the C-C bonds) create a range of interactions between substituents, both inter-strand, across the minor groove, and intra-strand. At one location, atoms of substituents from two residues are in van der Waals contact across the minor groove. Similarly, a close contact occurs between atoms of substituents from two adjacent intra-strand residues.

Previously determined crystal structures of A-DNA duplexes were for those that incorporated isolated 2'-O-methyl T residues. In the crystal structure noted above for the 2'-O-MOE substituents, a conserved hydration pattern has been observed for the 2'-O-MOE residues. A single water molecule is seen located between O2', O3' and the methoxy oxygen atom of the substituent, forming contacts to all three of between 2.9 and 3.4 Å. In addition, oxygen atoms of substituents are involved in several other hydrogen bonding contacts. For example, the methoxy oxygen atom of a particular 2'-O-

substituent forms a hydrogen bond to N3 of an adenosine from the opposite strand via a bridging water molecule.

In several cases a water molecule is trapped between the oxygen atoms O2', O3' and OC' of modified nucleosides. 2'-O-
5 MOE substituents with *trans* conformation around the C-C bond of the ethylene glycol linker are associated with close contacts between OC' and N2 of a guanosine from the opposite strand, and, water-mediated, between OC' and N3(G). When combined with the available thermodynamic data for duplexes
10 containing 2'-O-MOE modified strands, this crystal structure allows for further detailed structure-stability analysis of other antisense modifications.

In extending the crystallographic structure studies, molecular modeling experiments were performed to study further
15 enhanced binding affinity of oligonucleotides having 2'-O-modifications of the invention. The computer simulations were conducted on compounds of SEQ ID NO: 1, above, having 2'-O-modifications of the invention located at each of the nucleoside of the oligonucleotide. The simulations were
20 performed with the oligonucleotide in aqueous solution using the AMBER force field method (Cornell et al., *J. Am. Chem. Soc.*, **1995**, 117, 5179-5197) (modeling software package from UCSF, San Francisco, CA). The calculations were performed on an Indigo2 SGI machine (Silicon Graphics, Mountain View, CA).

25 Further 2'-O-modifications of the inventions include those having a ring structure that incorporates a two atom portion corresponding to the A' and B' atoms of Structure II. The ring structure is attached at the 2' position of a sugar moiety of one or more nucleosides that are incorporated into
30 an oligonucleotide. The 2'-oxygen of the nucleoside links to a carbon atom corresponding to the A' atom of Structure II. These ring structures can be aliphatic, unsaturated aliphatic, aromatic or heterocyclic. A further atom of the ring (corresponding to the B' atom of Structure II), bears a
35 further oxygen atom, or a sulfur or nitrogen atom. This

oxygen, sulfur or nitrogen atom is bonded to one or more hydrogen atoms, alkyl moieties, or haloalkyl moieties, or is part of a further chemical moiety such as a ureido, carbamate, amide or amidine moiety. The remainder of the ring structure
5 restricts rotation about the bond joining these two ring atoms. This assists in positioning the "further oxygen, sulfur or nitrogen atom" (part of the R position as described above) such that the further atom can be located in close proximity to the 3'-oxygen atom (O3') of the nucleoside.

10 The ring structure can be further modified with a group useful for modifying the hydrophilic and hydrophobic properties of the ring to which it is attached and thus the properties of an oligonucleotide that includes the 2'-O-modifications of the invention. Further groups can be
15 selected as groups capable of assuming a charged structure, e.g. an amine. This is particularly useful in modifying the overall charge of an oligonucleotide that includes a 2'-O-modifications of the invention. When an oligonucleotide is linked by charged phosphate groups, e.g. phosphorothioate or
20 phosphodiester linkages, location of a counter ion on the 2'-O-modification, e.g. an amine functionality, locally naturalizes the charge in the local environment of the nucleotide bearing the 2'-O-modification. Such neutralization of charge will modulate uptake, cell localization and other
25 pharmacokinetic and pharmacodynamic effects of the oligonucleotide.

Preferred ring structures of the invention for inclusion as a 2'-O modification include cyclohexyl, cyclopentyl and phenyl rings as well as heterocyclic rings having spacial
30 footprints similar to cyclohexyl, cyclopentyl and phenyl rings. Particularly preferred 2'-O-substituent groups of the invention are listed below including an abbreviation for each:

2'-O-(trans 2-methoxy cyclohexyl) -- 2'-O-(TMCHL)
35 2'-O-(trans 2-methoxy cyclopentyl) -- 2'-O-(TMCPL)

2'-O-(trans 2-ureido cyclohexyl) -- 2'-O-(TUCHL)
2'-O-(trans 2-methoxyphenyl) -- 2'-O-(2MP)

Structural details for duplexes incorporating such 2'-O-substituents were analyzed using the described AMBER force field program on the Indigo2 SGI machine. The simulated structure maintained a stable A-form geometry throughout the duration of the simulation. The presence of the 2' substitutions locked the sugars in the C3'-endo conformation.

The simulation for the TMCHL modification revealed that the 2'-O-(TMCHL) side chains have a direct interaction with water molecules solvating the duplex. The oxygen atoms in the 2'-O-(TMCHL) side chain are capable of forming a water-mediated interaction with the 3' oxygen of the phosphate backbone. The presence of the two oxygen atoms in the 2'-O-(TMCHL) side chain gives rise to favorable gauche interactions. The barrier for rotation around the O-C-C-O torsion is made even larger by this novel modification. The preferential preorganization in an A-type geometry increases the binding affinity of the 2'-O-(TMCHL) to the target RNA. The locked side chain conformation in the 2'-O-(TMCHL) group created a more favorable pocket for binding water molecules. The presence of these water molecules played a key role in holding the side chains in the preferable gauche conformation. While not wishing to be bound by theory, the bulk of the substituent, the diequatorial orientation of the substituents in the cyclohexane ring, the water of hydration and the potential for trapping of metal ions in the conformation generated will additionally contribute to improved binding affinity and nuclease resistance of oligonucleotides incorporating nucleosides having this 2'-O-modification.

As described for the TMCHL modification above, identical computer simulations of the 2'-O-(TMCPL), the 2'-O-(2MP) and 2'-O-(TUCHL) modified oligonucleotides in aqueous solution

also illustrate that stable A-form geometry will be maintained throughout the duration of the simulation. The presence of the 2' substitution will lock the sugars in the C3'-endo conformation and the side chains will have direct interaction with water molecules solvating the duplex. The oxygen atoms in the respective side chains are capable of forming a water-mediated interaction with the 3' oxygen of the phosphate backbone. The presence of the two oxygen atoms in the respective side chains give rise to the favorable gauche interactions. The barrier for rotation around the respective O-C-C-O torsions will be made even larger by respective modification. The preferential preorganization in A-type geometry will increase the binding affinity of the respective 2'-O-modified oligonucleotides to the target RNA. The locked side chain conformation in the respective modifications will create a more favorable pocket for binding water molecules. The presence of these water molecules plays a key role in holding the side chains in the preferable gauche conformation. The bulk of the substituent, the diequatorial orientation of the substituents in their respective rings, the water of hydration and the potential trapping of metal ions in the conformation generated will all contribute to improved binding affinity and nuclease resistance of oligonucleotides incorporating nucleosides having these respective 2'-O-modification.

Preferred for use as the B-form nucleotides for eliciting RNase H are ribonucleotides having 2'-deoxy-2'-S-methyl, 2'-deoxy-2'-methyl, 2'-deoxy-2'-amino, 2'-deoxy-2'-mono or dialkyl substituted amino, 2'-deoxy-2'-fluoromethyl, 2'-deoxy-2'-difluoromethyl, 2'-deoxy-2'-trifluoromethyl, 2'-deoxy-2'-methylene, 2'-deoxy-2'-fluoromethylene, 2'-deoxy-2'-difluoromethylene, 2'-deoxy-2'-ethyl, 2'-deoxy-2'-ethylene and 2'-deoxy-2'-acetylene. These nucleotides can alternately be described as 2'-SCH₃ ribonucleotide, 2'-CH₃ ribonucleotide, 2'-NH₂ ribonucleotide 2'-NH(C₁-C₂ alkyl) ribonucleotide, 2'-

$N(C_1-C_2 \text{ alkyl})_2$ ribonucleotide, 2'-CH₂F ribonucleotide, 2'-CHF₂ ribonucleotide, 2'-CF₃ ribonucleotide, 2'=CH₂ ribonucleotide, 2'=CHF ribonucleotide, 2'=CF₂ ribonucleotide, 2'-C₂H₅ ribonucleotide, 2'-CH=CH₂ ribonucleotide, 2'-C≡CH ribonucleotide. A further useful ribonucleotide is one having a ring located on the ribose ring in a cage-like structure including 3',O,4'-C-methylenetriphosphates. Such cage-like structures will physically fix the ribose ring in the desired conformation.

10 Additionally, preferred for use as the B-form nucleotides for eliciting RNase H are arabino nucleotides having 2'-deoxy-2'-cyano, 2'-deoxy-2'-fluoro, 2'-deoxy-2'-chloro, 2'-deoxy-2'-bromo, 2'-deoxy-2'-azido, 2'-methoxy and the unmodified arabino nucleotide (that includes a 2'-OH
15 projecting upwards towards the base of the nucleotide). These arabino nucleotides can alternately be described as 2'-CN arabino nucleotide, 2'-F arabino nucleotide, 2'-Cl arabino nucleotide, 2'-Br arabino nucleotide, 2'-N₃ arabino nucleotide, 2'-O-CH₃ arabino nucleotide and arabino
20 nucleotide.

Such nucleotides are linked together via phosphorothioate, phosphorodithioate, boranophosphate or phosphodiester linkages. particularly preferred is the phosphorothioate linkage.

25 Illustrative of the B-form nucleotides for use in the invention is a 2'-S-methyl (2'-SMe) nucleotide that resides in C2' endo conformation. It can be compared to 2'-O-methyl (2'-OMe) nucleotides that resides in a C3' endo conformation. Particularly suitable for use in comparing these two
30 nucleotides are molecular dynamic investigations using a SGI [Silicon Graphics, Mountain View, CA] computer and the AMBER [UCSF, San Francisco, CA] modeling software package for computer simulations.

Ribose conformations in C2'-modified nucleosides
35 containing S-methyl groups were examined. To understand the

influence of 2'-O-methyl and 2'-S-methyl groups on the conformation of nucleosides, we evaluated the relative energies of the 2'-O- and 2'-S-methylguanosine, along with normal deoxyguanosine and riboguanosine, starting from both C2'-endo and C3'-endo conformations using *ab initio* quantum mechanical calculations. All the structures were fully optimized at HF/6-31G* level and single point energies with electron-correlation were obtained at the MP2/6-31G*//HF/6-31G* level. As shown in Table 1, the C2'-endo conformation of deoxyguanosine is estimated to be 0.6 kcal/mol more stable than the C3'-endo conformation in the gas-phase. The conformational preference of the C2'-endo over the C3'-endo conformation appears to be less dependent upon electron correlation as revealed by the MP2/6-31G*//HF/6-31G* values which also predict the same difference in energy. The opposite trend is noted for riboguanosine. At the HF/6-31G* and MP2/6-31G*//HF/6-31G* levels, the C3'-endo form of riboguanosine is shown to be about 0.65 and 1.41 kcal/mol more stable than the C2'endo form, respectively.

20

Table 1

Relative energies' of the C3'-endo and C2'-endo conformations of representative nucleosides.

	HF/6-31G	MP2/6-31-G	CONTINUUM MODEL	AMBER
25 dG	0.60	0.56	0.88	0.65
rG	-0.65	-1.41	-0.28	-2.09
2'-O-MeG	-0.89	-1.79	-0.36	-0.86
2'-S-MeG	2.55	1.41	3.16	2.43

30 'energies are in kcal/mol relative to the C2'-endo conformation

Table 1 also includes the relative energies of 2'-O-methylguanosine and 2'-S-methylguanosine in C2'-endo and C3'-endo conformation. This data indicates the electronic nature of C2'-substitution has a significant impact on the relative stability of these conformations. Substitution of the 2'-O-methyl group increases the preference for the C3'-endo conformation (when compared to riboguanosine) by about 0.4 kcal/mol at both the HF/6-31G* and MP2/6-31G*//HF/6-31G* levels. In contrast, the 2'-S-methyl group reverses the trend. The C2'-endo conformation is favored by about 2.6 kcal/mol at the HF/6-31G* level, while the same difference is reduced to 1.41 kcal/mol at the MP2/6-31G*//HF/6-31G* level. For comparison, and also to evaluate the accuracy of the molecular mechanical force-field parameters used for the 2'-O-methyl and 2'-S-methyl substituted nucleosides, we have calculated the gas phase energies of the nucleosides. The results reported in Table 1 indicate that the calculated relative energies of these nucleosides compare qualitatively well with the *ab initio* calculations.

Additional calculations were also performed to gauge the effect of solvation on the relative stability of nucleoside conformations. The estimated solvation effect using HF/6-31G* geometries confirms that the relative energetic preference of the four nucleosides in the gas-phase is maintained in the aqueous phase as well (Table 1). Solvation effects were also examined using molecular dynamics simulations of the nucleosides in explicit water. From these trajectories, one can observe the predominance of C2'-endo conformation for deoxyriboguanosine and 2'-S-methylriboguanosine while riboguanosine and 2'-O-methylriboguanosine prefer the C3'-endo conformation. These results are in much accord with the available NMR results on 2'-S-methylribonucleosides. NMR studies of sugar puckering equilibrium using vicinal spin-coupling constants have indicated that the conformation of the sugar ring in 2'-S-methylpyrimidine nucleosides show an

average of >75% S-character, whereas the corresponding purine analogs exhibit an average of >90% S-pucker [Fraser, A., Wheeler, P., Cook, P.D. and Sanghvi, Y.S., *J. Heterocycl. Chem.*, **1993**, *30*, 1277-1287]. It was observed that the 2'-S-
5 methyl substitution in deoxynucleoside confers more conformational rigidity to the sugar conformation when compared with deoxyribonucleosides.

Structural features of DNA:RNA, OMe_DNA:RNA and SMe_DNA:RNA hybrids were also observed. The average RMS
10 deviation of the DNA:RNA structure from the starting hybrid coordinates indicate the structure is stabilized over the length of the simulation with an approximate average RMS deviation of 1.0 Å. This deviation is due, in part, to inherent differences in averaged structures (i.e. the starting
15 conformation) and structures at thermal equilibrium. The changes in sugar pucker conformation for three of the central base pairs of this hybrid are in good agreement with the observations made in previous NMR studies. The sugars in the RNA strand maintain very stable geometries in the C3'-endo
20 conformation with ring pucker values near 0°. In contrast, the sugars of the DNA strand show significant variability.

The average RMS deviation of the OMe_DNA:RNA is approximately 1.2 Å from the starting A-form conformation; while the SMe_DNA:RNA shows a slightly higher deviation
25 (approximately 1.8 Å) from the starting hybrid conformation. The SMe_DNA strand also shows a greater variance in RMS deviation, suggesting the S-methyl group may induce some structural fluctuations. The sugar puckers of the RNA complements maintain C3'-endo puckering throughout the
30 simulation. As expected from the nucleoside calculations, however, significant differences are noted in the puckering of the OMe_DNA and SMe_DNA strands, with the former adopting C3'-endo, and the latter, C1'-exo/C2'-endo conformations.

An analysis of the helicoidal parameters for all three
35 hybrid structures has also been performed to further

characterize the duplex conformation. Three of the more important axis-basepair parameters that distinguish the different forms of the duplexes, X-displacement, propeller twist, and inclination, are reported in Table 2. Usually, an X-displacement near zero represents a B-form duplex; while a negative displacement, which is a direct measure of deviation of the helix from the helical axis, makes the structure appear more A-like in conformation. In A-form duplexes, these values typically vary from -4\AA to -5\AA . In comparing these values for all three hybrids, the SMe_DNA:RNA hybrid shows the most deviation from the A-form value, the OMe_DNA:RNA shows the least, and the DNA:RNA is intermediate. A similar trend is also evident when comparing the inclination and propeller twist values with ideal A-form parameters. These results are further supported by an analysis of the backbone and glycosidic torsion angles of the hybrid structures. Glycosidic angles (χ) of A-form geometries, for example, are typically near -159° while B form values are near -102° . These angles are found to be -162° , -133° , and -108° for the OMe_DNA, DNA, and SMe_DNA strands, respectively. All RNA complements adopt an χ angle close to -160° . In addition, "crankshaft" transitions were also noted in the backbone torsions of the central UpU steps of the RNA strand in the SMe_DNA:RNA and DNA:RNA hybrids. Such transitions suggest some local conformational changes may occur to relieve a less favorable global conformation. Taken overall, the results indicate the amount of A-character decreases as OMe_DNA:RNA>DNA:RNA>SMe_DNA:RNA, with the latter two adopting more intermediate conformations when compared to A- and B-form geometries.

Table 2

Average helical parameters derived from
the last 500 ps of simulation time.

(canonical A-and B-form values are given for comparison)

5 Helicoidal Parameter	B-DNA (x-ray)	B-DNA (fibre)	A-DNA (fibre)	DNA:RNA	OMe_DNA: RNA	SMe_DNA: RNA
X-disp	1.2	0.0	-5.3	-4.5	-5.4	-3.5
Inclination	-2.3	1.5	20.7	11.6	15.1	0.7
Propeller	-16.4	-13.3	-7.5	-12.7	-15.8	-10.3

10 Stability of C2'-modified DNA:RNA hybrids was determined. Although the overall stability of the DNA:RNA hybrids depends on several factors including sequence-dependencies and the purine content in the DNA or RNA strands DNA:RNA hybrids are usually less stable than RNA:RNA duplexes and, in some cases,
15 even less stable than DNA:DNA duplexes. Available experimental data attributes the relatively lowered stability of DNA:RNA hybrids largely to its intermediate conformational nature between DNA:DNA (B-family) and RNA:RNA (A-family) duplexes. The overall thermodynamic stability of nucleic acid
20 duplexes may originate from several factors including the conformation of backbone, base-pairing and stacking interactions. While it is difficult to ascertain the individual thermodynamic contributions to the overall stabilization of the duplex, it is reasonable to argue that
25 the major factors that promote increased stability of hybrid duplexes are better stacking interactions (electrostatic π - π interactions) and more favorable groove dimensions for hydration. The C2'-S-methyl substitution has been shown to destabilize the hybrid duplex. The notable differences in the
30 rise values among the three hybrids may offer some explanation. While the 2'-S-methyl group has a strong influence on decreasing the base-stacking through high rise values (~ 3.2 Å), the 2'-O-methyl group makes the overall

structure more compact with a rise value that is equal to that of A-form duplexes (~ 2.6 Å). Despite its overall A-like structural features, the SMe_DNA:RNA hybrid structure possesses an average rise value of 3.2 Å which is quite close to that of B-family duplexes. In fact, some local base-steps (CG steps) may be observed to have unusually high rise values (as high as 4.5 Å). Thus, the greater destabilization of 2'-S-methyl substituted DNA:RNA hybrids may be partly attributed to poor stacking interactions.

10 It has been postulated that RNase H binds to the minor groove of RNA:DNA hybrid complexes, requiring an intermediate minor groove width between ideal A- and B-form geometries to optimize interactions between the sugar phosphate backbone atoms and RNase H. A close inspection of the averaged
15 structures for the hybrid duplexes using computer simulations reveals significant variation in the minor groove width dimensions as shown in Table 3. Whereas the O-methyl substitution leads to a slight expansion of the minor groove width when compared to the standard DNA:RNA complex, the S-
20 methyl substitution leads to a general contraction (approximately 0.9 Å). These changes are most likely due to the preferred sugar puckering noted for the antisense strands which induce either A- or B-like single strand conformations. In addition to minor groove variations, the results also point
25 to potential differences in the steric makeup of the minor groove. The O-methyl group points into the minor groove while the S-methyl is directed away towards the major groove. Essentially, the S-methyl group has flipped through the bases into the major groove as a consequence of C2'-endo puckering.

Table 3
Minor groove widths averaged
over the last 500 ps of simulation time

	Phosphate	DNA:RNA	OMe_DNA:	SMe_DNA:	DNA:RNA	RNA:RNA
	Distance		RNA	RNA	(B-form)	(A-form)
5	P5-P20	15.27	16.82	13.73	14.19	17.32
	P6-P19	15.52	16.79	15.73	12.66	17.12
	P7-P18	15.19	16.40	14.08	11.10	16.60
	P8-P17	15.07	16.12	14.00	10.98	16.14
10	P9-P16	15.29	16.25	14.98	11.65	16.93
	P10-P15	15.37	16.57	13.92	14.05	17.69

In addition to the modifications described above, the nucleotides of the oligonucleotides of the invention can have a variety of other modification so long as these other
15 modifications do not significantly detract from the properties described above. Thus, for nucleotides that are incorporated into oligonucleotides of the invention, these nucleotides can have sugar portions that correspond to naturally-occurring sugars or modified sugars. Representative modified sugars
20 include carbocyclic or acyclic sugars, sugars having substituent groups at their 2' position, sugars having substituent groups at their 3' position, and sugars having substituents in place of one or more hydrogen atoms of the sugar. Other altered base moieties and altered sugar moieties
25 are disclosed in United States Patent 3,687,808 and PCT application PCT/US89/02323.

Altered base moieties or altered sugar moieties also include other modifications consistent with the spirit of this invention. Such oligonucleotides are best described as being
30 structurally distinguishable from, yet functionally interchangeable with, naturally occurring or synthetic wild type oligonucleotides. All such oligonucleotides are

comprehended by this invention so long as they function effectively to mimic the structure of a desired RNA or DNA strand. A class of representative base modifications include tricyclic cytosine analog, termed "G clamp" (Lin, et al., *J. Am. Chem. Soc.* **1998**, 120, 8531). This analog makes four hydrogen bonds to a complementary guanine (G) within a helix by simultaneously recognizing the Watson-Crick and Hoogsteen faces of the targeted G. This G clamp modification when incorporated into phosphorothioate oligonucleotides, dramatically enhances antisense potencies in cell culture. The oligonucleotides of the invention also can include phenoxazine-substituted bases of the type disclosed by Flanagan, et al., *Nat. Biotechnol.* **1999**, 17(1), 48-52.

Additional modifications may also be made at other positions on the oligonucleotide, particularly the 3' position of the sugar on the 3' terminal nucleotide and the 5' position of 5' terminal nucleotide. For example, one additional modification of the oligonucleotides of the invention involves chemically linking to the oligonucleotide one or more moieties or conjugates which enhance the activity, cellular distribution or cellular uptake of the oligonucleotide. Such moieties include but are not limited to lipid moieties such as a cholesterol moiety (Letsinger et al., *Proc. Natl. Acad. Sci. USA*, 1989, 86, 6553), cholic acid (Manoharan et al., *Bioorg. Med. Chem. Lett.*, 1994, 4, 1053), a thioether, e.g., hexyl-S-tritylthiol (Manoharan et al., *Ann. N.Y. Acad. Sci.*, 1992, 660, 306; Manoharan et al., *Bioorg. Med. Chem. Lett.*, 1993, 3, 2765), a thiocholesterol (Oberhauser et al., *Nucl. Acids Res.*, 1992, 20, 533), an aliphatic chain, e.g., dodecandiol or undecyl residues (Saison-Behmoaras et al., *EMBO J.*, 1991, 10, 111; Kabanov et al., *FEBS Lett.*, 1990, 259, 327; Svinarchuk et al., *Biochimie*, 1993, 75, 49), a phospholipid, e.g., di-hexadecyl-rac-glycerol or triethylammonium 1,2-di-O-hexadecyl-rac-glycero-3-H-phosphonate (Manoharan et al.,

Tetrahedron Lett., 1995, 36, 3651; Shea et al., Nucl. Acids Res., 1990, 18, 3777), a polyamine or a polyethylene glycol chain (Manoharan et al., Nucleosides & Nucleotides, 1995, 14, 969), or adamantane acetic acid (Manoharan et al., Tetrahedron Lett., 1995, 36, 3651), a palmityl moiety (Mishra et al., Biochim. Biophys. Acta, 1995, 1264, 229), or an octadecylamine or hexylamino-carbonyl-oxysterol moiety (Crooke et al., J. Pharmacol. Exp. Ther., 1996, 277, 923).

Human RNase H1 displays a strong positional preference for cleavage, i.e., it cleaves between 8-12 nucleotides from the 5'-RNA:3'-DNA terminus of the duplex. Within the preferred cleavage site, the enzyme displays modest sequence preference with GU being a preferred dinucleotide. The minimum RNA:DNA duplex length that supports cleavage is 6-base pairs and the minimum RNA:DNA "gap size" that supports cleavage is 5-base pairs.

Properties of purified Human RNase H1

The effects of various reaction conditions on the activity of Human RNase H1 were evaluated (Fig. 1). The optimal pH for the enzyme in both Tris HCl and phosphate buffers was 7.0-8.0. At pH's above pH8.0, enzyme activity was reduced. However, this could be due to instability of the substrate or effects on the enzyme, or both. To evaluate the potential contribution of changes in ionic strength to the activities observed at different pHs, two buffers, NaHPO₄ and Tris HCl were studied at pH 7.0 and gave the same enzyme activity even though the ionic strengths differed. Enzyme activity was inhibited by increasing ionic strength (Fig. 1B) and N-ethylmaleamide (Fig. 1C). Enzyme activity increased as the temperature was raised from 25-42° C (Fig. 1D). Mg²⁺ stimulated enzyme activity with an optimal concentration of 1mM. At higher concentrations, Mg²⁺ was inhibitory (Fig. 1E). In the presence of 1mM Mg²⁺, Mn²⁺ was inhibitory at all

concentrations tested (Fig. 1F). The purified enzyme was quite stable and easily handled. In fact, the enzyme could be boiled and rapidly or slowly cooled without significant loss of activity (Fig. 1D). The initial rates of cleavage
5 were determined for four duplex substrates studied simultaneously. The initial rate of cleavage for a phosphodiester DNA:RNA duplex was 1050 ± 203 pmol L⁻¹min⁻¹ (Table 4A). The initial rate of cleavage of a phosphorothioate oligodeoxynucleotide duplex was approximately
10 four-fold faster than that of the same duplex comprised of a phosphodiester antisense oligodeoxynucleotide (Table 4A). The initial rates for 17-mer and 20-mer substrates of different sequences were equal (Table 4B). However, when a 25-mer heteroduplex, containing the 17-mer sequence in the center of
15 the duplex was digested (RNA 3), the rate was 50% faster. Interestingly, the K_m of the enzyme for the 25 mer duplex was 40% lower than that for the 17 mer while the V_{max} 's for both duplexes were the same (see Table 6), suggesting that with the increase in length, a larger number of cleavage sites are
20 available resulting in an increase in the number of productive binding interactions between the enzyme and substrate. As a result, a lower substrate concentration is required for the longer duplex to achieve a cleavage rate equal to that of the shorter duplex.

25 To better characterize the substrate specificity of Human RNase H1, duplexes in which the antisense oligonucleotide was modified in the 2'-position were studied. As previously reported for *E. coli* RNase H1, Human RNase H1 was unable to cleave substrates with 2'-modifications at the cleavage site
30 of the antisense DNA strand or the sense RNA strand (Table 5). For example, the initial rate of cleavage of a duplex containing a phosphorothioate oligodeoxynucleotide and its complement was 3400 pmol L⁻¹min⁻¹ while that of its 2'-propoxy modified analog was undetectable (Table 5). A duplex
35 comprised of a fully modified 2'-methoxy antisense strand also

failed to support any cleavage (Table 5). The placement of 2'-methoxy modifications around a central region of oligodeoxynucleotides reduced the initial rate (Table 5). The smaller the central oligodeoxynucleotide "gap" the lower the initial rate. The smallest "gapmer" for which cleavage could be measured was a 5 deoxynucleotide gap. These data are highly consistent with observations we have previously reported for *E. coli* RNase H1 except that for the bacterial enzyme the minimum gap size was 4 deoxynucleotides.

10 The K_m and V_{max} of Human RNase H1 for three substrates are shown in Table 6. The K_m values for all three substrates were substantially lower than those of *E. coli* RNase H1 (Table 6). As previously reported for *E. coli* RNase H1, the K_m for a phosphorothioate containing duplex was lower than that of
15 a phosphodiester duplex. The V_{max} of the human enzyme was 30 fold lower than that of the *E. coli* enzyme. The V_{max} for the phosphorothioate containing substrate was less than the phosphodiester duplex. This is probably due to inhibition of the enzyme at higher concentrations by excess phosphorothioate
20 single strand oligonucleotide as the initial rate of cleavage for a phosphorothioate containing duplex was, in fact, greater than the phosphodiester (Table 4)

Binding affinity and specificity

To evaluate the binding affinity of Human RNase H1, a
25 competitive cleavage assay in which increasing concentrations of noncleavable substrates were added was used. Using this approach, the K_i is formally equivalent to the K_d for the competing substrates. Of the noncleavable substrates studied, Lineweaver-Burk analyses demonstrated that all inhibitors
30 shown in Table 7 were competitive (data not shown). A duplex containing a phosphodiester oligodeoxynucleotide hybridized to a phosphodiester 2'-methoxy oligonucleotide as the noncleavable substrate is considered most like DNA:RNA. Table

7 shows the results of these studies and compares them to previously reported results for the *E. coli* enzyme performed under similar conditions. Clearly, the affinity of the human enzyme for its DNA:RNA like substrate (DNA:2'-O-Me) was substantially greater than that of the *E. coli* enzyme, consistent with the differences observed in K_m (Table 6).

E. coli RNase H1 displays approximately equal affinity for RNA:RNA, RNA:2'-O-Me and DNA:2'-O-Me duplexes (Table 7). The human enzyme displays similar binding properties, but is more able to discriminate between various duplexes. For example, the K_d for RNA:RNA was approximately 5 fold lower than the K_d for DNA:2'-O-Me. This is further demonstrated by the K_d for the RNA:2'-F duplex. The K_d for the DNA:2'-F duplex was slightly greater than for the RNA:2'-F duplex and the RNA:RNA duplex, but clearly lower than for other duplexes. Thus, both enzymes can be considered double strand RNA binding proteins. However, Human RNase H1 is somewhat less specific for duplexes as compared to single strand oligonucleotides than the *E. coli* enzyme. The enzyme bound to single strand RNA and DNA only 20 fold less well than an RNA:RNA duplex while the *E. coli* enzyme bound to single strand DNA nearly 600 fold less than to an RNA:RNA duplex (Table 7). The affinity of a single strand phosphorothioate oligodeoxynucleotide for both enzymes was significant relative to the affinity for the natural substrate and accounts for the inhibition of the enzymes by members of this class oligonucleotides. Remarkably, Human RNase H1 displayed the highest affinity for a single strand phosphorothioate oligodeoxynucleotide. Thus, this noncleavable substrate is a very effective inhibitor of the enzyme and excess phosphorothioate antisense drug in cells might be highly inhibitory.

Site and sequence preferences for cleavage

Fig. 2 shows the cleavage pattern for RNA duplexed with its phosphorothioate oligodeoxynucleotide and the pattern for

several gapmers. In the parent duplex, RNA cleavage occurred at a single major site with minor cleavage noted at several sites 3' to this major cleavage site that was 8 nucleotides from 5'-terminus of the RNA. Note that the preferred site
5 occurred at a GU dinucleotide. Cleavage of several "gapmers" occurred more slowly and the major cleavage site was at a different position from that of the parent duplex. Further, in contrast to the observations we have made for *E. coli* RNase H1, the major cleavage site in gapmers treated with Human
10 RNase H1 did not occur at the nucleotide apposed to the nucleotide adjacent to the first 2' methoxy nucleotide in the wing hybridized to the 3' portion of the RNA.

To further evaluate the site and sequence specificities of Human RNase H1, cleavage of substrates shown in Fig. 3 and
15 Fig. 4 was studied. In Fig. 3, the sequence of the RNA is displayed below the sequencing gels and the length and position of the complementary phosphodiester oligodeoxynucleotide indicated by the solid line below the RNA sequence. This figure demonstrates several important
20 properties of the enzyme. First, the main cleavage site was consistently observed 8-9 nucleotides from the 5'-RNA:3'-DNA terminus of the duplex irrespective of whether there were 5' or 3'-RNA single strand overhangs. Second, the enzyme, like *E. coli* RNase H1 was capable of cleaving single strand regions
25 of RNA adjacent to the 3'-terminus of an RNA:DNA duplex. Third, the minimum duplex length that supported any cleavage was approximately 6 nucleotides. RNase protection assays were used to confirm that under conditions of the assay the shorter duplexes were fully hybridized, so the differences observed
30 were not due to the failure to hybridize. To assure that the 6-nucleotide duplex was fully hybridized, the reactions were carried out at a 50:1 DNA:RNA ratio (data not shown). Fourth, the figure shows that for duplexes smaller than the nine base pairs, the smaller the duplex, the slower the cleavage rate.

Fifth, the preferred cleavage site was located at a GU dinucleotide.

The site and sequence specificities are further explored in Fig. 4. That the enzyme displays little sequence preference is demonstrated by comparing the rates and sites of cleavage for duplexes A, C and D. In all cases, the preferred site of cleavage was 8-12 nucleotides from the 5'-RNA:3'-DNA terminus of the duplex irrespective of the sequence. Comparison of the cleavage pattern for duplexes A and B shows that cleavage occurred at the 8-12 nucleotide position even when there were RNA overhangs also as shown in Fig. 3. Cleavage of duplex F demonstrated that the site of cleavage was retained even if there were 5'- and 3'-DNA overhangs. In a longer substrate, duplex G, the main site of cleavage was still 8-12 nucleotides from the terminus of the duplex. However, minor cleavage sites were observed throughout the RNA suggesting that this substrate might support binding of more than one enzyme molecule per substrate, but that the preferred site was near the 5'-RNA:3'-DNA terminus. Finally, optimal cleavage seemed to occur when a GU dinucleotide was located 8-12 nucleotides from the 5'-RNA:3'-DNA terminus of the duplex.

To address both the mechanism of cleavage and processivity, the cleavage of 5'-labeled and 3'-labeled substrates was compared (Fig. 5). Lane C shows that CIP treatment prior to and after digestion with Human RNase H1 resulted in a shift in the mobility of the digested fragments suggesting that Human RNase H1 generates cleavage products with 5'-phosphates. Thus, it is similar to *E. coli* RNase H1 in this regard. A second intriguing observation is that the addition of pC to the 3'-end of the RNA caused a shift in the position of the preferred cleavage site (A vs B or C). The four cleavage sites in the center of the duplex observed with a 5'-phosphate labeled RNA were observed in 3' pC-labeled substrates. However, the main cleavage site shifted from base pair 8 to base pair 12. Interestingly, the sequence at both

sites was GU. Thus, it is conceivable that the enzyme selects a position 8-12 nucleotide from the 5'-RNA:3'-DNA terminus, then cleaves at a preferred dinucleotide such as GU. Third, this figure considered along with the cleavage patterns shown in Figs. 3 and 4 demonstrates that this enzyme displays minimal processivity in either the 5' or 3'-direction. In no time course experiment using any substrate have we observed a pattern that would be consistent with processivity. The possibility that the failure to observe processivity in Figs. 3 and 4 was due to processivity in the 3' to 5'-direction is excluded by the results in Fig. 5. Again, this is significantly different from observations we have previously reported for *E. coli* RNase H1.

General properties of Human RNase H1 activity

The present invention also describes the properties of human RNase H1 that have been characterized. As the protein studied is a his-tag fusion and was denatured and refolded, it is possible that the activity of the enzyme in its native state might be greater than we have observed. However, basic properties are certainly likely to reflect the basic properties of the native enzyme. Numerous studies have shown that a his-tag does not interfere with protein folding and crystallization, kinetic and catalytic properties, or nucleic acid binding properties since it is very small (few amino acids) and its pK is near neutral. It is shown in the present invention that the his-tag fusion protein behaves like other RNase H's. It cleaved specifically the RNA strand in RNA:DNA duplexes, resulted in cleavage products with 5'-phosphate termini (Fig. 5) and was affected by divalent cations (Fig. 1). Optimal conditions for Human RNase H1 were similar to, but not identical to, *E. coli* RNase H1. For the human enzyme, the Mg^{2+} optimum was 1mM and 5 mM Mg^{2+} was inhibitory. In the presence of Mg^{2+} , both enzymes were inhibited by Mn^{2+} . The human enzyme was inhibited by n-ethylmaleimide and was quite

stable, easily handled and did not form multimeric structures (Fig. 1). The ease of handling, denaturation, refolding and stability in various conditions suggest that the Human RNase H1 was active as a monomer and has a relatively stable preferred conformation.

Studies on the structure and enzymatic activities of a number of mutants of *E. coli* RNase H1 have recently led to a hypothesis to explain the effects of divalent cations termed an activation/attenuation model. The effects of divalent cations on Human RNase H1 are complex and are consistent with the suggested activation/attenuation model. The amino acids proposed to be involved in both cation binding sites are conserved in Human RNase H1.

Positional and sequence preferences and processivity

The site and sequence specificity of Human RNase H1 differ substantially from *E. coli* RNase H1. Although neither enzyme displays significant sequence specificity and Figs. 2-5 this manuscript, the human enzyme displays remarkable site specificity. Figs. 2-4 show that Human RNase H1 preferentially cleaved 8-12 nucleotides 3' from the 5'-RNA:3'-DNA terminus of a DNA:RNA duplex irrespective of whether there were 5' or 3'-RNA or DNA overhangs. The process by which a position is selected and then within that position on the duplex a particular dinucleotide is cleaved preferentially must be relatively complex and influenced by sequence. Clearly, the dinucleotide, GU, is a preferred sequence. In Fig. 3, for example, all the duplexes contained a GU sequence near the optimal position for the enzyme and in all cases the preferential cleavage site was GU. Additionally, in duplexes A and B a second GU was also cleaved, albeit at a very slow rate. The third site in duplexes A and B cleaved was a GG dinucleotide 7 base pairs from the 3'-RNA:5'-DNA terminus. Thus, the data suggest that the enzyme displays strong

positional preference and within the appropriate site, slight preference for GU dinucleotides.

The strong positional preference exhibited by Human RNase H1 suggests that the enzyme fixes its position on the duplex via the 5'-RNA:3'-DNA terminus. Interestingly, the *in-vitro* cleavage pattern observed for the enzyme is compatible with its proposed *in-vivo* role, namely, the removal of RNA primers during DNA replication of the lagging strand. The average length of the RNA primer ranges from 7-14 nucleotides. Consequently, synthesis of the lagging strand results in chimeric sequences consisting of 7-14 ribonucleotides at the 5'-terminus with contiguous stretches of DNA extending in the 3' direction. The positional preference observed for Human RNase H1, (*i.e.*, 8-12 residues from the 5'-terminus of the RNA), would suggest that cleavage of the chimeric lagging strand by RNase H1 would occur at or near the RNA:DNA junction. The removal of residual ribonucleotides following RNase H digestion has been shown to be performed by the endonuclease FEN1.

Fig. 4 provides additional insight into the positional and sequence preferences of the enzyme. When there was a GU dinucleotide present in the correct position in the duplex, it was cleaved preferentially. When a GU dinucleotide was absent, AU was cleaved as well as other dinucleotides. For duplex G both a GU and a GG dinucleotide were present within the preferred site, and in this case the GG dinucleotide was cleaved slightly more extensively than the GU dinucleotide. Clearly, additional duplexes of different sequences must be studied before definitive conclusions concerning the roles of various sequences within the preferred cleavage sites can be drawn.

In Fig. 5, the 3'-terminus of the RNA was labeled with ³²pC. In this case the same four nucleotides were cleaved as when the RNA was 5' labeled (Fig. 5, panels B & C). However, the GU closer to the 3'-terminus of the RNA was cleaved at

least as rapidly as the 5'-GU. Interestingly in studies on the partially purified enzyme, differences in the cleavage pattern were also observed when 5'-labeled substrates were compared to 3'-labeled substrates. A possible explanation for this observation is that the presence of a 3'-phosphate on an oligonucleotide substrate affects the scanning mechanism the enzyme uses to select preferred positions for cleavage.

In a duplex comprised of RNA annealed to a chimeric oligonucleotide with an oligodeoxynucleotide center flanked by 2'-modified nucleotide wings, the cleavage by Human RNase H1 was directed to the DNA:RNA portion of the duplex as was observed for *E. coli* RNase H1. However, within this region, the preferred sites of cleavage for the human enzyme differed from *E. coli* RNase H1. *E. coli* RNase H1 preferentially cleaved at the ribonucleotide apposed to first 2'-modified nucleotide in the wing of antisense oligonucleotide at the 3'-end of the RNA. In contrast, the human enzyme preferentially cleaved at sites more centered within the gap until the gap was reduced to 5 nucleotides. Further, the minimum gap size for the human enzyme was 5 nucleotides while that of *E. coli* RNase H1 was 4 nucleotides. These differences in behavior suggest differences in the structures of the enzymes and their interactions with substrate that will require additional study.

Although *E. coli* RNase H1 degrades the heteroduplex substrate in a predominantly distributive manner, the enzyme displays modest 5'-3'-processivity. In contrast, Human RNase H1 evidences no 5'-3' or 3'-5'-processivity suggesting that the human enzyme hydrolyzes the substrate in an exclusively distributive manner. The lack of processivity observed with the Human RNase H1 may be a function of the significantly tighter binding affinity (Table 7), thereby reducing the ability of the enzyme to move on the substrate. Alternatively, Human RNase H1 appears to fix its position on the substrate with respect to the 5'-RNA:3'-DNA terminus and

this strong positional preference may preclude cleavage of the substrate in a processive manner. (Fig. 5). Thus, despite the fact that the enzymes are both metal-dependent endonucleases that result in cleavage products with 5'-phosphates (Fig. 5) and both can cleave single-strand 3'-RNA overhangs (Fig. 5), these enzymes display substantial differences.

E. coli RNase H1 has been suggested to exhibit "binding directionality" with respect to the RNA of the substrate such that the primary binding region of the enzyme is positioned several nucleotides 5' to the catalytic center. This results in cleavage sites being restricted from the 5'-RNA:3'-DNA end of a duplex, and cleavage sites occurring at the 3'-RNA:5'-DNA end of the duplex and in 3'-single-strand overhangs. The human enzyme behaves entirely analogously. Thus, we conclude that Human RNase H1 likely has the same binding directionality as the *E. coli* enzyme.

Substrate binding

RNA:RNA duplexes have been shown to adopt an A-form conformation. Many 2'-modifications shift the sugar conformation into a 3'-endo pucker characteristic of RNA. Consequently, when hybridized to RNA, the resulting duplex is "A" form and this is manifested in a more stable duplex. 2'-F Oligonucleotides display duplex forming properties most like RNA, while 2'-methoxy oligonucleotides result in duplexes intermediate information between DNA:RNA and RNA:RNA duplexes.

The results shown in Table 7 demonstrate that like the *E. coli* enzyme, Human RNase H1 is a double strand RNA binding protein. Moreover, it displays some ability to discriminate between various A-form duplexes (Table 7). The observation that the K_d for an RNA:2'-F duplex is equal to that for an RNA:RNA duplex suggests that 2'-hydroxy group is not required for binding to the enzyme. Nevertheless, we cannot exclude the possibility that bulkier 2'-modifications, e.g. 2'-methoxy or 2'-propyl might sterically inhibit the binding of the

enzyme as well as alter the A-form quality of the duplex. The human enzyme displays substantially greater affinity for all oligonucleotides than the *E. coli* enzyme and this is reflected in a lower K_m for cleavable substrates (Tables 6 and 7). In addition, the tighter binding affinity observed for Human RNase H1 may be responsible for the 20-fold lower V_{max} when compared to the *E. coli* enzyme. In this case, assuming that the *E. coli* and human enzymes exhibit similar catalytic rates (K_{cat}), then an increase in the binding affinity would result in a lower turnover rate and ultimately a lower V_{max} .

The principal substrate binding site in *E. coli* RNase H1 is thought to be a cluster of lysines that are believed to bind to the phosphates of the substrates. The interaction of the binding surface of the enzyme and substrate is believed to occur within the minor groove. This region is highly conserved in the human enzyme. In addition, eukaryotic enzymes contain an extra N-terminal region of variable length containing an abundance of basic amino acids. This region is homologous with a double strand RNA binding motif and indeed in the *S. cerevisiae* RNase H has been shown to bind to double strand RNA. The N-terminal extension in Human RNase H1 is longer than that in the *S. cerevisiae* enzyme and appears to correspond to a more complete double strand RNA binding motif. Consequently, the enhanced binding of Human RNase H1 to various nucleic acids may be due to the presence of this additional binding site.

As used herein, the term "alkyl" includes but is not limited to straight chain, branch chain, and cyclic unsaturated hydrocarbon groups including but not limited to methyl, ethyl, and isopropyl groups. Alkyl groups of the present invention may be substituted. Representative alkyl substituents are disclosed in United States Patent No. 5,212,295, at column 12, lines 41-50, hereby incorporated by reference in its entirety.

Alkenyl groups according to the invention are to straight chain, branch chain, and cyclic hydrocarbon groups containing at least one carbon-carbon double bond, and alkynyl groups are to straight chain, branch chain, and cyclic hydrocarbon groups
5 containing at least one carbon-carbon triply bond. Alkenyl and alkynyl groups of the present invention can be substituted.

Aryl groups are substituted and unsubstituted aromatic cyclic moieties including but not limited to phenyl, naphthyl,
10 anthracyl, phenanthryl, pyrenyl, and xylyl groups. Alkaryl groups are those in which an aryl moiety links an alkyl moiety to a core structure, and aralkyl groups are those in which an alkyl moiety links an aryl moiety to a core structure.

In general, the term "hetero" denotes an atom other than
15 carbon, preferably but not exclusively N, O, or S. Accordingly, the term "heterocyclic ring" denotes a carbon-based ring system having one or more heteroatoms (i.e., non-carbon atoms). Preferred heterocyclic rings include, for example but not limited to imidazole, pyrrolidine, 1,3-
20 dioxane, piperazine, morpholine rings. As used herein, the term "heterocyclic ring" also denotes a ring system having one or more double bonds, and one or more heteroatoms. Preferred heterocyclic rings include, for example but not limited to the pyrrolidino ring.

25 Oligonucleotides according to the present invention that are hybridizable to a target nucleic acid preferably comprise from about 5 to about 50 nucleosides. It is more preferred that such compounds comprise from about 8 to about 30 nucleosides, with 15 to 25 nucleosides being particularly
30 preferred. As used herein, a target nucleic acid is any nucleic acid that can hybridize with a complementary nucleic acid-like compound. Further in the context of this invention, "hybridization" shall mean hydrogen bonding, which may be Watson-Crick, Hoogsteen or reversed Hoogsteen hydrogen bonding
35 between complementary nucleobases. "Complementary" as used

herein, refers to the capacity for precise pairing between two nucleobases. For example, adenine and thymine are complementary nucleobases which pair through the formation of hydrogen bonds. "Complementary" and "specifically hybridizable," as used herein, refer to precise pairing or sequence complementarity between a first and a second nucleic acid-like oligomers containing nucleoside subunits. For example, if a nucleobase at a certain position of the first nucleic acid is capable of hydrogen bonding with a nucleobase at the same position of the second nucleic acid, then the first nucleic acid and the second nucleic acid are considered to be complementary to each other at that position. The first and second nucleic acids are complementary to each other when a sufficient number of corresponding positions in each molecule are occupied by nucleobases which can hydrogen bond with each other. Thus, "specifically hybridizable" and "complementary" are terms which are used to indicate a sufficient degree of complementarity such that stable and specific binding occurs between a compound of the invention and a target RNA molecule. It is understood that an oligomeric compound of the invention need not be 100% complementary to its target RNA sequence to be specifically hybridizable. An oligomeric compound is specifically hybridizable when binding of the oligomeric compound to the target RNA molecule interferes with the normal function of the target RNA to cause a loss of utility, and there is a sufficient degree of complementarity to avoid non-specific binding of the oligomeric compound to non-target sequences under conditions in which specific binding is desired, i.e. under physiological conditions in the case of *in vivo* assays or therapeutic treatment, or in the case of *in vitro* assays, under conditions in which the assays are performed.

As used herein, "human type 2 RNase H" and "human RNase H1" refer to the same human RNase H enzyme. Accordingly, these terms are meant to be used interchangeably.

The oligonucleotides of the invention can be used in diagnostics, therapeutics and as research reagents and kits. They can be used in pharmaceutical compositions by including a suitable pharmaceutically acceptable diluent or carrier.

5 They further can be used for treating organisms having a disease characterized by the undesired production of a protein. The organism should be contacted with an oligonucleotide having a sequence that is capable of specifically hybridizing with a strand of nucleic acid coding

10 for the undesirable protein. Treatments of this type can be practiced on a variety of organisms ranging from unicellular prokaryotic and eukaryotic organisms to multicellular eukaryotic organisms. Any organism that utilizes DNA-RNA transcription or RNA-protein translation as a fundamental part

15 of its hereditary, metabolic or cellular control is susceptible to therapeutic and/or prophylactic treatment in accordance with the invention. Seemingly diverse organisms such as bacteria, yeast, protozoa, algae, all plants and all higher animal forms, including warm-blooded animals, can be

20 treated. Further, each cell of multicellular eukaryotes can be treated, as they include both DNA-RNA transcription and RNA-protein translation as integral parts of their cellular activity. Furthermore, many of the organelles (e.g., mitochondria and chloroplasts) of eukaryotic cells also include

25 transcription and translation mechanisms. Thus, single cells, cellular populations or organelles can also be included within the definition of organisms that can be treated with therapeutic or diagnostic oligonucleotides.

The following nonlimiting examples are provided to

30 further illustrate the present invention.

EXAMPLES**EXAMPLE 1**

5'-O-DMT-2'-O-(2-methoxyethyl)-5-methyl uridine and 5'-O-DMT-3'-O-(2-methoxyethyl)-5-methyl uridine

5 2',3'-O-dibutylstannylene 5-methyl uridine (345 g)
(prepared as per: Wagner et al., *J. Org. Chem.*, **1974**, 39, 24)
was alkylated with 2-methoxyethyl bromide (196 g) in the
presence of tetrabutylammonium iodide (235 g) in DMF (3 L) at
70 °C to give a mixture of 2'-O- and 3'-O-(2-methoxyethyl)-5-
10 methyl uridine (150 g) in nearly 1:1 ratio of isomers. The
mixture was treated with DMT chloride (110 g, DMT-Cl) in
pyridine (1 L) to give a mixture of the 5'-O-DMT-nucleosides.
After the standard work-up the isomers were separated by
silica gel column chromatography. The 2'-isomer eluted first,
15 followed by the 3'-isomer.

EXAMPLE 2

5'-O-DMT-3'-O-(2-methoxyethyl)-5-methyl-uridine-2'-O-(2-cyanoethyl-N,N-diisopropyl) phosphoramidite

 5'-O-DMT-3'-O-(2-methoxyethyl)-5-methyluridine (5
20 g, .008 mol) was dissolved in CH₂Cl₂ (30 mL) and to this
solution, under argon, diisopropylaminotetrazolide (0.415 g)
and 2-cyanoethoxy-N,N-diisopropyl phosphoramidite (3.9 mL)
were added. The reaction was stirred overnight. The solvent
was evaporated and the residue was applied to silica column
25 and eluted with ethyl acetate to give 3.75 g title compound.

EXAMPLE 3

5'-O-DMT-3'-O-(2-methoxyethyl)-N⁴-benzoyl-5-methyl-cytidine

 5'-O-DMT-3'-O-(2-methoxyethyl)-5-methyl uridine (15
g) was treated with 150 mL anhydrous pyridine and 4.5 mL of
30 acetic anhydride under argon and stirred overnight. Pyridine
was evaporated and the residue was partitioned between 200 mL
of saturated NaHCO₃ solution and 200 mL of ethylacetate. The

organic layer was dried (anhydrous MgSO_4) and evaporated to give 16 g of 2'-acetoxy-5'-O-(DMT)-3'-O-(2-methoxyethyl)-5-methyl uridine.

To an ice-cold solution of triazole (19.9 g) in
5 triethylamine (50 mL) and acetonitrile (150 mL), with mechanical stirring, 9 mL of POCl_3 was added dropwise. After the addition, the ice bath was removed and the mixture stirred for 30 min. The 2'-acetoxy-5'-O-(DMT)-3'-O-(2-methoxyethyl)-5-methyl uridine (16 g in 50 mL CH_3CN) was added dropwise to
10 the above solution with the receiving flask kept at ice bath temperatures. After 2 hrs, TLC indicated a faster moving nucleoside, C-4-triazole-derivative. The reaction flask was evaporated and the nucleoside was partitioned between ethylacetate (500 mL) and NaHCO_3 (500 mL). The organic layer
15 was washed with saturated NaCl solution, dried (anhydrous MgSO_4) and evaporated to give 15 g of C-4-triazole nucleoside. This compound was then dissolved in 2:1 mixture of NH_4OH /dioxane (100 mL:200 mL) and stirred overnight. TLC indicated disappearance of the starting material. The
20 solution was evaporated and dissolved in methanol to crystallize out 9.6 g of 5'-O-(DMT)-3'-O-(2-methoxyethyl)-5-methyl cytidine.

5'-O-DMT-3'-O-(2-methoxyethyl)-5-methyl cytidine (9.6 g, 0.015 mol) was dissolved in 50 mL of DMF and treated
25 with 7.37 g of benzoic anhydride. After 24 hrs of stirring, DMF was evaporated and the residue was loaded on silica column and eluted with 1:1 hexane:ethylacetate to give the desired nucleoside.

30 EXAMPLE 4

5'-O-DMT-3'-O-(2-methoxyethyl)-N⁴-benzoyl-5-methyl-cytidine-2'-O-(2-cyanoethyl-N,N-diisopropyl) phosphoramidite

5'-O-DMT-3'-O-(2-methoxyethyl)-N⁴-benzoyl-5-methyl-cytidine-2'-O-(2-cyanoethyl-N,N-diisopropyl) phosphoramidite

was obtained from the above nucleoside using the phosphitylation protocol described for the corresponding 5-methyl-uridine derivative.

EXAMPLE 5

5 N⁶-Benzoyl-5'-O-(DMT) - 3'-O-(2-methoxyethyl) adenosine

A solution of adenosine (42.74 g, 0.16 mol) in dry dimethyl formamide (800 mL) at 5 °C was treated with sodium hydride (8.24 g, 60% in oil prewashed thrice with hexanes, 0.21 mol). After stirring for 30 min, 2-methoxyethyl bromide
10 (0.16 mol) was added over 20 min. The reaction was stirred at 5 °C for 8 h, then filtered through Celite. The filtrate was concentrated under reduced pressure followed by coevaporation with toluene (2x100 mL). The residue was adsorbed on silica gel (100 g) and chromatographed (800 g,
15 chloroform-methanol 9:14:1). Selected fractions were concentrated under reduced pressure and the residue was a mixture of 2'-O-(2-(methoxyethyl) adenosine and 3'-O-(2-methoxyethyl) adenosine in the ratio of 4:1.

The above mixture (0.056 mol) in pyridine (100 mL) was
20 evaporated under reduced pressure to dryness. The residue was redissolved in pyridine (560 mL) and cooled in an ice water bath. Trimethylsilyl chloride (36.4 mL, 0.291 mol) was added and the reaction was stirred at 5 °C for 30 min. Benzoyl chloride (33.6 mL, 0.291 mol) was added and the reaction was
25 allowed to warm to 25 °C for 2 h and then cooled to 5 °C. The reaction was diluted with cold water (112 mL) and after stirring for 15 min, concentrated ammonium hydroxide (112 mL) was added. After 30 min, the reaction was concentrated under reduced pressure (below 30 °C) followed by coevaporation with
30 toluene (2x100 mL). The residue was dissolved in ethyl acetate-methanol (400 mL, 9:1) and the undesired silyl by-products were removed by filtration. The filtrate was concentrated under reduced pressure and then chromatographed on silica gel (800 g, chloroform-methanol 9:1). Selected

fractions were combined, concentrated under reduced pressure and dried at 25 °C/0.2 mmHg for 2 h to give pure N⁶-Benzoyl-2'-O-(2-methoxyethyl) adenosine and pure N⁶-Benzoyl-3'-O-(2-methoxyethyl) adenosine.

5 A solution of N⁶-Benzoyl-3'-O-(2-methoxyethyl) adenosine (11.0 g, 0.285 mol) in pyridine (100 mL) was evaporated under reduced pressure to an oil. The residue was redissolved in dry pyridine (300 mL) and DMT-Cl (10.9 g, 95%, 0.31 mol) was added. The mixture was stirred at 25 °C for 16 h and then
10 poured onto a solution of sodium bicarbonate (20 g) in ice water (500 mL). The product was extracted with ethyl acetate (2x150 mL). The organic layer was washed with brine (50 mL), dried over sodium sulfate (powdered) and evaporated under reduced pressure (below 40C). The residue was chromatographed
15 on silica gel (400 g, ethyl acetate-acetonitrile-triethylamine 99:1:195:5:1). Selected fractions were combined, concentrated under reduced pressure and dried at 25 °C/0.2 mmHg to give 16.8 g (73%) of the title compound as a foam. The TLC was homogenous.

20 **EXAMPLE 6**

[N⁶-Benzoyl-5'-O-(DMT)-3'-O-(2-methoxyethyl) adenosin-2'-O-(2-cyanoethyl-N,N-diisopropyl) phosphoramidite

The title compound was prepared in the same manner as the 5-methyl-cytidine and 5-methyluridine analogs of Examples 2
25 and 4 by starting with the title compound of Example 5. Purification using ethyl acetate-hexanes-triethylamine 59:40:1 as the chromatography eluent gave 67% yield of the title compound as a solid foam. The TLC was homogenous. ³¹P-NMR (CDCl₃, H₃PO₄ std.) δ 147.89; 148.36 (diastereomers).

EXAMPLE 7

5'-O-(DMT)-N²-isobutyryl-3'-O-(2-methoxyethyl) guanosine

A. 2,6-Diaminopurine riboside

To a 2 L stainless steel Parr bomb was added
5 guanosine hydrate (100 g, 0.35 mol, Aldrich), hexamethyl
disilazane (320 mL, 1.52 mol, 4.4 eq.), trimethyl silyl
trifluoromethanesulfonate (8.2 mL), and toluene (350 mL). The
bomb was sealed and partially submerged in an oil bath (170
°C; internal T 150 °C, 150 psi) for 5 days. The bomb was
10 cooled in a dry ice/acetone bath and opened. The contents
were transferred with methanol (300 mL) to a flask and the
solvent was evaporated under reduced pressure. Aqueous
methanol (50%, 1.2 L) was added. The resulting brown
suspension was heated to reflux for 5 h. The suspension was
15 concentrated under reduced pressure to one half volume in
order to remove most of the methanol. Water (600 mL) was
added and the solution was heated to reflux, treated with
charcoal (5 g) and hot filtered through Celite. The solution
was allowed to cool to 25 °C. The resulting precipitate was
20 collected, washed with water (200 mL) and dried at 90 °C/0.2
mmHg for 5 h to give a constant weight of 87.4 g (89%) of tan,
crystalline solid; mp 247 °C (shrinks), 255 °C (dec, lit. (1)
mp 250-252 °C); TLC homogenous (R_f 0.50, isopropanol-
ammonium hydroxide-water 16:3:1); PMR (DMSO), δ 5.73 (d,
25 2, 2-NH₂), 5.78 (s, 1, H-1), 6.83 (br s, 2, 6-NH₂).

**B. 2'-O-(2-methoxyethyl)-2,6-diaminopurine
riboside and 3'-O-(2-methoxyethyl)-2,6-diaminopurine riboside**

To a solution of 2,6-diaminopurine riboside (10.0
g, 0.035 mol) in dry dimethyl formamide (350 mL) at 0 °C under
30 an argon atmosphere was added sodium hydride (60% in oil, 1.6
g, 0.04 mol). After 30 min., 2-methoxyethyl bromide (0.44
mol) was added in one portion and the reaction was stirred at
25 °C for 16 h. Methanol (10 mL) was added and the mixture
was concentrated under reduced pressure to an oil (20 g). The

crude product, containing a ratio of 4:1 of the 2'/3' isomers, was chromatographed on silica gel (500 g, chloroform-methanol 4:1). The appropriate fractions were combined and concentrated under reduced pressure to a semi-solid (12 g).
5 This was triturated with methanol (50 mL) to give a white, hygroscopic solid. The solid was dried at 40 °C/0.2 mmHg for 6 h to give a pure 2' product and the pure 3' isomer, which were confirmed by NMR.

C. 3'-O-2-(methoxyethyl)guanosine

10 With rapid stirring, 3'-O-(2-methoxyethyl)-2,6-diaminopurine riboside (0.078 mol) was dissolved in monobasic sodium phosphate buffer (0.1 M, 525 mL, pH 7.3-7.4) at 25 °C. Adenosine deaminase (Sigma type II, 1 unit/mg, 350 mg) was added and the reaction was stirred at 25 °C for 60 h. The
15 mixture was cooled to 5 °C and filtered. The solid was washed with water (2x25 mL) and dried at 60 °C/0.2 mmHg for 5 h to give 10.7 g of first crop material. A second crop was obtained by concentrating the mother liquors under reduced pressure to 125 mL, cooling to 5 °C, collecting the solid,
20 washing with cold water (2x20 mL) and drying as above to give 6.7 g of additional material for a total of 15.4 g (31 % from guanosine hydrate) of light tan solid; TLC purity 97%.

D. N²-Isobutyryl-3'-O-2-(methoxyethyl)guanosine

To a solution of 3'-O-2-(methoxyethyl)guanosine
25 (18.1 g, 0.0613 mol) in pyridine (300 mL) was added trimethyl silyl chloride (50.4 mL, 0.46 mol). The reaction was stirred at 25 °C for 16 h. Isobutyryl chloride (33.2 mL, 0.316 mol) was added and the reaction was stirred for 4 h at 25 °C. The reaction was diluted with water (25 mL). After stirring for
30 30 min, ammonium hydroxide (concentrated, 45 mL) was added until pH 6 was reached. The mixture was stirred in a water bath for 30 min and then evaporated under reduced pressure to an oil. The oil was suspended in a mixture of ethyl acetate (600 mL) and water (100 mL) until a solution formed. The
35 solution was allowed to stand for 17 h at 25 °C. The

resulting precipitate was collected, washed with ethyl acetate (2x50 mL) and dried at 60 °C/0.2 mmHg for 5 h to give 16.1 g (85%) of tan solid; TLC purity 98%.

E. 5'-O-(DMT)-N²-isobutyryl-3'-O-(2-methoxyethyl)

5 guanosine

A solution of N²-Isobutyryl-3'-O-2-(methoxyethyl) guanosine (0.051 mol) in pyridine (150 mL) was evaporated under reduced pressure to dryness. The residue was redissolved in pyridine (300 mL) and cooled to 10-15 °C. DMT-
10 Cl (27.2 g, 95%, 0.080 mol) was added and the reaction was stirred at 25 °C for 16 h. The reaction was evaporated under reduced pressure to an oil, dissolved in a minimum of methylene chloride and applied on a silica gel column (500 g). The product was eluted with a gradient of methylene chloride-
15 triethylamine (99:1) to methylene chloride-methanol-triethylamine (99:1:1). Selected fractions were combined, concentrated under reduced pressure and dried at 40 °C/0.2 mmHg for 2 h to afford 15 g (15.5% from guanosine hydrate) of tan foam; TLC purity 98%.

20 EXAMPLE 8

[5'-O-(DMT)-N²-isobutyryl-3'-O-(2-methoxyethyl) guanosin-2'-O-(2-cyanoethyl-N,N-diisopropyl) phosphoramidite

The protected nucleoside from Example 7 (0.0486 mol) was placed in a dry 1 L round bottom flask containing a Teflon
25 stir-bar. The flask was purged with argon. Anhydrous methylene chloride (400 mL) was cannulated into the flask to dissolve the nucleoside. Previously vacuum dried N,N-diisopropylaminohydro-tetrazolide (3.0 g, 0.0174 mol) was added under argon. With stirring, bis-N,N-diisopropyl-aminocyno-
30 ethylphosphoramidite (18.8 g, 0.0689 mol) was added via syringe over 1 min (no exotherm noted). The reaction was stirred under argon at 25 °C for 16 h. After verifying the completion of the reaction by TLC, the reaction was

transferred to a separatory funnel (1 L). The reaction flask was rinsed with methylene chloride (2x50 mL). The combined organic layer was washed with saturated aq. sodium bicarbonate (200 mL) and then brine (200 mL). The organic layer was dried
5 over sodium sulfate (50 g, powdered) for 2 h. The solution was filtered and concentrated under reduced pressure to a viscous oil. The resulting phosphoramidite was purified by silica gel flash chromatography (800 g, ethyl acetate-triethylamine 99:1). Selected fractions were combined,
10 concentrated under reduced pressure, and dried at 25°C/0.2 mmHg for 16 h to give 18.0 g (46%, 3% from guanosine hydrate) of solid foam TLC homogenous. ³¹P-NMR (CDCl₃, H₃PO₄ std.) δ 147.96; 148.20 (diastereomers).

15 **EXAMPLE 9**

5'-O-DMT-3'-O-(2-methoxyethyl)-5-methyl-uridine-2'-O-succinate

5'-O-DMT-3'-O-(2-methoxyethyl)-thymidine was first succinylated on the 2'-position. Thymidine nucleoside (4
20 mmol) was reacted with 10.2 mL dichloroethane, 615 mg (6.14 mmol) succinic anhydride, 570 µL (4.09 mmol) triethylamine, and 251 mg (2.05 mmol) 4-dimethylaminopyridine. The reactants were vortexed until dissolved and placed in heating block at 55 °C for approximately 30 minutes. Completeness of reaction
25 checked by thin layer chromatography (TLC). The reaction mixture was washed three times with cold 10% citric acid followed by three washes with water. The organic phase was removed and dried under sodium sulfate. Succinylated nucleoside was dried under P₂O₅ overnight in vacuum oven.

EXAMPLE 10

**5'-O-DMT-3'-O-methoxyethyl-5-methyl-uridine-2'-O-succinoyl
Linked LCA CPG**

5'-O-DMT-3'-O-(2-methoxyethyl)-2'-O-succinyl-
5 thymidine was coupled to controlled pore glass (CPG). 1.09
g (1.52 mmol) of the succinate were dried overnight in a
vacuum oven along with 4-dimethylaminopyridine (DMAP), 2,2'-
dithiobis (5-nitro-pyridine) (dTNP), triphenylphosphine (TPP),
and pre-acid washed CPG (controlled pore glass). After about
10 24 hours, DMAP (1.52 mmol, 186 mg) and acetonitrile (13.7 mL)
were added to the succinate. The mixture was stirred under
an atmosphere of argon using a magnetic stirrer. In a
separate flask, dTNP (1.52 mmol, 472 mg) was dissolved in
acetonitrile (9.6 mL) and dichloromethane (4.1 mL) under
15 argon. This reaction mixture was then added to the succinate.
In another separate flask, TPP (1.52 mmol, 399 mg) was
dissolved in acetonitrile (37 mL) under argon. This mixture
was then added to the succinate/DMAP/dTNP reaction mixture.
Finally, 12.23 g pre-acid washed LCA CPG (loading = 115.2
20 $\mu\text{mol/g}$) was added to the main reaction mixture, vortexed
shortly and placed on shaker for approximately 3 hours. The
mixture was removed from the shaker after 3 hours and the
loading was checked. A small sample of CPG was washed with
copious amounts of acetonitrile, dichloromethane, and then
25 with ether. The initial loading was found to be 63 $\mu\text{mol/g}$
(3.9 mg of CPG was cleaved with trichloroacetic acid, the
absorption of released trityl cation was read at 503 nm on a
spectrophotometer to determine the loading.) The whole CPG
sample was then washed as described above and dried under P_2O_5
30 overnight in vacuum oven. The following day, the CPG was
capped with 25 mL CAP A (tetrahydrofuran/acetic anhydride) and
25 mL CAP B (tetrahydrofuran/pyridine/1-methyl imidazole) for
approximately 3 hours on shaker. Filtered and washed with
dichloromethane and ether. The CPG was dried under P_2O_5

overnight in vacuum oven. After drying, 12.25 g of CPG was isolated with a final loading of 90 $\mu\text{mol/g}$.

EXAMPLE 11

3'-O-Methoxyethyl-5-methyl-N-benzoyl-cytidine-2'-O-succinate

5 5'-O-DMT-3'-O-(2-methoxy) ethyl-N-benzoyl-cytidine was first succinylated on the 2'-position. Cytidine nucleoside (4 mmol) was reacted with 10.2 mL dichloroethane, 615 mg (6.14 mmol) succinic anhydride, 570 μL (4.09 mmol) triethylamine, and 251 mg (2.05 mmol) 4-dimethylaminopyridine. The reactants
10 were vortexed until dissolved and placed in a heating block at 55 °C for approximately 30 minutes. Completeness of reaction was checked by thin layer chromatography (TLC). The reaction mixture was washed three times with cold 10% citric acid followed by three washes with water. The organic phase
15 was removed and dried under sodium sulfate. The succinylated nucleoside was dried under P_2O_5 overnight in vacuum oven.

EXAMPLE 12

5'-O-DMT-3'-O-methoxyethyl-5-methyl-N-benzoyl-cytidine-2'-O-succinoyl linked LCA CPG

20 5'-O-DMT-3'-O-(2-methoxyethyl)-2'-O-succinyl-N⁴-benzoyl cytidine was coupled to controlled pore glass (CPG). 1.05 g (1.30 mmol) of the succinate were dried overnight in a vacuum oven along with 4-dimethylaminopyridine (DMAP), 2,2'-dithiobis (5-nitro-pyridine) (dTNP), triphenylphosphine (TPP), and pre-
25 acid washed CPG (controlled pore glass). The following day, DMAP (1.30 mmol, 159 mg) and acetonitrile (11.7 mL) were added to the succinate. The mixture was "mixed" by a magnetic stirrer under argon. In a separate flask, dTNP (1.30 mmol, 400 mg) was dissolved in acetonitrile (8.2 mL) and
30 dichloromethane (3.5 mL) under argon. This reaction mixture was then added to the succinate. In another separate flask, TPP (1.30 mmol, 338 mg) was dissolved in acetonitrile (11.7

mL) under argon. This mixture was then added to the succinate/DMAP/dTNP reaction mixture. Finally, 10.46 g pre-acid washed LCA CPG (loading = 115.2 $\mu\text{mol/g}$) were added to the main reaction mixture, vortexed shortly and placed on shaker
5 for approximately 2 hours. A portion was removed from shaker after 2 hours and the loading was checked. A small sample of CPG was washed with copious amounts of acetonitrile, dichloromethane, and then with ether. The initial loading was found to be 46 $\mu\text{mol/g}$. (3.4 mg of CPG were cleaved with
10 trichloroacetic acid). The absorption of released trityl cation was read at 503 nm on a spectrophotometer to determine the loading. The whole CPG sample was then washed as described above and dried under P_2O_5 overnight in vacuum oven. The following day, the CPG was capped with 25 mL CAP A
15 (tetrahydrofuran/acetic anhydride) and 25 mL CAP B (tetrahydrofuran/pyridine/1-methyl imidazole) for approximately 3 hours on a shaker. The material was filtered and washed with dichloromethane and ether. The CPG was dried under P_2O_5 overnight in vacuum oven. After drying, 10.77 g of
20 CPG was isolated with a final loading of 63 $\mu\text{mol/g}$.

EXAMPLE 13

5'-O-DMT-3'-O-methoxyethyl-N⁶-benzoyl-adenosine-2'-O-succinate

5'-O-DMT-3'-O-(2-methoxyethyl)-N⁶-benzoyl adenosine was first succinylated on the 2'-position. 3.0 g (4.09 mmol) of
25 the adenosine nucleoside were reacted with 10.2 mL dichloroethane, 615 mg (6.14 mmol) succinic anhydride, 570 μL (4.09 mmol) triethylamine, and 251 mg (2.05 mmol) 4-dimethylaminopyridine. The reactants were vortexed until dissolved and placed in heating block at 55 °C for
30 approximately 30 minutes. Completeness of reaction was checked by thin layer chromatography (TLC). The reaction mixture was washed three times with cold 10% citric acid followed by three washes with water. The organic phase was

removed and dried under sodium sulfate. Succinylated nucleoside was dried under P_2O_5 overnight in vacuum oven.

EXAMPLE 14**5'-O-DMT- 3'-O-(2-methoxyethyl)-N⁶-benzoyl-adenosine-2'-O-succinoyl Linked LCA CPG**

Following succinylation, 5'-O-DMT-3'-O-(2-methoxyethyl)-2'-O-succinyl-N⁶-benzoyl adenosine was coupled to controlled pore glass (CPG). 3.41 g (4.10 mmol) of the succinate were dried overnight in a vacuum oven along with 4-
10 dimethylaminopyridine (DMAP), 2,2'-dithiobis (5-nitropyridine) (dTNP), triphenylphosphine (TPP), and pre-acid washed CPG (controlled pore glass). The following day, DMAP (4.10 mmol, 501 mg) and acetonitrile (37 mL) were added to the succinate. The mixture was "mixed" by a magnetic stirrer
15 under argon. In a separate flask, dTNP (4.10 mmol, 1.27g) was dissolved in acetonitrile (26 mL) and dichloromethane (11 mL) under argon. This reaction mixture was then added to the succinate. In another separate flask, TPP (4.10 mmol, 1.08 g) was dissolved in acetonitrile (37 mL) under argon. This
20 mixture was then added to the succinate/DMAP/dTNP reaction mixture. Finally, 33 g pre-acid washed LCA CPG (loading = 115.2 $\mu\text{mol/g}$) were added to the main reaction mixture, vortexed shortly and placed on shaker for approximately 20 hours. Removed from shaker after 20 hours and the loading was
25 checked. A small sample of CPG was washed with copious amounts of acetonitrile, dichloromethane, and then with ether. The initial loading was found to be 49 $\mu\text{mol/g}$. (2.9 mg of CPG were cleaved with trichloroacetic acid). The absorption of released trityl cation was read at 503 nm on a
30 spectrophotometer to determine the loading. The whole CPG sample was then washed as described above and dried under P_2O_5 overnight in vacuum oven. The following day, the CPG was capped with 50 mL CAP A (tetrahydrofuran/acetic anhydride) and

50 mL CAP B (tetrahydrofuran/pyridine/1-methyl imidazole) for approximately 1 hour on the shaker. The material was filtered and washed with dichloromethane and ether. The CPG was dried under P_2O_5 overnight in vacuum oven. After drying, 33.00 g of 5 CPG was obtained with a final loading of 66 $\mu\text{mol/g}$.

EXAMPLE 15**5'-O-DMT-3'-O-(2-methoxyethyl)-N²-isobutyryl-guanosine-2'-O-succinate**

5'-O-DMT-3'-O-(2-methoxyethyl)-N²-isobutyryl guanosine 10 was succinylated on the 2'-sugar position. 3.0 g (4.20 mmol) of the guanosine nucleoside were reacted with 10.5 mL dichloroethane, 631 mg (6.30 mmol) succinic anhydride, 585 μL (4.20 mmol) triethylamine, and 257 mg (2.10 mmol) 4-dimethylaminopyridine. The reactants were vortexed until 15 dissolved and placed in heating block at 55 °C for approximately 30 minutes. Completeness of reaction checked by thin layer chromatography (TLC). The reaction mixture was washed three times with cold 10% citric acid followed by three washes with water. The organic phase was removed and dried 20 under sodium sulfate. The succinylated nucleoside was dried under P_2O_5 overnight in vacuum oven.

EXAMPLE 16**5'-O-DMT-3'-O-methoxyethyl-N²-isobutyryl-guanosine-2'-O-succinoyl Linked LCA CPG**

25 Following succinylation, 5'-O-DMT-3'-O-(2-methoxyethyl)-2'-O-succinyl-N²-benzoyl guanosine was coupled to controlled pore glass (CPG). 3.42 g (4.20 mmol) of the succinate were dried overnight in a vacuum oven along with 4-dimethylaminopyridine (DMAP), 2,2'-dithiobis (5-nitro- 30 pyridine) (dTNP), triphenylphosphine (TPP), and pre-acid washed CPG (controlled pore glass). The following day, DMAP (4.20 mmol, 513 mg) and acetonitrile (37.5 mL) were added to

the succinate. The mixture was "mixed" by a magnetic stirrer under argon. In a separate flask, dTNP (4.20 mmol, 1.43 g) was dissolved in acetonitrile (26 mL) and dichloromethane (11 mL) under argon. This reaction mixture was then added to the
5 succinate. In another separate flask, TPP (4.20 mmol, 1.10 g) was dissolved in acetonitrile (37.5 mL) under argon. This mixture was then added to the succinate/DMAP/dTNP reaction mixture. Finally, 33.75 g pre-acid washed LCA CPG (loading = 115.2 $\mu\text{mol/g}$) were added to the main reaction mixture,
10 vortexed shortly and placed on shaker for approximately 20 hours. Removed from shaker after 20 hours and the loading was checked. A small sample of CPG was washed with copious amounts of acetonitrile, dichloromethane, and then with ether. The initial loading was found to be 64 $\mu\text{mol/g}$. (3.4 mg of CPG
15 were cleaved with trichloroacetic acid). The absorption of released trityl cation was read at 503 nm on a spectrophotometer to determine the loading. The CPG was then washed as described above and dried under P_2O_5 overnight in vacuum oven. The following day, the CPG was capped with 50
20 mL CAP A (tetrahydrofuran/acetic anhydride) and 50 mL CAP B (tetrahydrofuran/pyridine/1-methyl imidazole) for approximately 1 hour on a shaker. The material was filtered and washed with dichloromethane and ether. The CPG was dried under P_2O_5 overnight in vacuum oven. After drying, 33.75 g.
25 of CPG was isolated with a final loading of 72 $\mu\text{mol/g}$.

EXAMPLE 17

5'-O-DMT-3'-O-[hexyl-(6-phthalimido)]-uridine

2',3'-O-Dibutyl stannylene-uridine was synthesized according to the procedure of Wagner et. al., *J. Org. Chem.*,
30 **1974**, 39, 24. This compound was dried over P_2O_5 under vacuum for 12 hours. To a solution of this compound (29 g, 42.1 mmol) in 200 mL of anhydrous DMF were added (16.8 g, 55 mmol) of 6-bromohexyl phthalimide and 4.5 g of sodium iodide and the

mixture was heated at 130 °C for 16 hours under argon. The reaction mixture was evaporated, co-evaporated once with toluene and the gummy tar residue was applied on a silica column (500 g). The column was washed with 2 L of EtOAc followed by eluting with 10% methanol (MeOH):90% EtOAc. The product, 2'- and 3'-isomers of O-hexyl-6-N-phthalimido uridine, eluted as an inseparable mixture ($R_f=0.64$ in 10% MeOH in EtOAc). By ^{13}C NMR, the isomeric ration was about 55% of the 2' isomer and about 45% of the 3' isomer. The combined yield was 9.2 g (46.2%). This mixture was dried under vacuum and re-evaporated twice with pyridine. It was dissolved in 150 mL anhydrous pyridine and treated with 7.5 g of DMT-Cl (22.13 mmol) and 500 mg of dimethylaminopyridine (DMAP). After 2 hours, thin layer chromatography (TLC; 6:4 EtOAc:Hexane) indicated complete disappearance of the starting material and a good separation between 2' and 3' isomers ($R_f=0.29$ for the 2' isomer and 0.12 for the 3' isomer). The reaction mixture was quenched by the addition of 5 mL of CH_3OH and evaporated under reduced pressure. The residue was dissolved in 300 mL CH_2Cl_2 , washed successively with saturated NaHCO_3 followed by saturated NaCl solution. It was dried over Mg_2SO_4 and evaporated to give 15 g of a brown foam which was purified on a silica gel (500 g) to give 6.5 g of the 2'-isomer and 3.5 g of the 3' isomer.

25 **EXAMPLE 18**

5'-O-DMT-3'-O-[hexyl-(6-phthalimido)]-uridine-2'-O-(2-cyanoethyl-N,N,-diisopropyl) phosphoramidite

5'-DMT-3'-O-[hexyl-(6-phthalimido)]uridine (2 g, 2.6 mmol) was dissolved in 20 mL anhydrous CH_2Cl_2 . To this solution diisopropylaminotetrazolide (0.2 g, 1.16 mmol) and 2.0 mL 2-cyanoethyl-N,N,N',N'-tetraisopropyl phosphoramidite (6.3 mmol) were added with stirred overnight. TLC (1:1 EtOAc/hexane) showed complete disappearance of starting

material. The reaction mixture was transferred with CH_2Cl_2 and washed with saturated NaHCO_3 (100 mL), followed by saturated NaCl solution. The organic layer was dried over anhydrous Na_2SO_4 and evaporated to yield 3.8 g of a crude product, which
5 was purified in a silica column (200 g) using 1:1 hexane/ EtOAc to give 1.9 g (1.95 mmol, 74% yield) of the desired phosphoramidite.

EXAMPLE 19

**Preparation of 5'-O-DMT-3'-O-[hexyl-(6-phthalimido)]-uridine-
10 2'-O-succinoyl-aminopropyl CPG**

Succinylated and capped aminopropyl controlled pore glass (CPG; 500Å pore diameter, aminopropyl CPG, 1.0 grams prepared according to Damha *et. al.*, *Nucl. Acids Res.* **1990**, 18, 3813.) was added to 12 mL anhydrous pyridine in a 100 mL
15 round-bottom flask. 1-(3-Dimethylaminopropyl)-3-ethyl-carbo-diimide (DEC; 0.38 grams, 2.0 mmol), triethylamine (TEA; 100 μl , distilled over CaH_2), dimethylaminopyridine (DMAP; 0.012 grams, 0.1 mmol) and nucleoside 5'-O-DMT-3'-O-[hexyl-(6-phthalimido)]uridine (0.6 grams, 0.77 mmol) were added under
20 argon and the mixture shaken mechanically for 2 hours. Additional nucleoside (0.20 grams) was added and the mixture shaken for 24 hours. The CPG was filtered off and washed successively with dichloromethane, triethylamine, and dichloromethane. The CPG was then dried under vacuum,
25 suspended in 10 mL piperidine and shaken 15 minutes. The CPG was filtered off, washed thoroughly with dichloromethane and again dried under vacuum. The extent of loading (determined by spectrophotometric assay of DMT cation in 0.3 M p-toluenesulfonic acid at 498 nm) was approximately 28 $\mu\text{mol/g}$.
30 The 5'-O-(DMT)-3'-O-[hexyl-(6-phthalimido)] uridine-2'-O-succinyl-aminopropyl controlled pore glass was used to synthesize the oligomers in an ABI 380B DNA synthesizer using phosphoramidite chemistry standard conditions. A four base

oligomer 5'-GACU'-3' was used to confirm the structure of 3'-O-hexylamine tether introduced into the oligonucleotide by NMR. As expected a multiplet signal was observed between 1.0-1.8 ppm in ¹H NMR.

5 EXAMPLE 20

5'-O-DMT-3'-O-[hexylamino]-uridine

5'-O-(DMT)-3'-O-[hexyl-(6-phthalimido)] uridine (4.5 grams, 5.8 mmol) is dissolved in 200 mL methanol in a 500 mL flask. Hydrazine (1 ml, 31 mmol) is added to the stirring
10 reaction mixture. The mixture is heated to 60-65 °C in an oil bath and refluxed 14 hours. The solvent is evaporated in vacuo and the residue is dissolved in dichloromethane (250 mL) and extracted twice with an equal volume NH₄OH. The organic layer is evaporated to yield the crude product which NMR
15 indicates is not completely pure. R_f=0 in 100% ethyl acetate. The product is used in subsequent reactions without further purification.

EXAMPLE 21

3'-O-[Propyl-(3-phthalimido)]-adenosine

20 To a solution of adenosine (20.0 g, 75 mmol) in dry dimethylformamide (550 ml) at 5 °C was added sodium hydride (60% oil, 4.5 g, 112 mmol). After one hour, N-(3-bromopropyl)phthalimide (23.6 g, 86 mmol) was added and the temperature was raised to 30 °C and held for 16 hours. Ice
25 is added and the solution evaporated in vacuo to a gum. The gum was partitioned between water and ethyl acetate (4 x 300 mL). The organic phase was separated, dried, and evaporated in vacuo and the resultant gum chromatographed on silica gel (95/5 CH₂Cl₂/MeOH) to give a white solid (5.7 g) of the 2'-O-
30 (propylphthalimide)adenosine. Thee fractions containing the 3'-O-(propylphthalimide)adenosine were chromatographed a second time on silica gel using the same solvent system.

Crystallization of the 2'-O-(propylphthalimide)-adenosine fractions from methanol gave a crystalline solid, m.p. 123-124C. ¹H NMR (400 MHz: DMSO-d₆) δ 1.70 (m, 2H, CH₂), 3.4-3.7 (m, 6H, C₅, CH₂, OCH₂, Phth CH₂), 3.95 (q, 1H, C₄H), 4.30 (q, 1H, C₅H), 4.46 (t, 1H, C₂H), 5.15 (d, 1H, C₃OH), 5.41 (t, 1H, C₅OH), 5.95 (d, 1H, C₁H) 7.35 (s, 2H, NH₂), 7.8 (brs, 4H, Ar), 8.08 (s, 1H, C₂H) and 8.37 (s, 1H, C₈H). Anal. Calcd. C₂₁H₂₂N₆O₆: C, 55.03; H, 4.88; N, 18.49. Found: C, 55.38; H, 4.85; N, 18.46.

10 Crystallization of the 3'-O-(propylphthalimide)-adenosine fractions from H₂O afforded an analytical sample, m.p. 178-179C. ¹H NMR (400 MHz: DMSO-d₆) δ 5.86 (d, 1H, H-1').

EXAMPLE 22

3'-O-[Propyl-(3-phthalimido)]-N6-benzoyl-adenosine

15 3'-O-(3-propylphthalimide)adenosine is treated with benzoyl chloride in a manner similar to the procedure of Gaffney, et al., *Tetrahedron Lett.* **1982**, 23, 2257. Purification of crude material by chromatography on silica gel (ethyl acetate-methanol) gives the title compound.

20 EXAMPLE 23

3'-O-[Propyl-(3-phthalimido)]-5'-O-DMT-N6-benzoyl-adenosine

To a solution of 3'-O-(propyl-3-phthalimide)-N⁶-benzoyl-adenosine (4.0 g) in pyridine (250 ml) is added DMT-Cl (3.3 g). The reaction is stirred for 16 hours. The reaction
25 is added to ice/water/ethyl acetate, the organic layer separated, dried, and concentrated in vacuo and the resultant gum chromatographed on silica gel (ethyl acetate-methanol triethylamine) to give the title compound.

EXAMPLE 24

**3'-O-[Propyl-(3-phthalimido)]-5'-O-DMT-N⁶-Benzoyl-adenosine-
2'-O-(2-cyanoethyl-N,N-diisopropyl) phosphoramidite**

3'-O-(Propyl-3-phthalimide)-5'-O-DMT-N⁶-
5 benzoyl-adenosine is treated with (β-cyanoethoxy)chloro-N,N-diisopropylaminophosphane in a manner similar to the procedure of Seela, et al., *Biochemistry* **1987**, 26, 2233. Chromatography on silica gel (EtOAc/hexane) gives the title compound as a white foam.

10 **EXAMPLE 25**

3'-O-(Aminopropyl)-adenosine

A solution of 3'-O-(propyl-3-phthalimide)adenosine (8.8 g, 19 mmol), 95% ethanol (400 mL) and hydrazine (10 mL, 32 mmol) is stirred for 16 hrs at room temperature. The
15 reaction mixture is filtered and filtrate concentrated *in vacuo*. Water (150 mL) is added and acidified with acetic acid to pH 5.0. The aqueous solution is extracted with EtOAc (2 x 30 mL) and the aqueous phase is concentrated *in vacuo* to afford the title compound as a HOAc salt.

20 **EXAMPLE 26**

3'-O-[3-(N-trifluoroacetamido)propyl]-adenosine

A solution of 3'-O-(propylamino)adenosine in methanol (50 mL) and triethylamine (15 mL, 108 mmol) is treated with ethyl trifluoroacetate (18 mL, 151 mmol). The reaction is
25 stirred for 16 hrs and then concentrated *in vacuo* and the resultant gum chromatographed on silica gel (9/1, EtOAc/MeOH) to give the title compound.

EXAMPLE 27**N⁶-Dibenzoyl-3'-O-[3-(N-trifluoroacetamido)propyl]-adenosine**

3'-O-[3-(N-trifluoroacetamido)propyl]adenosine is treated as per Example 22 using a Jones modification wherein
5 tetrabutylammonium fluoride is utilized in place of ammonia hydroxide in the work up. The crude product is purified using silica gel chromatography (EtOAc/MeOH 1/1) to give the title compound.

EXAMPLE 28

10 **N⁶-Dibenzoyl-5'-O-DMT-3'-O-[3-(N-trifluoroacetamido)propyl]-adenosine**

DMT-Cl (3.6 g, 10.0 mmol) is added to a solution of N⁶-(dibenzoyl)-3'-O-[3-(N-trifluoroacetamido)propyl]adenosine in pyridine (100 mL) at room temperature and stirred for 16 hrs.
15 The solution is concentrated *in vacuo* and chromatographed on silica gel (EtOAc/TEA 99/1) to give the title compound.

EXAMPLE 29**N⁶-Dibenzoyl-5'-O-DMT-3'-O-[3-(N-trifluoroacetamido)propyl]-adenosine-2'-O-(2-cyanoethyl-N,N-diisopropyl) phosphoramidite**

20 A solution of N⁶-(dibenzoyl)-5'-O-(DMT)-3'-O-[3-(N-trifluoroacetamido)propyl]adenosine in dry CH₂Cl₂ is treated with bis-N,N-diisopropylamino cyanoethyl phosphite (1.1 equiv) and N,N-diisopropylaminotetrazolide (catalytic amount) at room temperature for 16 hrs. The reaction is concentrated *in vacuo*
25 and chromatographed on silica gel (EtOAc/hexane/TEA 6/4/1) to give the title compound.

EXAMPLE 30**3'-O-(butylphthalimido)-adenosine**

The title compound is prepared as per Example 21,
30 using N-(4-bromobutyl)phthalimide in place of the 1-bromopropane. Chromatography on silica gel (EtOAc-MeOH) gives

Table II

Physical characteristics of 3'-O-(2-methoxyethyl)
containing 2'-5' linked oligonucleotides.

		Expected Mass	Observed Mass	HPLC ² T _R (min.)	#Ods (260nm) Purified
5	17176	6440.743	6440.300	23.47	3006
	17177	6514.814	6513.910	23.67	3330
	17178	6482.814	6480.900	23.06	390
10	17179	6513.798	6513.560	23.20	3240
	17180	6588.879	6588.200	23.96	3222
	17181	6540.879	6539.930	23.01	
	21415	6662.976	6662.700	24.18	4008
	21416	6598.969	6597.800	23.01	3060
15	21945	1099.924	1099.300	19.92	121
	21663	1487.324	1486.800	20.16	71
	20389	1483.000	1482.000		62
	20390	4588.000	4591.000		151

²Conditions: Waters 600E with detector 991; Waters C4
20 column (3.9X300mm); Solvent A: 50 mM TEA-Ac, pH 7.0; B:
100% acetonitrile; 1.5 mL/min. flow rate; Gradient: 5% B for
first five minutes with linear increase in B to 60% during
the next 55 minutes.

EXAMPLE 51

25 T_m Studies on modified oligonucleotides

Oligonucleotides synthesized in Examples 49 and 50
were evaluated for their relative ability to bind to their
complementary nucleic acids by measurement of their melting
temperature (T_m). The melting temperature (T_m), a character-
30 istic physical property of double helices, denotes the
temperature (in degrees centigrade) at which 50% helical
(hybridized) versus coil (unhybridized) forms are present.
T_m is measured by using the UV spectrum to determine the
formation and breakdown (melting) of the hybridization
35 complex. Base stacking, which occurs during hybridization,
is accompanied by a reduction in UV absorption

(hypochromicity). Consequently, a reduction in UV absorption indicates a higher T_m . The higher the T_m , the greater the strength of the bonds between the strands.

Selected test oligonucleotides and their complementary
 5 nucleic acids were incubated at a standard concentration of
 4 μ M for each oligonucleotide in buffer (100 mM NaCl, 10 mM
 sodium phosphate, pH 7.0, 0.1 mM EDTA). Samples were heated
 to 90 °C and the initial absorbance taken using a Guilford
 Response II Spectrophotometer (Corning). Samples were then
 10 slowly cooled to 15 °C and then the change in absorbance at
 260 nm was monitored with heating during the heat
 denaturation procedure. The temperature was increased by 1
 degree °C/absorbance reading and the denaturation profile
 analyzed by taking the 1st derivative of the melting curve.
 15 Data was also analyzed using a two-state linear regression
 analysis to determine the T_m 's. The results of these tests
 for the some of the oligonucleotides from Examples 49 and 50
 are shown in Table III below.

Table III

20 **T_m Analysis of Oligonucleotides**

ISIS #	Sequence (5'-3')	Backbone	T_m	# Mods	#2'-5' Linkages
11061	ATG-CAT-TCT-GCC-CCC-AAG-GA	P=S	61.4	0	0
25 17176	ATG-CAT-TCT-GCC-CCC-AAG-GA*	P=S	61.4	1	0
17177	ATG-CAT-TCT-GCC-CCC-AAG-G'A*	P=S	61.3	2	1
17178	ATG-CAT-TCT-GCC-CCC-AAG _o -G'A*	P=S/P=O	61.8	2	1
17179	A'TG-CAT-TCT-GCC-CCC-AAG-GA*	P=S	61.1	2	1
17180	A'TG-CAT-TCT-GCC-CCC-AAG-G'A*	P=S	61.0	3	2
30 17181	A _o TG-CAT-TCT-GCC-AAA-AAG _o -G'A*	P=S/P=O	61.8	3	2
21415	A'T'G-CAT-TCT-GCC-AAA-AAG-G'A*	P=S	61.4	4	3
21416	A _o T'G-CAT-TCT-GCC-AAA-AAG _o -G'A*	P=S/P=O	61.7	4	3

*All nucleosides with an asterisk contain 3'-O-(2-methoxyethyl).

EXAMPLE 52

NMR experiments on modified oligonucleotides comparison of 3',5' versus 2',5' internucleotide linkages and 2'-substituents versus 3'-substituents by NMR

5 The 400MHz ^1H spectrum of oligomer $\text{d}(\text{GAU}_2^*\text{CT})$, where $\text{U}_2^* = 2'\text{-O-aminohexyluridine}$ showed 8 signals between 7.5 and 9.0 ppm corresponding to the 8 aromatic protons. In addition, the anomeric proton of U^* appears as a doublet at 5.9 ppm with $J_{1',2'} = 7.5\text{Hz}$, indicative of C2'-endo sugar
10 puckering. The corresponding 2'-5' linked isomer shows a similar structure with $J_{1',2'} = 3.85\text{ Hz}$ at 5.75 ppm, indicating an RNA type sugar puckering at the novel modification site favorable for hybridization to an mRNA target. The proton spectrum of the oligomer $\text{d}(\text{GACU}_3^*)$, where $\text{U}_3^* = 3'\text{-O-hexylamine}$,
15 showed the expected 7 aromatic proton signals between 7.5 and 9.0 ppm and the anomeric proton doublet at 5.9 ppm with $J_{1',2'} = 4.4\text{ Hz}$. This suggests more of a C3'-endo puckering for the 3'-O-alkylamino compounds compared to their 2' analogs. ^{31}P NMR of these oligonucleotides showed the
20 expected 4 and 3 signals from the internucleotide phosphate linkages for $\text{d}(\text{GAU}^*\text{CT})$ and $\text{d}(\text{GACU}^*)$, respectively. 3'-5' Linked vs. 2'-5' linked have different retention times in RP HPLC and hence different lipophilicities, implying potentially different extent of interactions with cell
25 membranes.

EXAMPLE 53

T_a Analysis of 2',5'-linked oligonucleotides versus 3',5'-linked oligonucleotides

30 Thermal melts were done as per standardized literature procedures. Oligonucleotide identity is as follows:
Oligonucleotide A is a normal 3'-5' linked phosphodiester oligodeoxyribonucleotide of the sequence $\text{d}(\text{GGC TGU}^* \text{CTG CG})$ where the * indicates the attachment site of a 2'-

aminolinker. Oligonucleotide B is a normal 3'-5' linked phosphodiester oligoribonucleotide of the sequence d(GGC TGU* CTG CG) where the * indicates the attachment site of a 2'-aminolinker. Each of the ribonucleotides of the oligonucleotide, except the one bearing the * substituent, are 2'-O-methyl ribonucleotides. Oligonucleotide C has 2'-5' linkage at the * position in addition to a 3'-aminolinker at this site. The remainder of the oligonucleotide is a phosphodiester oligodeoxyribonucleotide of the sequence d(GGC TGU* CTG CG). The base oligonucleotide (no 2'-aminolinker) was not included in the study.

Table IIIa

OLIGONUCLEOTIDE		MODIFICATION	DNA TARGET	RNA TARGET
15	A	none	52.2	54.1
		2'-aminolinker	50.9	55.5
	B	none	51.5	72.3
		2'-aminolinker	49.8	69.3
20	C	none	NA	
		3'-aminolinker	42.7	51.7

The 2'-5' linkages demonstrated a higher melting temperature against an RNA target compared to a DNA target.

EXAMPLE 54**Snake Venom Phosphodiesterase and Liver Homogenate
Experiments on Oligonucleotide Stability**

The following oligonucleotides were synthesized following the procedure of Example 49.

Table IV
Modified Oligonucleotides
synthesized to evaluate stability

	ISIS #	Sequence (5'-3')	Backbone	Chemistry
5	22110	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -T [*]	P=O	3'-O-MOE
	22111	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -O [*]	P=O	3'-O-MOE
	22112	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -T [*]	P=S	3'-O-MOE
	22113	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -O [*]	P=S	3'-O-MOE
	22114	TTT-TTT-TTT-TTT-TTT _o -T _o T _o T _o T [*]	P=S/P=O	3'-O-MOE
10	22115	TTT-TTT-TTT-TTT-TTT _o -T _o T _o T _o -O [*]	P=S/P=O	3'-O-MOE

¹All nucleosides with an asterisk contain 3'-O-(2-methoxyethyl). All nucleosides with a # contain 2'-O-(2-methoxyethyl).

The oligonucleotides were purified following the procedure of Example 50 and analyzed for their structure.

Table V
Properties of Modified Oligonucleotides

	ISIS	#Sequence (5'-3') ¹	Expected Mass	Observed Mass	HPLC ² T _R (min.)	#Ods(260nm) Purified
20	22110	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -T [*]	6314.189	6315.880	20.39	174
	22111	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -O [*]	6004.777	5997.490	20.89	147
	22112	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -T [*]	6298.799	6301.730	25.92	224
	22113	TTT-TTT-TTT-TTT-TTT-T [*] T [*] T [*] -O [*]	6288.745	6286.940	24.77	209
25	22114	TTT-TTT-TTT-TTT-TTT _o -T _o T _o T _o T [*]	6234.799	6237.150	24.84	196
	22115	TTT-TTT-TTT-TTT-TTT _o -T _o T _o T _o -O [*]	6224.745	6223.780	23.30	340

¹All nucleosides with an asterisk contain 3'-O-(2-methoxyethyl). All nucleosides with a # contain 2'-O-(2-methoxy) ethyl. ²Conditions: Waters 600E with detector

991; Waters C4 column (3.9X300mm); Solvent A: 50 mM TEA-Ac, pH 7.0; B: 100% acetonitrile; 1.5 mL/min. flow rate; Gradient: 5% B for first five minutes with linear increase in B to 60% during the next 55 minutes.

EXAMPLE 55**3'-O-Aminopropyl modified oligonucleotides**

Following the procedures illustrated above for the synthesis of oligonucleotides, modified 3'-amidites were used in addition to conventional amidites to prepare the oligonucleotides listed in tables VI and VII. Nucleosides used include: N6-benzoyl-3'-O-propylphthalimido-A-2'-amidite, 2'-O-propylphthaloyl-A-3'-amidite, 2'-O-methoxyethyl-thymidine-3'-amidite (RIC, Inc.), 2'-O-MOE-G-3'-amidite (RI Chemical), 2'-O-methoxyethyl-5-methylcytidine-3'-amidite, 2'-O-methoxyethyl-adenosine-3'-amidite (RI Chemical), and 5-methylcytidine-3'-amidite. 3'-propylphthalimido-A and 2'-propylphthalimido-A were used as the LCA-CPG solid support. The required amounts of the amidites were placed in dried vials, dissolved in acetonitrile (unmodified nucleosides were made into 1M solutions and modified nucleosides were 100 mg/mL), and connected to the appropriate ports on a Millipore Expedite™ Nucleic Acid Synthesis System. Solid support resin (60 mg) was used in each column for 2X1 µmole scale synthesis (2 columns for each oligo were used). The synthesis was run using the IBP-PS(1 µmole) coupling protocol for phosphorothioate backbones and CSO-8 for phosphodiester. The trityl reports indicated normal coupling results.

After synthesis the oligonucleotides were deprotected with conc. ammonium hydroxide(aq) containing 10% of a solution of 40% methylamine (aq) at 55 °C for approximately 16 hrs. Then they were evaporated, using a Savant AS160 Automatic SpeedVac, (to remove ammonia) and filtered to remove the CPG-resin. The crude samples were analyzed by MS, HPLC, and CE. Then they were purified on a Waters 600E HPLC system with a 991 detector using a Waters C4 Prep. scale column (Alice C4 Prep.) and the following solvents: A: 50 mM TEA-Ac, pH 7.0 and B: acetonitrile utilizing the AMPREP20 method. After purification the

oligonucleotides were evaporated to dryness and then detritylated with 80% acetic acid at room temp. for approximately 30 min. Then they were evaporated. The oligonucleotides were dissolved in conc. ammonium hydroxide and run through a column containing Sephadex G-25 using water as the solvent and a Pharmacia LKB SuperFrac fraction collector. The resulting purified oligonucleotides were evaporated and analyzed by MS, CE, and HPLC.

Table VI

Oligonucleotides bearing Aminopropyl Substituents

ISIS #	Sequence (5'-3') ¹	Backbone
23185-1	A* <u>TG</u> -CAT-TCT-GCC-CCC-AAG-GA*	P=S
23186-1	A* <u>TG</u> - <u>CAT</u> -TCT-GCC-CCC-AAG-GA*	P=S
15 23187-1	A* <u>TG</u> - <u>CAT</u> -TCT-GCC-CCC-AAG-GA*	P=S/P=O
23980-1	A* <u>TG</u> - <u>CAT</u> -TCT-GCC-CCC-AAG-GA*	P=S/P=O
23981-1	A* <u>TG</u> - <u>CAT</u> -TCT-GCC-CCC-AAG-GA*	P=S
23982-1	A* <u>TG</u> - <u>CAT</u> -TCT-GCC-CCC-AAG-GA*	P=S

¹All underlined nucleosides bear a 2'-O-methoxyethyl substituent; internucleotide linkages in PS/PO oligonucleotides are indicated by subscript >s= and >o= notations respectively; A* = 3'-aminopropyl-A; A* = 2'-aminopropyl-A; C = 5-methyl-C

Table VII

Aminopropyl Modified Oligonucleotides

ISIS #	Expected Mass (g/mol)	Observed Mass (g/mol)	HPLC Retention Time (min)	CE Retention Time (min)	Crude Yield (Ods)	Final Yield (Ods)
23185-1	6612.065	6610.5	23.19	5.98	948	478
23186-1	7204.697	7203.1	24.99	6.18	1075	379
23187-1	7076.697	7072.33	23.36	7.56	838	546
23980-1	7076.697	7102.31	23.42	7.16	984	373
23981-1	7204.697	7230.14	25.36	7.18	1170	526
23982-1	6612.065	6635.71	23.47	7.31	1083	463

- 91 -

ISIS-4186

EXAMPLE 56**In vivo stability of modified oligonucleotides**

The in vivo stability of selected modified oligonucleotides synthesized in Examples 49 and 55 was determined in 5 BALB/c mice. Following a single i.v. administration of 5 mg/kg of oligonucleotide, blood samples were drawn at various time intervals and analyzed by CGE. For each oligonucleotide tested, 9 male BALB/c mice (Charles River, 10 Wilmington, MA) weighing about 25 g were used. Following a one week acclimatization the mice received a single tail-vein injection of oligonucleotide (5 mg/kg) administered in phosphate buffered saline (PBS), pH 7.0. One retro-orbital bleed (either at 0.25, 0.5, 2 or 4 h post-dose) and a 15 terminal bleed (either 1, 3, 8, or 24 h post-dose) were collected from each group. The terminal bleed (approximately 0.6-0.8 mL) was collected by cardiac puncture following ketamine/xylazine anesthesia. The blood 20 was transferred to an EDTA-coated collection tube and centrifuged to obtain plasma. At termination, the liver and kidneys were collected from each mouse. Plasma and tissue homogenates were used for analysis to determine intact oligonucleotide content by CGE. All samples were 25 immediately frozen on dry ice after collection and stored at -80C until analysis.

25 The CGE analysis indicated the relative nuclease resistance of 2',5'-linked oligomers compared to ISIS 11061 (Table III, Example 51) (uniformly 2'-deoxy-phosphorothioate oligonucleotide targeted to mouse c-raf). Because of the nuclease resistance of the 2',5'-linkage, 30 coupled with the fact that 3'-methoxyethoxy substituents are present and afford further nuclease protection the oligonucleotides ISIS 17176, ISIS 17177, ISIS 17178, ISIS 17180, ISIS 17181 and ISIS 21415 were found to be more

ISIS-4186

stable in plasma, while ISIS 11061 (Table III) was not. Similar observations were noted in kidney and liver tissue. This implies that 2',5'-linkages with 3'-methoxyethoxy substituents offer excellent nuclease resistance in plasma, kidney and liver against 5'-exonucleases and 3'-exonucleases. Thus oligonucleotides with longer durations of action can be designed by incorporating both the 2',5'-linkage and 3'-methoxyethoxy motifs into their structure. It was also observed that 2',5'-phosphorothioate linkages are more stable than 2',5'-phosphodiester linkages. A plot of the percentage of full length oligonucleotide remaining intact in plasma one hour following administration of an i.v. bolus of 5 mg/kg oligonucleotide is shown in Figure 4.

A plot of the percentage of full length oligonucleotide remaining intact in tissue 24 hours following administration of an i.v. bolus of 5 mg/kg oligonucleotide is shown in Figure 5.

CGE traces of test oligonucleotides and a standard phosphorothioate oligonucleotide in both mouse liver samples and mouse kidney samples after 24 hours are shown in Figure 6. As is evident from these traces, there is a greater amount of intact oligonucleotide for the oligonucleotides of the invention as compared to the standard seen in panel A. The oligonucleotide shown in panel B included one substituent of the invention at each of the 5' and 3' ends of a phosphorothioate oligonucleotide while the phosphorothioate oligonucleotide seen in panel C included one substituent of the invention at the 5' end and two at the 3' end. The oligonucleotide of panel D includes a substituent of the invention incorporated in a 2',5' phosphodiester linkage at both its 5' and 3' ends. While less stable than the oligonucleotide seen in panels B and C, it is more stable than the full phosphorothioate standard oligonucleotide of panel A.

EXAMPLE 57**Control of c-raf message in bEND cells using modified oligonucleotides**

In order to assess the activity of some of the
5 oligonucleotides, an in vitro cell culture assay was used
that measures the cellular levels of c-raf expression in
bEND cells.

Cells and Reagents

The bEnd.3 cell line, a brain endothelioma, was
10 obtained from Dr. Werner Risau (Max-Planck Institute).
Opti-MEM, trypsin-EDTA and DMEM with high glucose were
purchased from Gibco-BRL (Grand Island, NY). Dulbecco's
PBS was purchased from Irvine Scientific (Irvine, CA).
Sterile, 12 well tissue culture plates and Facsflow
15 solution were purchased from Becton Dickinson (Mansfield,
MA). Ultrapure formaldehyde was purchased from
Polysciences (Warrington, PA). NAP-5 columns were
purchased from Pharmacia (Uppsala, Sweden).

Oligonucleotide Treatment

20 Cells were grown to approximately 75 % confluency in 12
well plates with DMEM containing 4.5 g/L glucose and 10 %
FBS. Cells were washed 3 times with Opti-MEM pre-warmed to
37 °C. Oligonucleotide were premixed with a cationic lipid
(Lipofectin reagent, (GIBCO/BRL) and, serially diluted to
25 desired concentrations and transferred on to washed cells
for a 4 hour incubation at 37 °C. Media was then removed
and replaced with normal growth media for 24 hours for
northern blot analysis of mRNA.

Northern Blot Analysis

30 For determination of mRNA levels by Northern blot
analysis, total RNA was prepared from cells by the
guanidinium isothiocyanate procedure (Monia et al., Proc.
Natl. Acad. Sci. USA, 1996, 93, 15481-15484) 24 h after
initiation of oligonucleotide treatment. Total RNA was

isolated by centrifugation of the cell lysates over a CsCl cushion. Northern blot analysis, RNA quantitation and normalization to G#PDH mRNA levels were done according to a reported procedure (Dean and McKay, *Proc. Natl. Acad. Sci. USA*, **1994**, 91, 11762-11766). In bEND cells the 2-,5-linked-3'-O-methoxyethyl oligonucleotides showed reduction of *c-raf* message activity as a function of concentration. The fact that these modified oligonucleotides retained activity promises reduced frequency of dosing with these oligonucleotides which also show increased *in vivo* nuclease resistance. All 2',5'-linked oligonucleotides retained the activity of parent 11061 (Table III) oligonucleotide and improved the activity even further. A graph of the effect of the oligonucleotides of the present invention on *c-raf* expression (compared to control) in bEND cells is shown in Figure 7.

EXAMPLE 58

Synthesis of MMI-containing Oligonucleotides

a. Bis-2'-O-methyl MMI Building Blocks

The synthesis of MMI (*i.e.*, R = CH₃) dimer building blocks have been previously described (see, *e.g.*, Swayze, *et al.*, *Synlett* **1997**, 859; Sanghvi, *et al.*, *Nucleosides & Nucleotides* **1997**, 16 907; Swayze, *et al.*, *Nucleosides & Nucleotides* **1997**, 16, 971; Dimock, *et al.*, *Nucleosides & Nucleotides* **1997**, 16, 1629). Generally, 5'-O-(4,4'-dimethoxytrityl)-2'-O-methyl-3'-C-formyl nucleosides were condensed with 5'-O-(N-methylhydroxylamino)-2'-O-methyl-3'-O-TBDPS nucleosides using 1 equivalent of BH₃ pyridine/1 equivalent of pyridinium para-toluene sulfonate (PPTS) in 3:1 MeOH/THF. The resultant MMI dimer blocks were then deprotected at the lower part of the sugar with 15 equivalents of Et₃N-2HF in THF. Thus the T*G^{iBu} dimer unit was synthesized and

phosphitylated to give T*G(MMI) phosphoramidite. In a similar fashion, A^{Bz}*T(MMI) dimer was synthesized, succinylated and attached to controlled pore glass.

b. Oligonucleotide synthesis

5 Oligonucleotides were synthesized on a Perseptive Biosystems Expedite 8901 Nucleic Acid Synthesis System. Multiple 1- μ mol syntheses were performed for each oligonucleotide. A*_{MMI}T solid support was loaded into the column. Trityl groups were removed with trichloroacetic
10 acid (975 μ L over one minute) followed by an acetonitrile wash. The oligonucleotide was built using a modified thioate protocol. Standard amidites were delivered (210 μ L) over a 3 minute period in this protocol. The T*_{MMI}G amidite was double coupled using 210 μ L over a total of 20
15 minutes. The amount of oxidizer, 3H-1,2-benzodithiole-3-one-1,1-dioxide (Beaucage reagent, 3.4 g Beaucage reagent/200 mL acetonitrile), was 225 μ L (one minute wait step). The unreacted nucleoside was capped with a 50:50 mixture of tetrahydrofuran/acetic anhydride and
20 tetrahydrofuran/pyridine/1-methyl imidazole. Trityl yields were followed by the trityl monitor during the duration of the synthesis. The final DMT group was left intact. After the synthesis, the contents of the synthesis cartridge (1 μ mole) were transferred to a Pyrex vial and the
25 oligonucleotide was cleaved from the controlled pore glass (CPG) using 5 mL of 30% ammonium hydroxide (NH₄OH) for approximately 16 hours at 55 °C.

c. Oligonucleotide Purification

30 After the deprotection step, the samples were filtered from CPG using Gelman 0.45 μ m nylon acrodisc syringe filters. Excess NH₄OH was evaporated away in a Savant AS160 automatic SpeedVac. The crude yield was measured on a Hewlett Packard 8452A Diode Array Spectrophotometer at 260 nm. Crude samples were then

analyzed by mass spectrometry (MS) on a Hewlett Packard electrospray mass spectrometer. Trityl-on oligonucleotides were purified by reverse phase preparative high performance liquid chromatography (HPLC). HPLC conditions were as follows: Waters 600E with 991 detector; Waters Delta Pak C4 column (7.8X300mm); Solvent A: 50 mM triethylammonium acetate (TEA-Ac), pH 7.0; B: 100% acetonitrile; 2.5 mL/min flow rate; Gradient: 5% B for first five minutes with linear increase in B to 60% during the next 55 minutes. Fractions containing the desired product (retention time = 41 min. for DMT-ON-16314; retention time = 42.5 min. for DMT-ON-16315) were collected and the solvent was dried off in the SpeedVac. Oligonucleotides were detritylated in 80% acetic acid for approximately 60 minutes and lyophilized again. Free trityl and excess salt were removed by passing detritylated oligonucleotides through Sephadex G-25 (size exclusion chromatography) and collecting appropriate samples through a Pharmacia fraction collector. The solvent was again evaporated away in a SpeedVac. Purified oligonucleotides were then analyzed for purity by CGE, HPLC (flow rate: 1.5 mL/min; Waters Delta Pak C4 column, 3.9X300mm), and MS. The final yield was determined by spectrophotometer at 260 nm.

The synthesized oligonucleotides and their physical characteristics are shown, respectively, in Tables VIII and IX. All nucleosides with an asterisk contain MMI linkage.

Table VIII

**ICAM-1 Oligonucleotides Containing MMI Dimers Synthesized
for in Vivo Nuclease and Pharmacology Studies.**

	ISIS #	Sequence (5'-3')	Backbone	2'-Chemistry
5	16314	TGC ATC CCC CAG GCC ACC A*T	P=S, MMI	Bis-2'-OMe-MMI, 2'-H
	16315	T*GC ATC CCC CAG GCC ACC A*T	P=S, MMI	Bis-2'-OMe-MMI, 2'-H
10	3082	TGC ATC CCC CAG GCG ACC AT	P=S	2'-H, single
	mismatch			
	13001	TGC ATC CCC CAG GCC ACC AT	P=S	2'-H

Table IX

15 **Physical Characteristics of MMI Oligomers
Synthesized for Pharmacology, and In Vivo Nuclease Studies**

	ISIS #	Sequence (5'-3')	Expected Mass (g)	Observed Mass (g)	HPLC Time
20	16314	TGC ATC CCC CAG GCC ACC A*T	6295	6297	23.9
	16315	T*G C ATC CCC CAG GCC ACC A*T	6302	6303	24.75

25 HPLC Conditions: Waters 600E with detector 991;
Waters C4 column (3.9X300mm); Solvent A: 50 mM TEA-Ac, pH
7.0; B: 100% acetonitrile; 1.5 mL/min. flow rate;
Gradient: 5% B for first five minutes with linear increase
in B to 60% during the next 55 minutes.

EXAMPLE 59**Synthesis of Sp Terminal Oligonucleotide****a. 3'-O-t-Butyldiphenylsilyl-thymidine (1)**

5'-O-Dimethoxytritylthymidine is silylated with 1
5 equivalent of t-butyldiphenylsilyl chloride (TBDPSCl) and 2
equivalents of imidazole in DMF solvent at room
temperature. The 5'-protecting group is removed by
treating with 3% dichloroacetic acid in CH₂Cl₂.

10 **b. 5'-O-Dimethoxytrityl-thymidin-3'-O-yl-N,N-
diisopropylamino (S-pivaloyl-2-mercaptoethoxy)
phosphoramidite (2)**

5'-O-Dimethoxytrityl thymidine is treated with
bis-(N,N-diisopropylamino)-S-pivaloyl-2-mercaptoethoxy
phosphoramidite and tetrazole in CH₂Cl₂/CH₃CN as described
15 by Guzaev et al., *Bioorganic & Medicinal Chemistry Letters*
1998, 8, 1123) to yield the title compound.

**c. 5'-O-Dimethoxytrityl-2'-deoxy-adenosin-3'-O-
yl-N,N-diisopropylamino (S-pivaloyl-2-mercapto ethoxy)
phosphoramidite (3)**

20 5'-O-Dimethoxytrityl-N-6-benzoyl-2'-deoxy-
adenosine is phosphitylated as in the previous example to
yield the desired amidite.

**d. 3'-O-t-Butyldiphenylsilyl-2'-deoxy-N₂-
isobutyryl-guanosine (4)**

25 5'-O-Dimethoxytrityl-2'-deoxy-N₂-isobutyryl-
guanosine is silylated with TBDPSCl and imidazole in DMF.
The 5'-DMT is then removed with 3% DCA in CH₂Cl₂.

e. T_(sp)G dimers and T_(s) Phosphoramidite

30 Compounds 4 and 2 are condensed (1:1 equivalents)
using 1H-tetrazole in CH₃CN solvent followed by
sulfurization employing Beaucage reagent (see, e.g., Iyer,
et al., *J. Org. Chem.* 1990, 55, 4693). The dimers (TG) are
separated by column chromatography and the silyl group is

deprotected using t-butyl ammonium fluoride/THF to give Rp and Sp dimers of T₃G. Small amounts of these dimers are completely deprotected and treated with either P1 nuclease or snake venom phosphodiesterase. The R isomer is
5 resistant to P1 nuclease and hydrolyzed by SVPD. The S isomer is resistant to SVPD and hydrolyzed P1 nuclease. The Sp isomer of the fully protected T₃G dimer is phosphitylated to give DMT-T-Sp-G-phosphoramidite.

f. A₃T Dimers and Solid Support Containing A₃T

10 Dimer

Compounds **3** and **1** are condensed using 1H-tetrazole in CH₃CN solvent followed by sulfurization to give AT dimers. The dimers are separated by column chromatography and the silyl group is deprotected with TBAF/THF. The
15 configurational assignments are done generally as in the previous example. The Sp isomer is then attached to controlled pore glass according to standard procedures to give DMT-A_{Sp}-T-CPG oligomerization with chirally pure Sp dimer units at the termini.

20 g. Oligonucleotide Synthesis

The oligonucleotide having the sequence T*GC ATC CCC CAG GCC ACC A*T is synthesized, where T*G and A*T represent chiral Sp dimer blocks described above. DMT-A_{Sp}-T-CPG is taken in the synthesis column and the next 16b
25 residues are built using standard phosphorothioate protocols and 3H-1,2-benzodithiol-3-one 1,1 dioxide as the sulfurizing agent. After building this 18 mer unit followed by final detritylation, the chiral Sp dimer phosphoramidite of 5'-DMT-T_{Sp}-G amidite is coupled to give
30 the desired antisense oligonucleotide. This compound is then deprotected in 30% NH₄OH over 16 hours and the oligomer purified in HPLC and desalted in Sephadex G-25 column. The final oligomer has Sp configuration at the 5'-

terminus and 3'-terminus and the interior has diastereomeric mixture of Rp and Sp configurations.

EXAMPLE 60

5 Evaluation of in vivo stability of MMI capped oligonucleotides mouse experiment procedures

For each oligonucleotide tested, 9 male BALB/c mice (Charles River, Wilmington, MA), weighing about 25 g was used (Crooke et al., *J. Pharmacol. Exp. Ther.*, 1996, 10 277, 923). Following a 1-week acclimation, mice received a single tail vein injection of oligonucleotide (5 mg/kg) administered in phosphate buffered saline (PBS), pH 7.0. One retro-orbital bleed (either 0.25, 0.5, 2 or 4 lv post dose) and a terminal bleed (either 1, 3, 8 or 24 h post 15 dose) were collected from each group. The terminal bleed (approximately 0.6-0.8 mL) was collected by cardiac puncture following ketamine/xylazine anesthesia. The blood was transferred to an EDTA-coated collection tube and centrifuged to obtain plasma. At termination, the liver 20 and kidneys were collected from each mouse. Plasma and tissues homogenates were used for analysis for determination of intact oligonucleotide content by CGE. All samples were immediately frozen on dry ice after collection and stored at -80 °C until analysis.

25 The capillary gel electrophoretic analysis indicated the relative nuclease resistance of MMI capped oligomers compared to ISIS 3082 (uniform 2'-deoxy phosphorothioate). Because of the resistance of MMI linkage to nucleases, the compound 16314 was found to be 30 stable in plasma while 3082 was not. However, in kidney and liver, the compound 16314 also showed certain amount of degradation. This implied that while 3'-exonuclease is important in plasma, 5'-exonucleases or endonucleases may be active in tissues. To distinguish between these two

possibilities, the data from 16315 was analyzed. In plasma as well as in tissues, (liver and kidney) the compound was stable in various time points. (1, 3 and 24 hrs.). The fact that no degradation was detected proved that 5'-
5 exonucleases and 3'-exonuclease are prevalent in tissues and endonucleases are not active. Furthermore, a single linkage (MMI or Sp thioate linkage) is sufficient as a gatekeeper against nucleases.

Control of ICAM-1 Expression Cells and Reagents

10 The bEnd.3 cell line, a brain endothelioma, was the kind gift of Dr. Werner Risau (Max-Planck Institute). Opti-MEM, trypsin-EDTA and DMEM with high glucose were purchased from Gibco-BRL (Grand Island, NY). Dulbecco's PBS was purchased from Irvine Scientific (Irvine, CA).
15 Sterile, 12 well tissue culture plates and Facsflow solution were purchased from Becton Dickinson (Mansfield, MA). Ultrapure formaldehyde was purchased from Polysciences (Warrington, PA). Recombinant human TNF- α was purchased from R&D Systems (Minneapolis, MN). Mouse
20 interferon- γ was purchased from Genzyme (Cambridge, MA). Fraction V, BSA was purchased from Sigma (St. Louis, MO). The mouse ICAM-1-PE, VCAM-1-FITC, hamster IgG-FITC and rat IgG_{2a}-PE antibodies were purchased from Pharmingen (San Diego, CA). Zeta-Probe nylon blotting membrane was
25 purchased from Bio-Rad (Richmond, CA). QuickHyb solution was purchased from Stratagene (La Jolla, CA). A cDNA labeling kit, Prime-a-Gene, was purchased from ProMega (Madison, WI). NAP-5 columns were purchased from Pharmacia (Uppsala, Sweden).

30 Oligonucleotide Treatment

Cells were grown to approximately 75 % confluency in 12 well plates with DMEM containing 4.5 g/L glucose and 10 % FBS. Cells were washed 3 times with Opti-MEM pre-warmed to 37 °C. Oligonucleotide was premixed with Opti-

MEM, serially diluted to desired concentrations and transferred onto washed cells for a 4 hour incubation at 37 °C. Media was removed and replaced with normal growth media with or without 5 ng/mL TNF- α and 200 U/mL
5 interferon- γ , incubated for 2 hours for northern blot analysis of mRNA or overnight for flow cytometric analysis of cell surface protein expression.

Flow Cytometry

After oligonucleotide treatment, cells were
10 detached from the plates with a short treatment of trypsin-EDTA (1-2 min.). Cells were transferred to 12x75 mm polystyrene tubes and washed with 2% BSA, 0.2% sodium azide in D-PBS at 4 °C. Cells were centrifuged at 1000 rpm in a Beckman GPR centrifuge and the supernatant was then
15 decanted. ICAM-1, VCAM-1 and the control antibodies were added at 1 ug/mL in 0.3 mL of the above buffer. Antibodies were incubated with the cells for 30 minutes at 4 °C in the dark, under gentle agitation. Cells were washed again as above and then resuspended in 0.3 mL of FACSFlow buffer
20 with 0.5 % ultrapure formaldehyde. Cells were analyzed on a Becton Dickinson FACScan. Results are expressed as percentage of control expression, which was calculated as follows:
$$\frac{((\text{CAM expression for oligonucleotide-treated cytokine induced cells}) - (\text{basal CAM expression}))}{((\text{cytokine-induced CAM expression}) - (\text{basal CAM expression}))} \times 100.$$

25 For the experiments involving cationic lipids, both basal and cytokine-treated control cells were pretreated with Lipofectin for 4 hours in the absence of oligonucleotides.

30 The results reveal the following: 1) Isis 3082 showed an expected dose response (25-200 nM); 2) Isis 13001 lost its ability to inhibit ICAM-1 expression as expected from a mismatch compound, thus proving an antisense mechanism; 3) 3'-MMI capped oligomer 16314 improved the

activity of 3082, and at 200 nM concentration, nearly twice as active as 3082; 4) 5'- and 3'- MMI capped oligomer is the most potent compound and it is nearly 4 to 5 times more efficacious than the parent compound at 100 and 200 nM concentrations. Thus, improved nuclease resistance increased the potency of the antisense oligonucleotides.

EXAMPLE 61

Control of H-ras Expression

10 Antisense oligonucleotides targeting the H-ras message were tested for their ability to inhibit production of H-ras mRNA in T-24 cells. For these test, T-24 cells were plated in 6-well plates and then treated with various escalating concentrations of oligonucleotide in the
15 presence of cationic lipid (Lipofectin, GIBCO) at the ratio of 2.5 µg/ml Lipofectin per 100 nM oligonucleotide. Oligonucleotide treatment was carried out in serum free media for 4 hours. Eighteen hours after treatment the total RNA was harvested and analyzed by northern blot for
20 H-ras mRNA and control gene G3PDH. The data is presented in figures 8 and 9 in bar graphs as percent control normalized for the G3PDH signal. As can be seen, the oligonucleotide having a single MMI linkage in each of the flank regions showed significant reduction of H-ras mRNA.

25 EXAMPLE 62

5-Lipoxygenase Analysis and Assays

A. Therapeutics

For therapeutic use, an animal suspected of having a disease characterized by excessive or abnormal supply of
30 5-lipoxygenase is treated by administering a compound of the invention. Persons of ordinary skill can easily determine optimum dosages, dosing methodologies and repetition rates. Such treatment is generally continued

until either a cure is effected or a diminution in the diseased state is achieved. Long term treatment is likely for some diseases.

B. Research Reagents

5 The oligonucleotides of the invention will also be useful as research reagents when used to cleave or otherwise modulate 5-lipoxygenase mRNA in crude cell lysates or in partially purified or wholly purified RNA preparations. This application of the invention is
10 accomplished, for example, by lysing cells by standard methods, optimally extracting the RNA and then treating it with a composition at concentrations ranging, for instance, from about 100 to about 500 ng per 10 Mg of total RNA in a buffer consisting, for example, of 50 mm phosphate, pH
15 ranging from about 4-10 at a temperature from about 30 to about 50 °C. The cleaved 5-lipoxygenase RNA can be analyzed by agarose gel electrophoresis and hybridization with radiolabeled DNA probes or by other standard methods.

C. Diagnostics

20 The oligonucleotides of the invention will also be useful in diagnostic applications, particularly for the determination of the expression of specific mRNA species in various tissues or the expression of abnormal or mutant RNA species. In this example, while the macromolecules target
25 a abnormal mRNA by being designed complementary to the abnormal sequence, they would not hybridize to normal mRNA. Tissue samples can be homogenized, and RNA extracted by standard methods. The crude homogenate or extract can be treated for example to effect cleavage of the target RNA.
30 The product can then be hybridized to a solid support which contains a bound oligonucleotide complementary to a region on the 5' side of the cleavage site. Both the normal and abnormal 5' region of the mRNA would bind to the solid support. The 3' region of the abnormal RNA, which is

cleaved, would not be bound to the support and therefore would be separated from the normal mRNA.

Targeted mRNA species for modulation relates to 5-lipoxygenase; however, persons of ordinary skill in the art will appreciate that the present invention is not so limited and it is generally applicable. The inhibition or modulation of production of the enzyme 5-lipoxygenase is expected to have significant therapeutic benefits in the treatment of disease. In order to assess the effectiveness of the compositions, an assay or series of assays is required.

D. In Vitro Assays

The cellular assays for 5-lipoxygenase preferably use the human promyelocytic leukemia cell line HL-60. These cells can be induced to differentiate into either a monocyte like cell or neutrophil like cell by various known agents. Treatment of the cells with 1.3% dimethyl sulfoxide, DMSO, is known to promote differentiation of the cells into neutrophils. It has now been found that basal HL-60 cells do not synthesize detectable levels of 5-lipoxygenase protein or secrete leukotrienes (a downstream product of 5-lipoxygenase). Differentiation of the cells with DMSO causes an appearance of 5-lipoxygenase protein and leukotriene biosynthesis 48 hours after addition of DMSO. Thus induction of 5-lipoxygenase protein synthesis can be utilized as a test system for analysis of oligonucleotides which interfere with 5-lipoxygenase synthesis in these cells.

A second test system for oligonucleotides makes use of the fact that 5-lipoxygenase is a "suicide" enzyme in that it inactivates itself upon reacting with substrate. Treatment of differentiated HL-60 or other cells expressing 5 lipoxygenase, with 10 μ M A23187, a calcium ionophore, promotes translocation of 5-lipoxygenase from the cytosol

to the membrane with subsequent activation of the enzyme. Following activation and several rounds of catalysis, the enzyme becomes catalytically inactive. Thus, treatment of the cells with calcium ionophore inactivates endogenous 5-lipoxygenase. It takes the cells approximately 24 hours to recover from A23187 treatment as measured by their ability to synthesize leukotriene B₄. Macromolecules directed against 5-lipoxygenase can be tested for activity in two HL-60 model systems using the following quantitative assays. The assays are described from the most direct measurement of inhibition of 5-lipoxygenase protein synthesis in intact cells to more downstream events such as measurement of 5-lipoxygenase activity in intact cells. A direct effect which oligonucleotides can exert on intact cells and which can be easily be quantitated is specific inhibition of 5-lipoxygenase protein synthesis. To perform this technique, cells can be labeled with ³⁵S-methionine (50 μ Ci/mL) for 2 hours at 37 °C to label newly synthesized protein. Cells are extracted to solubilize total cellular proteins and 5-lipoxygenase is immunoprecipitated with 5-lipoxygenase antibody followed by elution from protein A Sepharose beads. The immunoprecipitated proteins are resolved by SDS-polyacrylamide gel electrophoresis and exposed for autoradiography. The amount of immunoprecipitated 5-lipoxygenase is quantitated by scanning densitometry.

A predicted result from these experiments would be as follows. The amount of 5-lipoxygenase protein immunoprecipitated from control cells would be normalized to 100%. Treatment of the cells with 1 μ M, 10 μ M, and 30 μ M of the macromolecules of the invention for 48 hours would reduce immunoprecipitated 5-lipoxygenase by 5%, 25% and 75% of control, respectively.

Measurement of 5-lipoxygenase enzyme activity in cellular homogenates could also be used to quantitate the amount of enzyme present which is capable of synthesizing leukotrienes. A radiometric assay has now been developed
5 for quantitating 5-lipoxygenase enzyme activity in cell homogenates using reverse phase HPLC. Cells are broken by sonication in a buffer containing protease inhibitors and EDTA. The cell homogenate is centrifuged at 10,000 x g for 30 min and the supernatants analyzed for 5-lipoxygenase
10 activity. Cytosolic proteins are incubated with 10 μ M 14 C-arachidonic acid, 2mM ATP, 50 μ M free calcium, 100 μ g/mL phosphatidylcholine, and 50mM bis-Tris buffer, pH 7.0, for 5 min at 37 °C. The reactions are quenched by the addition of an equal volume of acetone and the fatty acids extracted
15 with ethyl acetate. The substrate and reaction products are separated by reverse phase HPLC on a Novapak C18 column (Waters Inc., Millford, MA). Radioactive peaks are detected by a Beckman model 171 radiochromatography detector. The amount of arachidonic acid converted into
20 di-HETE's and mono-HETE's is used as a measure of 5-lipoxygenase activity.

A predicted result for treatment of DMSO differentiated HL-60 cells for 72 hours with effective the macromolecules of the invention at 1 μ M, 10 μ M, and 30 μ M would be as
25 follows. Control cells oxidize 200 pmol arachidonic acid/5 min/ 10^6 cells. Cells treated with 1 μ M, 10 μ M, and 30 μ M of an effective oligonucleotide would oxidize 195 pmol, 140 pmol, and 60 pmol of arachidonic acid/5 min/ 10^6 cells respectively.

30 A quantitative competitive enzyme linked immunosorbant assay (ELISA) for the measurement of total 5-lipoxygenase protein in cells has been developed. Human 5-lipoxygenase expressed in *E. coli* and purified by extraction, Q-Sepharose, hydroxyapatite, and reverse phase HPLC is used

as a standard and as the primary antigen to coat microtiter plates. Purified 5-lipoxygenase (25 ng) is bound to the microtiter plates overnight at 4 °C. The wells are blocked for 90 min with 5% goat serum diluted in 20mM Tris!HCL
5 buffer, pH 7.4, in the presence of 150mM NaCl (TBS). Cell extracts (0.2% Triton X-100, 12,000 x g for 30 min.) or purified 5-lipoxygenase were incubated with a 1:4000 dilution of 5-lipoxygenase polyclonal antibody in a total volume of 100 µL in the microtiter wells for 90 min. The
10 antibodies are prepared by immunizing rabbits with purified human recombinant 5-lipoxygenase. The wells are washed with TBS containing 0.05% tween 20 (TBST), then incubated with 100 µL of a 1:1000 dilution of peroxidase conjugated goat anti-rabbit IgG (Cappel Laboratories, Malvern, PA) for
15 60 min at 25 °C. The wells are washed with TBST and the amount of peroxidase labeled second antibody determined by development with tetramethylbenzidine.

Predicted results from such an assay using a 30 mer oligonucleotide at 1 µM, 10 µM, and 30 µM would be 30
20 ng, 18 ng and 5 ng of 5-lipoxygenase per 10⁶ cells, respectively with untreated cells containing about 34 ng 5-lipoxygenase.

A net effect of inhibition of 5-lipoxygenase biosynthesis is a diminution in the quantities of leukotrienes released
25 from stimulated cells. DMSO-differentiated HL-60 cells release leukotriene B4 upon stimulation with the calcium ionophore A23187. Leukotriene B4 released into the cell medium can be quantitated by radioimmunoassay using commercially available diagnostic kits (New England
30 Nuclear, Boston, MA). Leukotriene B4 production can be detected in HL-60 cells 48 hours following addition of DMSO to differentiate the cells into a neutrophil-like cell. Cells (2 x 10⁵ cells/mL) will be treated with increasing concentrations of the macromolecule for 48-72 hours in the

presence of 1.3% DMSO. The cells are washed and resuspended at a concentration of 2×10^6 cell/mL in Dulbecco's phosphate buffered saline containing 1% delipidated bovine serum albumin. Cells are stimulated
5 with 10 μ M calcium ionophore A23187 for 15 min and the quantity of LTB₄ produced from 5×10^5 cell determined by radioimmunoassay as described by the manufacturer.

Using this assay the following results would likely be obtained with an oligonucleotide directed to the
10 5-LO mRNA. Cells will be treated for 72 hours with either 1 μ M, 10 μ M or 30 μ M of the macromolecule in the presence of 1.3% DMSO. The quantity of LTB₄ produced from 5×10^5 cells would be expected to be about 75 pg, 50 pg, and 35 pg, respectively with untreated differentiated cells
15 producing 75 pg LTB₄.

E. In Vivo Assay

Inhibition of the production of 5-lipoxygenase in the mouse can be demonstrated in accordance with the following protocol. Topical application of arachidonic
20 acid results in the rapid production of leukotriene B₄, leukotriene C₄ and prostaglandin E₂ in the skin followed by edema and cellular infiltration. Certain inhibitors of 5-lipoxygenase have been known to exhibit activity in this assay. For the assay, 2 mg of arachidonic acid is applied
25 to a mouse ear with the contralateral ear serving as a control. The polymorphonuclear cell infiltrate is assayed by myeloperoxidase activity in homogenates taken from a biopsy 1 hour following the administration of arachidonic acid. The edematous response is quantitated by measurement
30 of ear thickness and wet weight of a punch biopsy. Measurement of leukotriene B₄ produced in biopsy specimens is performed as a direct measurement of 5-lipoxygenase activity in the tissue. Oligonucleotides will be applied topically to both ears 12 to 24 hours prior to

administration of arachidonic acid to allow optimal activity of the compounds. Both ears are pretreated for 24 hours with either 0.1 μ mol, 0.3 μ mol, or 1.0 μ mol of the macromolecule prior to challenge with arachidonic acid.

5 Values are expressed as the mean for three animals per concentration. Inhibition of polymorphonuclear cell infiltration for 0.1 μ mol, 0.3 μ mol, and 1 μ mol is expected to be about 10%, 75% and 92% of control activity, respectively. Inhibition of edema is expected to be about

10 3%, 58% and 90%, respectively while inhibition of leukotriene B₄ production would be expected to be about 15%, 79% and 99%, respectively.

EXAMPLE 63

5'-O-DMT-2'-deoxy-2'-methylene-5-methyl uridine-3'-(2-
15 **cyanoethyl-N,N-diisopropyl) phosphoramidite**

2'-Deoxy-2'-methylene-3',5'-O-(tetraisopropyl disiloxane-1,3-diyl)-5-methyl uridine is synthesized following the procedures reported for the corresponding uridine derivative (Hansske, F.; Madej, D.; Robins, M.J.

20 Tetrahedron (1984) **40**, 125; Matsuda, A.; Takenusi, K.; Tanaka, S.; Sasaki, T.; Ueda, T. *J. Med. Chem.* (1991) **34**, 812; See also Cory, A. H.; Samano, V.; Robins, M. J.; Cory, J. G. 2'-Deoxy-2'-methylene derivatives of adenosine, guanosine, tubercidin, cytidine and uridine as inhibitors

25 of L1210 cell growth in culture. *Biochem. Pharmacol.* (1994), **47**(2), 365-71.)

It is treated with IM TBAF in THF to give 2'-deoxy-2'-methylene-5-methyl uridine. It is dissolved in pyridine and treated with DMT-Cl and stirred to give the

30 5'-O-DMT-2'-deoxy-2'-methylene-5-methyl uridine. This compound is treated with 2-cyanoethyl-N,N-diisopropyl phosphoramidite and diisopropylaminotetrazolide. In a similar manner the corresponding N-6 benzoyl adenosine, N-

4-benzoyl cytosine, N-2-isobutyryl guanosine phosphoramidite derivatives are synthesized.

EXAMPLE 63

Synthesis of 3'-O-4'-C-methyleneneribonucleoside

5 5'-O-DMT-3'-O-4'-C-methylene uridine and 5-methyl uridine are synthesized and phosphitylated according to the procedure of Obika et al. (Obika et al. *Bioorg. Med. Chem. Lett.* (1999) **9**, 515-158). The amidites are incorporated into oligonucleotides using the protocols described above.

10 EXAMPLE 64

Synthesis of 2'-methylene phosphoramidites

 5'-O-DMT-2'-(methyl)-3'-O-(2-cyanoethyl-N,N-diisopropylamine)-5-methyluridine-phosphoramidite, 5'-O-DMT-2'-(methyl)-N-6-benzoyl adenosine (3'-O-2-cyanoethyl-N,N-diisopropylamino) phosphoramidite, 5'-O-DMT-2'-(methyl)-N2-isobutyryl guanosine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidite and 5'-O-DMT-2'-(methyl)-N-4-benzoyl cytidine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidites were obtained by the
20 phosphitylation of the corresponding nucleosides. The nucleosides were synthesized according to the procedure described by Iribarren, Adolfo M.; Cicero, Daniel O.; Neuner, Philippe J. Resistance to degradation by nucleases of (2'S)-2'-deoxy-2'-C-methyloligonucleotides, novel
25 potential antisense probes. *Antisense Res. Dev.*, (1994), 4(2), 95-8; Schmit, Chantal; Bevierre, Marc-Olivier; De Mesmaeker, Alain; Altmann, Karl-Heinz. "The effects of 2'- and 3'-alkyl substituents on oligonucleotide hybridization and stability". *Bioorg. Med. Chem. Lett.* (1994),
30 4(16), 1969-74.

The phosphitylation is carried out by using the bisamidite procedure.

EXAMPLE 65

Synthesis of 2'-S-methyl phosphoramidites

5 5'-O-DMT-2'-S-(methyl)-3'-O-(2-cyanoethyl-N,N-diisopropylamine)-5-methyl uridine-phosphoramidite, 5'-O-DMT-2'-S(methyl)-N-6-benzoyl adenosine (3'-O-2-cyanoethyl-N,N-diisopropylamino) phosphoramidite, 5'-O-DMT-2'-S-(methyl)-N2-isoburytyl guanosine-3'-O-(2-cyanoethyl-N,N-
10 diisopropylamino) phosphoramidite and 5'-O-DMT-2'-S-(methyl)-N-4-benzoyl cytidine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidites were obtained by the phosphitylation of the corresponding nucleosides. The nucleosides were synthesized according to the procedure
15 described by Fraser et al. (Fraser, A.; Wheeler, P.; Cook, P.D.; Sanghvi, Y.S. *J. Heterocycl. Chem.* (1993) **31**, 1277-1287). The phosphitylation is carried out by using the bisamidite procedure.

20 EXAMPLE 66

Synthesis of 2'-O-methyl- β -D-arabinofuranosyl compounds

2'-O-Methyl- β -D-arabinofuranosyl-thymidine containing oligonucleotides were synthesized following the procedures of Gotfredson et. al. (Gotfredson, C.H. et. al.
25 *Tetrahedron Lett.* (1994) **35**, 6941-6944; Gotfredson, C.H. et. al. *Bioorg. Med. Chem.* (1996) **4**, 1217-1225). 5'-O-DMT-2'-ara-(O-methyl)-3'-O-(2-cyanoethyl-N,N-diisopropylamine)-5-methyl uridine-phosphoramidite, 5'-O-DMT-2'-ara-(O-methyl)-N-6-benzoyl adenosine (3'-O-2-cyanoethyl-N,N-
30 diisopropylamino) phosphoramidite, 5'-O-DMT-2'-ara-(O-methyl)-N2-isoburytyl guanosine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidite and 5'-O-DMT-2'-ara-(O-

5 methyl)-N-4-benzoyl cytidine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidites are obtained by the phosphitylation of the corresponding nucleosides. The nucleosides are synthesized according to the procedure described by Gotfredson, C.H. et. al. *Tetrahedron Lett.* (1994) **35**, 6941-6944; Gotfredson, C.H. et. al. *Bioorg. Med. Chem.* (1996) **4**, 1217-1225. The phosphitylation is carried out by using the bisamidite procedure.

10 **EXAMPLE 67**

Synthesis of 2'-fluoro- β -D-arabinofuranosyl compounds

2'-Fluoro- β -D-arabinofuranosyl oligonucleotides are synthesized following the procedures by Kois, P. et al., *Nucleosides Nucleotides* 12, 1093, 1993 and Damha et al., *J. Am. Chem. Soc.*, 120, 12976, 1998 and references cited therein. 5'-O-DMT-2'-ara-(fluoro)-3'-O-(2-cyanoethyl-N,N-diisopropylamine)-5-methyl uridine-phosphoramidite, 5'-O-DMT-2'-ara-(fluoro)-N-6-benzoyl adenosine (3'-O-2-cyanoethyl-N,N-diisopropylamino) phosphoramidite, 5'-O-DMT-2'-ara-(fluoro)-N2-isobutyryl guanosine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidite and 5'-O-DMT-2'-ara-(fluoro)-N-4-benzoyl cytidine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidites are obtained by the phosphitylation of the corresponding nucleosides. The nucleosides are synthesized according to the procedure described by Kois, P. et al., *Nucleosides Nucleotides* 12, 1093, 1993 and Damha et al., *J. Am. Chem. Soc.*, 120, 12976, 1998. The phosphitylation is carried out by using the bisamidite procedure.

EXAMPLE 68**Synthesis of 2'-hydroxyl- β -D-arabinofuranosyl compounds**

2'-Hydroxyl- β -D-arabinofuranosyl oligonucleotides are synthesized following the procedures by Resmini and
5 Pfleiderer *Helv. Chim. Acta*, 76, 158, 1993; Schmit et al.,
Bioorg. Med. Chem. Lett. 4, 1969, 1994 Resmini, M.;
Pfleiderer, W. Synthesis of arabinonucleic acid (tANA).
Bioorg. Med. Chem. Lett. (1994), 16, 1910.; Resmini,
Matthias; Pfleiderer, W. Nucleosides. Part LV. Efficient
10 synthesis of arabinoguanosine building blocks (*Helv. Chim. Acta*, (1994), 77, 429-34; and Damha et al., *J. Am. Chem. Soc.*, 1998, 120, 12976, and references cited therein).

5'-O-DMT-2'-ara-(hydroxy)-3'-O-(2-cyanoethyl-N,N-diisopropylamine)-5-methyl uridine-phosphoramidite, 5'-O-
15 DMT-2'-ara-(hydroxy)-N-6-benzoyl adenosine (3'-O-2-cyanoethyl-N,N-diisopropylamino) phosphoramidite, 5'-O-DMT-2'-ara-(hydroxy)-N2-isobutyryl guanosine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidite and 5'-O-DMT-2'-ara-(hydroxy)-N-4-benzoyl cytidine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidites are
20 obtained by the phosphitylation of the corresponding nucleosides. The nucleosides are synthesized according to the procedure described by Kois, P. et al., *Nucleosides Nucleotides* 12, 1093, 1993 and Damha et al., *J. Am. Chem. Soc.*, 120, 12976, 1998. The phosphitylation is carried out
25 by using the bisamidite procedure.

EXAMPLE 69**Synthesis of difluoromethylene compounds**

5'-O-DMT-2'-deoxy-2'-difluoromethylene-5-methyluridine-3'-(2-cyanoethyl-N,N-diisopropyl
30 phosphoramidite), 5'-O-DMT-2'-deoxy-2'-difluoromethylene-N-4-benzoyl-cytidine, 5'-O-DMT-2'-deoxy-2'-difluoromethylene-N-6-benzoyl adenosine, and 5'-O-DMT-2'-deoxy-2'-

difluoroethylene-N₂-isobutyryl guanosine are synthesized following the protocols described by Usman et. al. (U.S. Patent 5639649, June 17, 1997).

EXAMPLE 70

5 **Synthesis of 5'-O-DMT-2'-deoxy-2'-β-(O-acetyl)-2'-α-methyl-N6-benzoyl-adenosine-3'-(2-cyanoethyl-N,N-diisopropyl phosphoramidite**

5'-O-DMT-2'-deoxy-2'-β-(OH)-2'-α-methyl-adenosine is synthesized from the compound 5'-3'-protected-2'-keto-
10 adenosine (Rosenthal, Sprinzl and Baker, Tetrahedron Lett. 4233, 1970; see also Nucleic acid related compounds. A convenient procedure for the synthesis of 2'- and 3'-ketonucleosides is shown Hansske et al., Dep. Chem., Univ. Alberta, Edmonton, Can., Tetrahedron Lett. (1983), 24(15),
15 1589-92.) by Grigand addition of MeMgI in THF solvent, followed by separation of the isomers. The 2-β-(OH) is protected as acetate. 5'-3'-acetal group is removed, 5'-position dimethoxy, tritylated, N-6 position is benzoylated and then 3'-position is phosphitylated to give 5'-O-DMT-2'-
20 deoxy-2'-β-(O-acetyl)-2'-α-methyl-N6-benzoyl-adenosine-3'-(2-cyanoethyl-N,N-diisopropyl)phosphoramidite.

EXAMPLE 71

Synthesis of 5'-O-DMT-2'-α-ethynyl-N6-benzoyl-adenosine-3'-(2-cyanoethyl-N,N-diisopropyl phosphoramidite

25 5'-O-DMT-2'-deoxy-2'-β-(OH)-2'-α-ethynyl-adenosine is synthesized from the compound 5'-3'-protected-2'-keto-adenosine (Rosenthal, Sprinzl and Baker, Tetrahedron Lett. 4233, 1970) by Grigand addition of Ethynyl-MgI in THF solvent, followed by separation of the isomers. The 2'-β-
30 (OH) is removed by Robins' deoxygenation procedure (Robins et al., J. Am. Chem. Soc. (1983), 105, 4059-65. 5'-3'-

acetal group is removed, 5'-position dimethoxytritylated, N-6 position is benzoylated and then 3'-position is phosphitylated to give the title compound.

EXAMPLE 72**5 2'-O-(guaiacolyl)-5-methyluridine**

2-Methoxyphenol (6.2 g, 50 mmol) was slowly added to a solution of borane in tetrahydrofuran (1 M, 10 mL, 10 mmol) with stirring in a 100 mL bomb. Hydrogen gas evolved as the solid dissolved O-2,2'-anhydro-5-methyluridine
10 (1.2g, 5 mmol), and sodium bicarbonate (2.5 mg) were added and the bomb was sealed, placed in an oil bath and heated to 155 °C for 36 hours. The bomb was cooled to room temperature and opened. The crude solution was concentrated and the residue partitioned between water (200
15 mL) and hexanes (200 mL). The excess phenol was extracted into hexanes. The aqueous layer was extracted with ethyl acetate (3x200 mL) and the combined organic layer was washed once with water, dried over anhydrous sodium sulfate and concentrated. The residue was purified by silica gel
20 flash column chromatography using methanol:methylene chloride (1/10, v/v) as the eluent. Fractions were collected and the target fractions were concentrated to give 490 mg of pure product as a white solid. Rf= 0.545 in CH₂Cl₂/CH₃OH (10:1). MS/ES for C₁₇H₂₀N₂O₇, 364.4; Observed
25 364.9.

EXAMPLE 73**5'-Dimethoxytrityl-2'-O-(2-methoxyphenyl)-5-methyluridine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidite**

2'-O-(guaiacolyl)-5-methyl-uridine is treated with
30 1.2 equivalents of dimethoxytrityl chloride (DMT-Cl) in pyridine to yield the 5'-O-dimethoxy tritylated nucleoside. After evaporation of the pyridine and work up

(CH₂Cl₂/saturated NaHCO₃ solution) the compound is purified in a silica gel column. The 5'-protected nucleoside is dissolved in anhydrous methylene chloride and under argon atmosphere, N,N-diisopropylaminohydrotetrazolide (0.5
5 equivalents) and bis-N,N-diisopropylamino-2-cyanoethyl-phosphoramidite (2 equivalents) are added via syringe over 1 min. The reaction mixture is stirred under argon at room temperature for 16 hours and then applied to a silica column. Elution with hexane:ethylacetate (25:75) gives the
10 title compound.

EXAMPLE 74**5'-Dimethoxytrityl-2'-O-(2-methoxyphenyl)-5-methyluridine-3'-O-succinate**

The 5'-protected nucleoside from Example 73 is
15 treated with 2 equivalents of succinic anhydride and 0.2 equivalents of 4-N,N-dimethylaminopyridine in pyridine. After 2 hours the pyridine is evaporated, the residue is dissolved in CH₂Cl₂ and washed three times with 100 mL of 10% citric acid solution. The organic layer is dried over
20 anhydrous MgSO₄ to give the desired succinate. The succinate is then attached to controlled pore glass (CPG) using established procedures (Pon, R.T., Solid phase supports for oligonucleotide synthesis, in *Protocols for Oligonucleotides and Analogs*, S. Agrawal (Ed.), Humana
25 Press: Totawa, NJ, 1993, 465-496).

EXAMPLE 75**5'-Dimethoxytrityl-2'-O-(trans-2-methoxycyclohexyl)-5-methyl uridine**

2'-3'-O-Dibutylstannyl-5-methyl uridine (Wagner et
30 al., *J. Org. Chem.*, 1974, 39, 24) is alkylated with trans-2-methoxycyclohexyl tosylate at 70 °C in DMF. A 1:1

mixture of 2'-O- and 3'-O-(*trans*-2-methoxycyclohexyl)-5-methyluridine is obtained in this reaction. After evaporation of the DMF solvent, the crude mixture is dissolved in pyridine and treated with dimethoxytrityl-chloride (DMT-Cl) (1.5 equivalents). The resultant mixture is purified by silica gel flash column chromatography to give the title compound.

EXAMPLE 76

5'-Dimethoxytrityl-2'-O-(*trans*-2-methoxycyclohexyl)-5-methyluridine-3'-O-(2-cyanoethyl-N,N-diisopropylamino) phosphoramidite

5'-Dimethoxytrityl-2'-O-(*trans*-2-methoxycyclohexyl)-5-methyl uridine is phosphitylated according to the procedure described above to give the required phosphoramidite.

EXAMPLE 77

5'-Dimethoxytrityl-2'-O-(*trans*-2-methoxycyclohexyl)-5-methyluridine-3'-O-(succinyl-amino) CPG

5'-Dimethoxytrityl-2'-O-(*trans*-2-methoxycyclohexyl)-5-methyl uridine is succinylated and attached to controlled pore glass to give the solid support bound nucleoside.

EXAMPLE 78

***trans*-2-ureido-cyclohexanol**

Trans-2-amino-cyclohexanol (Aldrich) is treated with triphosgene in methylene chloride (1/3 equivalent). To the resulting solution, excess ammonium hydroxide is added to give after work up the title compound.

EXAMPLE 79**2'-O-(trans-2-uriedo-cyclohexyl)-5-methyl uridine**

Trans-2-uriedo-cyclohexanol (50 mmol) is added to a solution of borane in tetrahydrofuran (1 M, 10 mL, 10 mmol) while stirring in a 10 mL bomb. Hydrogen gas evolves as the reactant dissolves. 02,2'-Anhydro-5-methyluridine (5 mmol) and sodium bicarbonate (2.5 mg) are added to the bomb and sealed. Then it is heated to 140 for 72 hrs. The bomb is cooled to room temperature and opened. The crude material was worked up as illustrated above followed by purification by silica gel flash column chromatography to give the title compound.

EXAMPLE 80**5'-O-(Dimethoxytrityl)-2'-O-(trans-2-uriedo-cyclohexyl) 3'-O-(2-cyanoethyl, N,N,-diisopropyl) uridine phosphoramidite**

2'-O-(*trans*-2-uriedo-cyclohexyl)-5-methyl uridine tritylated at the 5'-OH and phosphitylated at the 3'-OH following the procedures illustrated in example 2 to give the title compound.

EXAMPLE 81**5'-O-dimethoxytrityl-2'-O-(trans-2-uriedo-cyclohexyl)-5-methyl-3'-O-(succinyl)-amino CPG uridine**

5'-O-dimethoxytrityl-2'-O-(*trans*-2-uriedo-cyclohexyl)-5-methyl uridine is succinylated and attached to CPG as illustrated above.

EXAMPLE 82**2'-O-(trans-2-methoxy-cyclohexyl) adenosine**

Trans-2-methoxycyclopentanol, *trans*-2-methoxycyclohexanol, *trans*-2-methoxy-cyclopentyl tosylate and *trans*-2-methoxy-cyclohexyl tosylate are prepared according

to reported procedures (Roberts, D.D., Hendrickson, W., *J. Org. Chem.*, **1967**, 34, 2415-2417; *J. Org. Chem.*, **1997**, 62, 1857-1859). A solution of adenosine (42.74 g, 0.16 mol) in dry dimethylformamide (800 mL) at 5 °C is treated with
5 sodium hydride (8.24 g, 60% in oil prewashed thrice with hexanes, 0.21 mol). After stirring for 30 min, *trans*-2-methoxycyclohexyl tosylate (0.16 mol) is added over 20 minutes at 5 °C. The reaction is stirred at room temperature for 48 hours, then filtered through Celite.
10 The filtrate is concentrated under reduced pressure followed by coevaporation with toluene (2x100 mL) to give the title compound.

EXAMPLE 83**N⁶-Benzoyl-2'-O-(*trans*-2-methoxycyclohexyl) adenosine**

15 A solution of 2'-O-(*trans*-2-methoxy-cyclohexyl) adenosine (0.056 mol) in pyridine (100 mL) is evaporated under reduced pressure to dryness. The residue is redissolved in pyridine (560 mL) and cooled in an ice water bath. Trimethylsilyl chloride (36.4 mL, 0.291 mol) is
20 added and the reaction is stirred at 5 °C for 30 minutes. Benzoyl chloride (33.6 mL, 0.291 mol) is added and the reaction is allowed to warm to 25 °C for 2 hours and then cooled to 5 °C. The reaction is diluted with cold water (112 mL) and after stirring for 15 min, concentrated
25 ammonium hydroxide (112 mL). After 30 min, the reaction is concentrated under reduced pressure (below 30 °C) followed by coevaporation with toluene (2x100 mL). The residue is dissolved in ethyl acetate-methanol (400 mL, 9:1) and the undesired silyl by-products are removed by filtration. The
30 filtrate is concentrated under reduced pressure and purified by silica gel flash column chromatography (800 g, chloroform-methanol 9:1). Selected fractions are combined,

concentrated under reduced pressure and dried at 25 °C/0.2 mmHg for 2 h to give the title compound.

EXAMPLE 84

N⁶-Benzoyl-5'-O-(dimethoxytrityl)-2'-O-(trans-2-methoxycyclohexyl) adenosine

A solution of N⁶-benzoyl-2'-O-(trans-2-methoxycyclohexyl) adenosine (0.285 mol) in pyridine (100 mL) is evaporated under reduced pressure to an oil. The residue is redissolved in dry pyridine (300 mL) and 4,4'-dimethoxy-
10 triphenylmethyl chloride (DMT-Cl, 10.9 g, 95%, 0.31 mol) added. The mixture is stirred at 25 °C for 16 h and then poured onto a solution of sodium bicarbonate (20 g) in ice water (500 mL). The product is extracted with ethyl acetate (2x150 mL). The organic layer is washed with brine
15 (50 mL), dried over sodium sulfate (powdered) and evaporated under reduced pressure (below 40 °C). The residue is chromatographed on silica gel (400 g, ethyl acetate-hexane 1:1. Selected fractions were combined, concentrated under reduced pressure and dried at 25 °C/0.2
20 mmHg to give the title compound.

EXAMPLE 85

[N⁶-Benzoyl-5'-O-(4,4'-dimethoxytrityl)-2'-O-(trans-2-methoxycyclohexyl) adenosine-3'-O-yl]-N,N-diisopropylamino-cyanoethoxy phosphoramidite

25 Phosphitylation of N⁶-benzoyl-5'-O-(dimethoxytrityl)-2'-O-(trans-2-methoxycyclohexyl) adenosine was performed as illustrated above to give the title compound.

EXAMPLE 86**General procedures for chimeric C3'-endo and C2'-endo modified oligonucleotide synthesis**

Oligonucleotides are synthesized on a PerSeptive Biosystems Expedite 8901 Nucleic Acid Synthesis System. Multiple 1-mmol syntheses are performed for each oligonucleotide. The 3'-end nucleoside containing solid support is loaded into the column. Trityl groups are removed with trichloroacetic acid (975 mL over one minute) followed by an acetonitrile wash. The oligonucleotide is built using a modified diester (P=O) or thioate (P=S) protocol.

Phosphodiester protocol

All standard amidites (0.1 M) are coupled over a 1.5 minute time frame, delivering 105 μ L material. All novel amidites are dissolved in dry acetonitrile (100 mg of amidite/1 mL acetonitrile) to give approximately 0.08-0.1 M solutions. The 2'-modified amidites (both ribo and arabino monomers) are double coupled using 210 μ L over a total of 5 minutes. Total coupling time is approximately 5 minutes (210 mL of amidite delivered). 1-H-tetrazole in acetonitrile is used as the activating agent. Excess amidite is washed away with acetonitrile. (1S)-(+)-(10-camphorsulfonyl) oxaziridine (CSO, 1.0 g CSO/8.72 mL dry acetonitrile) is used to oxidize (3 minute wait step) delivering approximately 375 μ L of oxidizer. Standard amidites are delivered (210 μ L) over a 3-minute period.

Phosphorothioate protocol

The 2'-modified amidite is double coupled using 210 μ L over a total of 5 minutes. The amount of oxidizer, 3H-1,2-benzodithiole-3-one-1,1-dioxide (Beaucage reagent, 3.4 g Beaucage reagent/200 mL acetonitrile), is 225 μ L (one minute wait step). The unreacted nucleoside is capped with

a 50:50 mixture of tetrahydrofuran/acetic anhydride and tetrahydrofuran/pyridine/1-methyl imidazole. Trityl yields are followed by the trityl monitor during the duration of the synthesis. The final DMT group is left intact. After
5 the synthesis, the contents of the synthesis cartridge (1 mmole) is transferred to a Pyrex vial and the oligonucleotide is cleaved from the controlled pore glass (CPG) using 30% ammonium hydroxide (NH₄OH, 5 mL) for approximately 16 hours at 55 °C.

10 **Oligonucleotide Purification**

After the deprotection step, the samples are filtered from CPG using Gelman 0.45 µm nylon acrodisc syringe filters. Excess NH₄OH is evaporated away in a Savant AS160 automatic speed vac. The crude yield is
15 measured on a Hewlett Packard 8452A Diode Array Spectrophotometer at 260 nm. Crude samples are then analyzed by mass spectrometry (MS) on a Hewlett Packard electrospray mass spectrometer. Trityl-on oligonucleotides are purified by reverse phase preparative high performance
20 liquid chromatography (HPLC). HPLC conditions are as follows: Waters 600E with 991 detector; Waters Delta Pak C4 column (7.8X300mm); Solvent A: 50 mM triethylammonium acetate (TEA-Ac), pH 7.0; Solvent B: 100% acetonitrile; 2.5 mL/min flow rate; Gradient: 5% B for first five minutes
25 with linear increase in B to 60% during the next 55 minutes. Fractions containing the desired product/s (retention time = 41 minutes for DMT-ON-16314; retention time = 42.5 minutes for DMT-ON-16315) are collected and the solvent is dried off in the speed vac. Oligonucleotides
30 are detritylated in 80% acetic acid for approximately 60 minutes and lyophilized again. Free trityl and excess salt are removed by passing detritylated oligonucleotides through Sephadex G-25 (size exclusion chromatography) and collecting appropriate samples through a Pharmacia fraction

collector. The solvent is again evaporated away in a speed vac. Purified oligonucleotides are then analyzed for purity by CGE, HPLC (flow rate: 1.5 mL/min; Waters Delta Pak C4 column, 3.9X300mm), and MS. The final yield is
5 determined by spectrophotometer at 260 nm.

Example 87

Rapid amplification of 5'-cDNA end (5' -RACE) and 3'-cDNA end (3'-RACE)

An internet search of the XREF database in the
10 National Center of Biotechnology Information (NCBI) yielded a 361 base pair (bp) human expressed sequenced tag (EST, GenBank accession #H28861), homologous to yeast RNase H (RNH1) protein sequenced tag (EST, GenBank accession #Q04740) and its chicken homologue (accession #D26340).
15 Three sets of oligonucleotide primers encoding the human RNase H EST sequence were synthesized. The sense primers were ACGCTGGCCGGGAGTCGAAATGCTTC (H1: SEQ ID NO: 6), CTGTTCCTGGCCACAGAGTCGCCTTGG (H3: SEQ ID NO: 7) and GGTCTTTCTGACCTGGAATGAGTGCAGAG (H5: SEQ ID NO: 8). The
20 antisense primers were CTTGCCTGGTTTCGCCCTCCGATTCTTGT (H2: SEQ ID NO: 9), TTGATTTTCATGCCCTTCTGAAACTTCCG (H4; SEQ ID NO: 10) and CCTCATCCTCTATGGCAAACCTTCTTAAATCTGGC (H6; SEQ ID NO: 11). The human RNase H 3' and 5' cDNAs derived from the EST sequence were amplified by polymerase chain
25 reaction (PCR), using human liver or leukemia (lymphoblastic Molt-4) cell line Marathon ready cDNA as templates, H1 or H3/AP1 as well as H4 or H6/AP2 as primers (Clontech, Palo Alto, CA). The fragments were subjected to agarose gel electrophoresis and transferred to
30 nitrocellulose membrane (Bio-Rad, Hercules CA) for confirmation by Southern blot, using ³²P-labeled H2 and H1 probes (for 3' and 5' RACE products, respectively, in accordance with procedures described by Ausubel et al.,

Current Protocols in Molecular Biology, Wiley and Sons, New York, NY., 1988. The confirmed fragments were excised from the agarose gel and purified by gel extraction (Qiagen, Germany), then subcloned into Zero-blunt vector
5 (Invitrogen, Carlsbad, CA) and subjected to DNA sequencing.

EXAMPLE 88

Screening of the cDNA library, DNA sequencing and sequence analysis

10 A human liver cDNA lambda phage Uni-ZAP library (Stratagene, La Jolla, CA) was screened using the RACE products as specific probes. The positive cDNA clones were excised into the pBluescript phagemid (Stratagene, La Jolla CA) from lambda phage and subjected to DNA sequencing with
15 an automatic DNA sequencer (Applied Biosystems, Foster City, CA) by Retrogen Inc. (San Diego, CA). The overlapping sequences were aligned and combined by the assembling programs of MacDNASIS v3.0 (Hitachi Software Engineering America, South San Francisco, CA). Protein
20 structure and subsequence analysis were performed by the program of MacVector 6.0 (Oxford Molecular Group Inc., Campbell, CA). A homology search was performed on the NCBI database by internet E-mail.

EXAMPLE 89

25 Northern blot and Southern blot analysis

Total RNA from different human cell lines (ATCC, Rockville, MD) was prepared and subjected to formaldehyde agarose gel electrophoresis in accordance with procedures described by Ausubel et al., Current Protocols in Molecular
30 Biology, Wiley and Sons, New York, NY, 1988, and transferred to nitrocellulose membrane (Bio-Rad, Hercules CA). Northern blot hybridization was carried out in

QuickHyb buffer (Stratagene, La Jolla, CA) with ^{32}P -labeled probe of full length RNase H cDNA clone or primer H1/H2 PCR-generated 322-base N-terminal RNase H cDNA fragment at 68°C for 2 hours. The membranes were washed twice with
5 0.1% SSC/0.1% SDS for 30 minutes and subjected to autoradiography. Southern blot analysis was carried out in 1X pre-hybridization/hybridization buffer (BRL, Gaithersburg, MD) with a ^{32}P -labeled 430 bp C-terminal restriction enzyme PstI/PvuII fragment or 1.7 kb full length cDNA probe at
10 60°C for 18 hours. The membranes were washed twice with 0.1% SSC/0.1% SDS at 60°C for 30 minutes, and subjected to autoradiography.

EXAMPLE 90

Expression and purification of the cloned RNase protein

15 The cDNA fragment coding the full RNase H protein sequence was amplified by PCR using 2 primers, one of which contains restriction enzyme NdeI site adapter and six histidine (his-tag) codons and 22 bp protein N terminal coding sequence. The fragment was cloned into expression
20 vector pET17b (Novagen, Madison, WI) and confirmed by DNA sequencing. The plasmid was transfected into E.coli BL21(DE3) (Novagen, Madison, WI). The bacteria were grown in M9ZB medium at 32°C and harvested when the OD_{600} of the culture reached 0.8, in accordance with procedures
25 described by Ausubel et al., *Current Protocols in Molecular Biology*, Wiley and Sons, New York, NY, 1988. Cells were lysed in 8M urea solution and recombinant protein was partially purified with Ni-NTA agarose (Qiagen, Germany). Further purification was performed with C4
30 reverse phase chromatography (Beckman, System Gold, Fullerton, CA) with 0.1% TFA water and 0.1% TFA acetonitrile gradient of 0% to 80% in 40 minutes as described by Deutscher, M. P., *Guide to Protein*

Purification, Methods in Enzymology 182, Academic Press, New York, NY, 1990. The recombinant proteins and control samples were collected, lyophilized and subjected to 12% SDS-PAGE as described by Ausubel et al. (1988) Current
5 Protocols in Molecular Biology, Wiley and Sons, New York, NY. The purified protein and control samples were resuspended in 6 M urea solution containing 20 mM Tris HCl, pH 7.4, 400 mM NaCl, 20% glycerol, 0.2 mM PMSF, 5 mM DTT, 10 µg/ml aprotinin and leupeptin, and refolded by dialysis
10 with decreasing urea concentration from 6 M to 0.5 M as well as DTT concentration from 5 mM to 0.5 mM as described by Deutscher, M. P., Guide to Protein Purification, Methods in Enzymology 182, Academic Press, New York, NY, 1990. The refolded proteins were concentrated (10 fold) by Centricon
15 (Amicon, Danvers, MA) and subjected to RNase H activity assay.

EXAMPLE 91

RNase H activity assay

³²P-end-labeled 17-mer RNA, GGGCGCCGTCGGTGTGG (SEQ
20 ID NO: 12) described by Lima, W. F. and Crooke, S. T., *Biochemistry*, 1997 36, 390-398, was gel-purified as described by Ausubel et al., *Current Protocols in Molecular Biology*, Wiley and Sons, New York, NY, 1988 and annealed with a tenfold excess of its complementary 17-mer
25 oligodeoxynucleotide or a 5-base DNA gapmer, i.e., a 17mer oligonucleotide which has a central portion of 5 deoxynucleotides (the "gap") flanked on both sides by 6 2'-methoxynucleotides. Annealing was done in 10 mM Tris HCl, pH 8.0, 10 mM MgCl, 50 mM KCl and 0.1 mM DTT to form one of
30 three different substrates: (a) single strand (ss) RNA probe, (b) full RNA/DNA duplex and (c) RNA/DNA gapmer duplex. Each of these substrates was incubated with protein samples at 37°C for 5 minutes to 2 hours at the

same conditions used in the annealing procedure and the reactions were terminated by adding EDTA in accordance with procedures described by Lima, W. F. and Crooke, S. T., *Biochemistry*, 1997, 36, 390-398. The reaction mixtures
5 were precipitated with TCA centrifugation and the supernatant was measured by liquid scintillation counting (Beckman LS6000IC, Fullerton, CA). An aliquot of the reaction mixture was also subjected to denaturing (8 M urea) acrylamide gel electrophoresis in accordance with
10 procedures described by Lima, W. F. and Crooke, S. T., *Biochemistry*, 1997, 36, 390-398 and Ausubel et al., *Current Protocols in Molecular Biology*, Wiley and Sons, New York, NY, 1988.

EXAMPLE 92

15 Effects of phosphorothioate substitution and substrate length on digestion by Human RNase H1 (See Table 4)

Oligoribonucleotides were preannealed with the complementary antisense oligodeoxynucleotide at 10 nM and 20 nM respectively and subjected to digestion by Human
20 RNase H1. The 17mer (RNA no.1) and 25 mer (RNA no.3) RNA sequences are derived from Harvy-RAS oncogen 51) and the 25 mer RNA contains the 17 mer sequence. The 20 mer (RNA no.2) sequence is derived from human hepatitis C virus core protein coding sequence (52). The initial rates were
25 determined as described in Materials and Methods, 1A: Comparison of the initial rates of cleavage of an RNA:phosphodiester (P=O) and an RNA:phosphorothioate (P=S) duplexes, and 1B: Comparison among duplexes of different sequences and lengths.

EXAMPLE 93

Effects of 2'-substitution and deoxy-gap size on digestion rates by human RNase H1 (See Table 5)

Substrate duplexes were hybridized and initial
5 rates were determined as shown in Table 4 and described in
Material and Methods. The 17mer RNA is the same used in
Table 4, and the 20mer RNA (UGGUGGGCAAUGGGCGUGUU, RNA no.4)
is derived from the protein kinase C-zeta (53) sequence.
The 17mer and 20mer P=S oligonucleotides were full
10 deoxyphosphorothioate containing no 2'-modifications. The
9, 7, 5, 4 and 3 deoxy gap oligonucleotides were 17mer
oligonucleotide with a central portion consisting of nine,
seven, five and four deoxynucleotides flanked on both sides
by 2'-methoexynucleotides (also see Figure 2). Boxed
15 sequences indicate the position of the 2'-methoxy-modified
residues. Dash-boxed sequence indicates the position of
the 2'-propoxy-modified residues.

EXAMPLE 94

Kinetic constants for RNase H1 cleavage of RNA:DNA duplexes

20 (See Table 6)

The RNA:DNA duplexes in Table 4 were used to
determine K_m and V_{max} of Human and *E.coli* RNase H1 as
described in the Materials and Methods section.

EXAMPLE 95

25 **Binding constants and specificity of RNase H's** (See Table
7)

K_d 's were determined as described in Materials and
methods. The K_d 's for *E. coli* RNase H1 was derived from
previously reported data (21). The competing substrates
30 (competitive inhibitors) used in the binding study are
divided into two categories: single-strand (ss)

oligonucleotides and oligonucleotide duplexes all with the 17mer sequence as in Table 4 (RNA No. 1). The single-strand oligonucleotides included: ssRNA, ssDNA, ss fully modified 2'-methoxy phosphodiester oligonucleotide (ss 2'-O-Me) and ss full phosphorothioate deoxyoligonucleotide (ss DNA, P=S). The duplex substrates include: DNA:DNA duplex, RNA:RNA duplex, DNA:fully modified 2' fluoro or fully modified 2'-methoxy oligonucleotide (DNA:2'-F or 2'-O-Me), RNA:2'-F or 2'-O-Me duplex. Dissociation constants are derived from ≥ 3 slopes of Lineweaver-Burk and /or Augustissson analysis. Estimated errors for the dissociation constants are 2 fold. Specificity is defined by dividing the K_d for a duplex by the K_d for an RNA:RNA duplex.

Table 4

A

	<i>RNA</i>	<i>Antisense</i>	<i>Initial Rate</i>
1	GGGCGCCGUCGGUGU	17mer P=O	1050 \pm 203
	GG		
1	GGGCGCCGUCGGUGU	17mer P=S	4034 \pm 266
	GG		

B

<i>RNA</i>	<i>RNA</i>	<i>Antisense</i>	<i>Initial Rate</i>
<i>No.</i>		<i>DNA</i>	<i>(pmol L⁻¹ min⁻¹)</i>
1	GGGCGCCGUCGGUGUGG	17mer P=O	1050 \pm 203
2	ACUCCACCAUAGUACACUCC	20mer P=O	1015 \pm 264
3	UGGUGGGCGCCGUCGGUGUGGGCAA	25mer P=O	1502 \pm 182

Table 5

<i>RNA No.</i>	<i>RNA</i>	<i>Antisense DNA</i>	<i>Initial Rate</i> ($\mu\text{mol L}^{-1}\text{min}^{-1}$)
1	17mer	CCACACCGACGGCGCCC	4034 ± 266
	17mer	CCACACCGACGGCGCCC	1081 ± 168
	17mer	CCACACCGACGGCGCCC	605 ± 81
	17mer	CCACACCGACGGCGCCC	330 ± 56
	17mer	CCACACCGACGGCGCCC	0
	17mer	CCACACCGACGGCGCCC	0
	17mer	CCACACCGACGGCGCCC	0
4*	20mer	AACACGCCCCATTGCCCCACCA	3400 ± 384
	20mer	AACACGCCCCATTGCCCCACCA	0

* Table legend for sequence

Table 6

<i>Substrates</i>	<i>Human RNase H</i>		<i>E. coli RNase HI</i>	
	<i>K_m</i>	($\text{nmol L}^{-1}\text{min}^{-1}$)	<i>K_m</i>	<i>V_{max}</i>
	(<i>nM</i>)		(<i>nM</i>)	($\text{nmol L}^{-1}\text{min}^{-1}$)
25mer Ras (RNA no.3):DNA (P=O)	35.4	1.907		
17mer Ras (RNA no.1):DNA (P=O)	56.1	1.961	385	38.8
17mer Ras (RNA no.1):DNA (P=S)	13.9	1.077		

Table 7

<i>Inhibitors</i>	<i>Human RNase H1</i>		<i>E. coli RNase H1</i>	
	<i>Kd (nM)</i>	<i>Specificity</i>	<i>Kd (nM)</i>	<i>Specificity</i>
DNA:2'-O-Me	458	5.8	3400	2.1
RNA:2'-O-Me	409	5.2	3100	1.9
RNA:RNA	79	1.0	1600	1.0
RNA:2'-F	76	1.0		
DNA:2'-F	99	1.3		
DNA:DNA	3608	45.7	176000	110.0
ssRNA	1400	17.7		
ssDNA	1506	19.6	942000	588.8
ss2'-O-Me	2304	29.2	118000	73.8
ssDNA, P=S	36	0.5	14000	8.8

PROCEDURES**PROCEDURE 1****ICAM-1 Expression*****Oligonucleotide Treatment of HUVECs***

5 Cells were washed three times with Opti-MEM (Life Technologies, Inc.) prewarmed to 37 °C. Oligonucleotides were premixed with 10 g/mL Lipofectin (Life Technologies, Inc.) in Opti-MEM, serially diluted to the desired concentrations, and applied to washed cells. Basal and
10 untreated (no oligonucleotide) control cells were also treated with Lipofectin. Cells were incubated for 4 h at 37 °C, at which time the medium was removed and replaced with standard growth medium with or without 5 mg/mL TNF- α 7 & D Systems). Incubation at 37 °C was continued until the
15 indicated times.

Quantitation of ICAM-1 Protein Expression by Fluorescence-activated Cell Sorter

Cells were removed from plate surfaces by brief trypsinization with 0.25% trypsin in PBS. Trypsin activity
20 was quenched with a solution of 2% bovine serum albumin and 0.2% sodium azide in PBS (+Mg/Ca). Cells were pelleted by centrifugation (1000 rpm, Beckman GPR centrifuge), resuspended in PBS, and stained with 3 l/10⁵ cells of the ICAM-1 specific antibody, CD54-PE (Pharmingen). Antibodies
25 were incubated with the cells for 30 min at 4C in the dark, under gently agitation. Cells were washed by centrifugation procedures and then resuspended in 0.3 mL of FacsFlow buffer (Becton Dickinson) with 0.5% formaldehyde (Polysciences). Expression of cell surface ICAM-1 was then
30 determined by flow cytometry using a Becton Dickinson FACScan. Percentage of the control ICAM-1 expression was calculated as follows: [(oligonucleotide-treated ICAM-1 value) - (basal ICAM-1 value)/(non-treated ICAM-1 value) - (basal ICAM-1 value)]. (Baker, Brenda, et. al. 2'-O-(2-

Methoxy)ethyl-modified Anti-intercellular Adhesion Molecule 1 (ICAM-1) Oligonucleotides Selectively Increase the ICAM-1 mRNA Level and Inhibit Formation of the ICAM-1 Translation Initiation Complex in Human Umbilical Vein Endothelial Cells, *The Journal of Biological Chemistry*, 272, 11994-12000, 1997.)

ICAM-1 expression of chimeric C3'-endo and C2'-endo modified oligonucleotides of the invention is measured by the reduction of ICAM-1 levels in treated HUVEC cells. The oligonucleotides are believed to work by RNase H cleavage mechanism. Appropriate scrambled control oligonucleotides are used as controls. They have the same base composition as the test sequence.

Sequences that contain the chimeric C3'-endo (2'-MOE) and C2'-endo (one of the following modifications: 2'-S-Me, 2'-Me, 2'-ara-F, 2'-ara-OH, 2'-ara-O-Me) as listed in Table X below are prepared and tested in the above assay. SEQ ID NO: 43, a C-raf targeted oligonucleotide, is used as a control.

20

Table X

**Oligonucleotides Containing chimeric
2'-O-(2-methoxyethyl) and 2'-S-(methyl) modifications.**

SEQ ID NO:	Sequence (5'-3')	Target
43	AsTsGs C^msAsTs TsCs ^m Ts GsCs _m	mouse
25	Cs ^m Cs ^m C ^m s C^ms AsAsGs GsA	C-raf
44	GsC ^m sC ^m s C ^m sAsAs GsC ^m sTs	human
	GsGsC ^m s ASTsC^mS C^msGSTs	ICAM-1
	C ^m SA	

All nucleosides in bold are 2'-O-(methoxyethyl); subscript s indicates a phosphorothioate linkage; underlined nucleosides indicate

2'-S-Me- modification. superscript m on C (C^m) indicates a 5-methyl-C.

Table XI

Oligonucleotides Containing chimeric

5 2'-O-(2-methoxyethyl) and 2'-O-(methyl) modifications

	SEQ ID NO:	Sequence (5'-3')	Target
	43	AsTsGs C ^m sAsTs TsCs ^m Ts GsCs ^m Cs ^m Cs ^m C ^m sC ^m s AsAsGs GsA	mouse C-raf
10	44	GsC ^m sC ^m s C ^m sAsAs GsC ^m sTs GsGsC ^m s ASTsC ^m S C ^m sGSTs C ^m SA	human ICAM-1

All nucleosides in bold are 2'-O-(methoxyethyl);
subscript s indicates a phosphorothioate linkage;
15 underlined nucleosides indicate 2'-Methyl modification.
Superscript m on C (C^m) indicates a 5-methyl-C.

Table XII

Oligonucleotides Containing chimeric

2'-O-(2-methoxyethyl) and 2'-ara-(fluoro) modifications

	SEQ ID NO:	Sequence (5'-3')	Target
20	43	AsTsGs C ^m sAsTs TsCs ^m Ts GsCs ^m Cs ^m Cs ^m C ^m sC ^m s AsAsGs GsA	mouse C-raf
25	44	GsC ^m sC ^m s C ^m sAsAs GsC ^m sTs GsGsC ^m s ASTsC ^m S C ^m sGSTs C ^m SA	human ICAM-1

All nucleosides in bold are 2'-O-(methoxyethyl);
subscript s indicates a phosphorothioate linkage;
underlined nucleosides indicate 2'-ara-(fluoro)
30 modification. superscript m on C (C^m) indicates a
5-methyl-C.

Table XIII
Oligonucleotides Containing chimeric
2'-O-(2-methoxyethyl) and 2'-ara-(OH) modifications

	SEQ ID NO:	Sequence (5'-3')	Target
5	43	AsTsGs C ^m sAsTs TsCs ^m Ts GsCs ^m Cs ^m Cs ^m C ^m sC ^m s AsAsGs GsA	mouse C-raf
10	44	GsC ^m sC ^m s C ^m sAsAs GsC ^m sTs GsGsC ^m s ASTsC ^m S C ^m sGSTs C ^m SA	human ICAM-1

All nucleosides in bold are 2'-O-(methoxyethyl); subscript s indicates a phosphorothioate linkage; underlined nucleosides indicate 2'-ara-(OH) modification. superscript m on C (C^m) indicates a 5-methyl-C.

15 **Table XIV**
Oligonucleotides Containing chimeric
2'-O-(2-methoxyethyl) and 2'-ara-(OMe) modifications

	SEQ ID NO:	Sequence (5'-3')	Target
20	43	AsTsGs C ^m sAsTs TsCs ^m Ts GsCs ^m Cs ^m Cs ^m C ^m sC ^m s AsAsGs GsA	mouse C-raf
	44	GsC ^m sC ^m s C ^m sAsAs GsC ^m sTs GsGsC ^m s ASTsC ^m S C ^m sGSTs C ^m SA-3'	human ICAM-1

25 All nucleosides in bold are 2'-O-(methoxyethyl); subscript S indicates a phosphorothioate linkage; underlined nucleosides indicate 2'-ara-(OMe) modification. superscript m on C (C^m) indicates a 5-methyl-C.

PROCEDURE 2

30 **Enzymatic Degradation of 2'-O-modified oligonucleotides**

Three oligonucleotides are synthesized incorporating the modifications shown in Table 2 below at

the 3'-end. These modified oligonucleotides are subjected to snake venom phosphodiesterase action.

Oligonucleotides (30 nanomoles) are dissolved in 20 mL of buffer containing 50 mM Tris-HCl pH 8.5, 14 mM MgCl₂, and 72 mM NaCl. To this solution 0.1 units of snake-venom phosphodiesterase (Pharmacia, Piscataway, NJ), 23 units of nuclease P1 (Gibco LBRL, Gaithersburg, MD), and 24 units of calf intestinal phosphatase (Boehringer Mannheim, Indianapolis, IN) are added and the reaction mixture is incubated at 37C for 100 hours. HPLC analysis is carried out using a Waters model 715 automatic injector, model 600E pump, model 991 detector, and an Alltech (Alltech Associates, Inc., Deerfield, IL) nucleoside/nucleotide column (4.6 x 250 mm). All analyses are performed at room temperature. The solvents used are A: water and B: acetonitrile. Analysis of the nucleoside composition is accomplished with the following gradient: 0-5 min., 2% B (isocratic); 5-20 min., 2% B to 10% B (linear); 20-40 min., 10% B to 50% B. The integrated area per nanomole is determined using nucleoside standards. Relative nucleoside ratios are calculated by converting integrated areas to molar values and comparing all values to thymidine, which is set at its expected value for each oligomer.

Table XV

Relative Nuclease Resistance of 2'-Modified
Chimeric Oligonucleotides

5'-TTT TTT TTT TTT TTT T*T*T*T*-3' SEQ ID NO 45
(Uniform phosphodiester)

T* = 2'-modified T

-S-Me

-Me

-2'-ara-(F)

-2'-ara-(OH)

-2'-ara-(OMe)

PROCEDURE 3**General procedure for the evaluation of chimeric C3'-endo and C2'-endo modified oligonucleotides targeted to *Ha-ras***

Different types of human tumors, including sarcomas, neuroblastomas, leukemias and lymphomas, contain active oncogenes of the *ras* gene family. *Ha-ras* is a family of small molecular weight GTPases whose function is to regulate cellular proliferation and differentiation by transmitting signals resulting in constitutive activation of *ras* are associated with a high percentage of diverse human cancers. Thus, *ras* represents an attractive target for anticancer therapeutic strategies.

SEQ ID NO: 46 is a 20-base phosphorothioate oligodeoxynucleotide targeting the initiation of translation region of human *Ha-ras* and it is a potent isotype-specific inhibitor of *Ha-ras* in cell culture based on screening assays ($IC_{50}=45$ nm). Treatment of cells *in vitro* with SEQ ID NO: 46 results in a rapid reduction of *Ha-ras* mRNA and protein synthesis and inhibition of proliferation of cells containing an activating *Ha-ras* mutation. When administered at doses of 25 mg/kg or lower by daily intraperitoneal injection (IP), SEQ ID NO: 46 exhibits potent antitumor activity in a variety of tumor xenograft models, whereas mismatch controls do not display antitumor activity. SEQ ID NO: 46 has been shown to be active against a variety of tumor types, including lung, breast, bladder, and pancreas in mouse xenograft studies (Cowser, L.M. *Anti-cancer drug design*, 1997, 12, 359-371). A second-generation analog of SEQ ID NO: 46, where the 5' and 3' termini ("wings") of the sequence are modified with 2'-methoxyethyl (MOE) modification and the backbone is kept as phosphorothioate (Table XV, SEQ ID NO: 52), exhibits IC_{50} of 15 nm in cell culture assays. thus, a 3-fold improvement in efficacy is observed from this chimeric

analog. Because of the improved nuclease resistance of the 2'-MOE phosphorothioate, SEQ ID NO: 52 increases the duration of antisense effect *in vitro*. This will relate to frequency of administration of this drug to cancer

5 patients. SEQ ID NO: 52 is currently under evaluation in *ras* dependent tumor models (Cowser, L.M. *Anti-cancer drug design*, 1997, 12, 359-371). The parent compound, SEQ ID NO: 46, is in Phase I clinical trials against solid tumors by systemic infusion.

10 Antisense oligonucleotides having the 2'-Me modification are prepared and tested in the aforementioned assays in the manner described to determine activity.

Ha-*ras* Antisense Oligonucleotides With chimeric C3'-endo and C2'-endo modifications and Their
15 Controls.

Table XV

Ha-*ras* Antisense Oligonucleotides With chimeric C3'-endo and C2'-endo modifications and Their Controls.

	SEQ	Sequence ID NO:	Backbone	2'-Modif.	Comments
20					
	46	5'-TsCsCs GsTsCs AsTsCs GsCsTs CsCsTs CsAsGs GsG-3'	P=S	2'-H	parent
25	47	5'-TsCsAs GsTsAs AsTsAs GsGsCs CsCsAs CsAsTs GsG-3'	P=S	2'-H	mismatch control
	48	5'-ToToCo <u>GsTsCs</u> <u>AsTsCs</u> <u>GsCsTs</u> CoCoTo CoAoGo GoG-3'	P=O/P=S/ P=O	2'-O-Moe in wings	Parent Gapmer (Mixed Backbone)
30					
	49	5'-TsCsCs <u>GsTsCs</u> <u>AsTsCs</u> <u>GsCsTs</u> CsCsTs CsAsGs GsG-3'	P=S	2'-O-MOE in wings	Parent Gapmer as uniform thioate
35	50	5'-ToCoAo <u>GsTsAs</u> <u>AsTsAs</u> <u>GsCsCs</u> <u>GsCsCs</u> <u>GsCoCo</u> CoCoAo CoAoTo GoG-3'	P=O/P=S/ P=O	2'-O-MOE in wings	Parent Gapmer (mixed

					Backbone,
	51	5'-TsCsAs <u>GsTsAs</u> <u>AsTs</u> <u>As</u> <u>GsCsCs</u> GsCsCs CsCsAs CsAsTs GsC-3'	P=S	2'-O-MOE in wings	Control Gapmer as uniform Thioate
5					
	52	5'-TsCsCs <u>GsTsCs</u> <u>AsTsCs</u> <u>GsCsTs</u> CsCsTs CsAsGs GsG-3'	P=S	2'-O-MOE in wings	Control Gapmer with MOE control
10	53	5'-TsCsAs <u>GsTsAs</u> <u>AsTsAs</u> <u>GsCsCs</u> GsCsCs CsCsAs CsAsTs GsC-3'	P=S	2'-O-MOE in wings	Control Gapmer with MOE control

All underlined portions of sequences are 2'-Me.

15 PROCEDURE 7

In vivo nuclease resistance

The *in vivo* Nuclease Resistance of chimeric C3'-endo and C2'-endo modified oligonucleotides is studied in mouse plasma and tissues (kidney and liver). For this purpose, 20 the C-raf oligonucleotide series SEQ ID NO: 54 are used and the following five oligonucleotides listed in the Table below will be evaluated for their relative nuclease resistance.

Table XVI

25 **Study of *in vivo* Nuclease Resistance of chimeric C3'-endo (2'-O-MOE) and C2'-endo (2'-S-Me) modified oligonucleotides with and without nuclease resistant caps (2'-5'-phosphate or phosphorothioate linkage with 3'-O-MOE in cap ends).**

30	SEQ	Sequence	Backbone	Description
	ID			
	NO:			
35	54	5'-ATG CAT TCT GCC CCA AGGA-3'	P=S, 2'-H	(control) rodent C-raf antisense oligo

55	AoToGo CoAsTs TsCsTs GsCsCs	P=O/P=S/P=O	2'-MOE/2'-S-Me/
	CsCsAo AoGoGo A		2'-MOE
5	56 AsTsGs CsAsTs TsCsTs GsCsCs	P=S	2'-MOE/2'-S-Me/
	CsCsAs AsGsGs A		2'-MOE
57	Ao*ToGo CoAsTs TsCsTs GsCsCs	P=O/P=S/P=O	In asterisk,
10	CsCsAo AoGoGo *A		2'-5'
			linkage with
			3'-O-MOE; 2'-O-MOE
			/
			2'-S-Me/2'-O-
15			MOE/2'-5' linkage
			with 3'-O-MOE in
			asterisk;
58	As*TsGs CsAsTs TsCsTs GsCsCs	P=S	In asterisk,
	CsCsAs AsGsGs *A		2'-5'
20			linkage with
	3'-O-MOE; 2'-O-MOE/		
	2'-S-Me/2'-O-		
25			MOE/2'-5' linkage
			with 3'-O-MOE in
			asterisk.

Table XVII

Study of in vivo Nuclease Resistance of chimeric C3'-endo (2'-O-MOE) and C2'-endo (2'-Me) modified oligonucleotides with and without nuclease resistant caps (2'-5'-phosphate or phosphorothioate linkage with 3'-O-MOE in cap ends).

SEQ ID NO:	Sequence	Backbone	Description
35	54 5'-ATG CAT TCT GCC CCA AGGA-3'	P=S, 2'-H	(control) rodent C-raf antisense oligo
40	55 AoToGo CoAsTs TsCsTs GsCsCs CsCsAo AoGoGo A'	P=O/P=S/P=O	2'-MOE/2'-Me/2'-MOE
	56 AsTsGs CsAsTs TsCsTs GsCsCs CsCsAs AsGsGs A	P=S	2'-MOE/2'-Me/2'-MOE
45	57 Ao*ToGo CoAsTs TsCsTs GsCsCs CsCsAo AoGoGo *A	P=O/P=S/P=O	In asterisk, 2'-5' linkage with

	3'-O-MOE;2'-O-MOE/	2'-Me/2'-O-MOE/2'-5' linkage with 3'-O-MOE in asterisk;
5		
	58 As*TsGs CsAsTs TsCsTs GsCsCs P=S	In asterisk, 2'-5'
10	CsCsAs AsGsGs *A	linkage with
15	3'-O-MOE;2'-O-MOE/ 2'-Me/2'-O-	MOE/2'-5' linkage with 3'-O-MOE in asterisk;

Table XVIII

Study of in vivo Nuclease Resistance of chimeric C3'-endo (2'-O-MOE) and C2'-endo (2'-ara-F) modified oligonucleotides with and without nuclease resistant caps (2'-5'-phosphate or phosphorothioate linkage with 3'-O-MOE in cap ends).

SEQ	ID	Sequence	Backbone	Description
25	NO:			
	54	5'-ATG CAT TCT GCC CCA AGGA-3'	P=S, 2'-H	(control) rodent C-raf antisense oligo
30	55	AoToGo CoAsTs TsCsTs GsCsCs CsCsAo AoGoGo A	P=O/P=S/P=O	2'-MOE/2'-ara-F/ 2'-MOE
35	56	AsTsGs CsAsTs TsCsTs CsCsAs GsCsCs AsGsGs A	P=S	2'-MOE/2'-ara-F/ 2'-MOE
40	57	Ao*ToGo CoAsTs TsCsTs GsCsCs CsCsAo AoGoGo *A	P=O/P=S/P=O	In asterisk, 2'-5' linkage with 3'-O-MOE;2'-O-MOE / 2'-ara-F/2'-O-MOE/2'-5' linkage with 3'-O-MOE in asterisk;
45	58	As*TsGs CsAsTs TsCsTs GsCsCs CsCsAs AsGsGs *A	P=S	In asterisk, 2'-5' linkage with 3'-O-MOE;2'-O-MO

2'-ara-F/2'-O-
MOE/2'-5' linkage
with 3'-O-MOE in
asterisk;

5

Table XIX

Study of in vivo Nuclease Resistance of chimeric
C3'-endo (2'-O-MOE) and C2'-endo (2'-ara-OH) modified
oligonucleotides with and without nuclease resistant caps
(2'-5'-phosphate or phosphorothioate linkage
with 3'-O-MOE in cap ends).

10

SEQ ID NO:	Sequence	Backbone	Description
15 54	5'-ATG CAT TCT GCC CCA AGGA-3'	P=S, 2'-H	(control) rodent C-raf antisense oligo
20 55	AoToGo CoAsTs TsCsTs GsCsCs CsCsAo AoGoGo A	P=O/P=S/P=O	2'-MOE/2'-ara-OH/ 2'-MOE
56	AsTsGs CsAsTs TsCsTs GsCsCs CsCsAs AsGsGs A	P=S	2'-MOE/2'-ara-OH/ 2'-MOE
25 57	Ao*ToGo CoAsTs TsCsTs GsCsCs CsCsAo AoGoGo *A	P=O/P=S/P=O	In asterisk, 2'-5' linkage with
30	3'-O-MOE;2'-O-MOE/ 2'-ara-OH/2'-O-		2'-ara-OH /2'-O- MOE/2'-5' linkage with 3'-O-MOE in asterisk;
35 58	As*TsGs CsAsTs TsCsTs GsCsCs CsCsAs AsGsGs *A	P=S	In asterisk, 2'-5' linkage with
40	3'-O-MOE;2'-O-MOE/ 2'-ara-OH/2'-O-		MOE/2'-5' linkage with 3'-O-MOE in asterisk;

Table XX

Study of in vivo Nuclease Resistance of chimeric C3'-endo
(2'-O-MOE) and C2'-endo (2'-ara-OMe) modified
oligonucleotides with and without nuclease resistant caps
5 (2'-5'-phosphate or phosphorothioate linkage
with 3'-O-MOE in cap ends).

SEQ ID NO:	Sequence	Backbone	Description
10 54	5'-ATG CAT TCT GCC CCA AGG A-3'	P=S, 2'-H	(control) rodent C-raf antisense oligo
55	AoToGo CoAsTs TsCsTs GsCsCs	P=O/P=S/P=O	2'-MOE/2'-ara-OMe /
15 CsCsAo AoGoGo Aa			2'-MOE
56	AsTsGs CsAsTs TsCsTs GsCsCs	P=S	2'-MOE/2'-ara-OMe
CsCsAs AsGsGs A			/2'-MOE
20 57	Ao*ToGo CoAsTs TsCsTs GsCsCs	P=O/P=S/P=O	In asterisk, 2'-5'
CsCsAo AoGoGo *A			linkage with 3'-O-MOE; 2'-O-MOE /
25			2'-ara-OMe/2'-O- MOE/2'-5' linkage with 3'-O-MOE in asterisk;
30 58	As*TsGs CsAsTs TsCsTs GsCsCs	P=S	In asterisk, 2'-5'
CsCsAs AsGsGs *A			linkage with 3'-O-MOE; 2'-O-MOE /
35			2'-ara-OMe/2'-O- MOE/2'-5' linkage with 3'-O-MOE in asterisk.

40 PROCEDURE 8

Animal studies for in vivo nuclease resistance

For each oligonucleotide to be studied, 9 male BALB/c
mice (Charles River, Wilmington, MA), weighing about 25 g
are used (Crooke et al., *J. Pharmacol. Exp. Ther.*, 1996,
45 277, 923). Following a 1-week acclimation, the mice

receive a single tail vein injection of oligonucleotide (5 mg/kg) administered in phosphate buffered saline (PBS), pH 7.0. The final concentration of oligonucleotide in the dosing solution is (5 mg/kg) for the PBS formulations. One retro-orbital bleed (either 0.25, 9.05, 2 or 4 post dose) and a terminal bleed (either 1, 3, 8 or 24 h post dose) is collected from each group. The terminal bleed (approximately 0.6-0.8 mL) is collected by cardiac puncture following ketamine/xylazine anesthesia. The blood is transferred to an EDTA-coated collection tube and centrifuged to obtain plasma. At termination, the liver and kidneys will be collected from each mouse. Plasma and tissues homogenates will be used for analysis for determination of intact oligonucleotide content by CGE. All samples are immediately frozen on dry ice after collection and stored at -80C until analysis.

PROCEDURE 9

RNase H studies with chimeric C3'-endo and C2'-endo modified oligonucleotides with and without nuclease resistant caps

³²P Labeling of Oligonucleotides

The oligoribonucleotide (sense strand) was 5'-end labeled with ³²P using [³²P]ATP, T4 polynucleotide kinase, and standard procedures (Ausubel, F. M., Brent, R., Kingston, R. E., Moore, D. D., Seidman, J. G., Smith, J. A., and Struhl, K., in *Current Protocols in Molecular Biology*, John Wiley, New York (1989)). The labeled RNA was purified by electrophoresis on 12% denaturing PAGE (Sambrook, J., Frisch, E. F., and Maniatis, T., *Molecular Cloning: A Laboratory Manual*, Cold Spring Harbor Laboratory Press, Plainview (1989)). The specific activity of the labeled oligonucleotide was approximately 6000

cpm/fmol.

Determination of RNase H Cleavage Patterns

Hybridization reactions were prepared in 120 μ L of reaction buffer [20 mM Tris-HC (pH 7.5), 20 mM KCl, 10 mM
5 MgCl₂, 0.1 mM DTT] containing 750 nM antisense oligonucleotide, 500 nM sense oligoribonucleotide, and 100,000 cpm ³²P-labeled sense oligoribonucleotide. Reactions were heated at 90 °C for 5 min and 1 unit of Inhibit-ACE was added. Samples were incubated overnight at
10 37 °C degrees. Hybridization reactions were incubated at 37 °C with 1.5 x 10⁻⁸ mg of *E. coli* RNase H enzyme for initial rate determinations and then quenched at specific time points. Samples were analyzed by trichloroacetic acid (TCA) assay or by denaturing polyacrylamide gel
15 electrophoresis as previously described [Crooke, S. T., Lemonidis, K. M., Neilson, L., Griffey, R., Lesnik, E. A., and Monia, B. P., Kinetic characteristics of *Escherichia coli* RNase H1: cleavage of various antisense oligonucleotide-RNA duplexes, *Biochem J*, 312, 599 (1995);
20 Lima, W.F. and Crooke, S. T., *Biochemistry* 36, 390-398, 1997].

Those skilled in the art will appreciate that numerous changes and modifications can be made to the preferred embodiments of the invention and that such changes and
25 modifications can be made without departing from the spirit of the invention. It is therefore intended that the appended claims cover all such equivalent variations as fall within the true spirit and scope of the invention.